

TYPICAL CROSS-SECTION OF SWALE

NOTE: LOWEST LAYER OF TENSAR GEOGRID TO BE RUN THROUGH BELOW ALL DRAINAGE RUNS. THIS WILL INVOLVE SOME ADDITIONAL LOCAL EXCAVATIONS SEE DRG. NO. AA4814/EW/10A

SURFACE WATER STRATEGY

1. All roof water to be positively collected and discharged to Balancing Pond and/or Eastern Swale.
2. All hardstanding drainage to be positively collected.
3. Area around building to be drained to channels at face of kerb on outer side of circulatory road. Channels to discharge to pipework below road. Water will pass through a Full Retention Oil Separator and then outfall to Balancing Pond and/or Eastern Swale. Penstock protection shall be provided to contain any spillages from entering the swale.
4. Surface water flow to be attenuated in swales. Swales to be unlined and will act as bio retention / bio remediation areas.
5. Discharge from swales to be via Hydrobrakes to restrict discharge rate to existing ditches to total of 35 litres / second maximum.

FOUL WATER STRATEGY:

1. Domestic foul connections from offices in plant and freestanding offices to be discharged to underground storage tank.
2. Underground storage tank to be pumped out weekly and tankered to disposal off site.



PROCESS WATER STRATEGY:

1. Process water to be pumped from sumps at drainage channels within Process Building, Argent North Building and Boiler Room, to Wastewater Storage Tank, then discharged for treatment to Phase 1.
2. Rainwater from Tank Bund to be drained to sumps. Water quality to be monitored: water to be pumped into surface water system, provided that the required standard is met. In the event of spillages, the sump will be pumped for treatment to the Wastewater Storage Tank, then to Phase 1.
3. Tanker loading/unloading station to be drained to surface water. Interlocking valves to be provided so that the surface water drainage connection is shut off during loading operation.
4. Blow down water from Boiler Room and transformer bund drainage to be gravitated to pumping station west of bund, then pumped over bridge to Phase 1.

ITEMS IN ABEYANCE / TO BE CONFIRMED

1. DETAILED SPECIFICATION FOR CHEMICAL RESISTANT PIPEWORK.
2. DETAILED SPECIFICATION FOR VALVES.

EXISTING SITE FIRE WATER STORAGE TANKS



- NOTES.**
1. DO NOT SCALE FROM THIS DRAWING.
 2. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 3. ALL MATERIALS AND WORKMANSHIP ARE TO BE IN ACCORDANCE WITH "SEWERS FOR SCOTLAND" 3rd EDITION (2015).
 4. FOUL AND SURFACE WATER SEWER PIPES AND PIPE FITTINGS ARE TO BE VITRIFIED CLAY TO BS EN 285 OR PLASTIC HARLEY QUANTUM SYSTEM OR EQUIVALENT TO ALW WATER APPROVAL. PLASTIC TO BE USED UP TO 300mm x. PIPES LARGER THAN THIS WILL BE VITRIFIED CLAY OR CONCRETE.
 5. PIPES ARE TO BE BEDDED AND SURROUNDED (150mm) WITH 10mm SINGLE SIZED PEA GRAVEL OTHER THAN WHERE COVER IS LESS THAN 300mm. A MINIMUM OF 150mm CONCRETE SURROUNDING IS TO BE PROVIDED (VITRIFIED CLAY) OR A REINFORCED CONCRETE SLAB WHICH BRIGGS THE TRENCH IS TO BE PROVIDED (PLASTIC OPTION).
 6. ALL GULLY CONNECTIONS ARE TO BE 150mm DIAMETER AND INSTALLED TO A MINIMUM GRADIENT OF 1:150.
 7. ALL MANHOLE COVERS AND FRAMES ARE TO BE DUCTILE IRON TO EN 1224-1994 WITH A 675 x 675 mm CLEAR OPENING. FOR STANDARD MANHOLE DETAILS SEE DRG NO. AA4814/EW/08 & 09.
 8. THE INVERT LEVELS OF THE EXISTING DITCHES AT CONNECTION POINTS ARE TO BE CHECKED ON SITE PRIOR TO COMMENCING CONSTRUCTION, AND ANY DISCREPANCIES FROM LEVELS GIVEN ON ATTACHED SCHEDULES ARE TO BE REPORTED TO THE ENGINEER IMMEDIATELY.

KEY: EXISTING

EXISTING SERVICES	
STREET LIGHTING CABLE	SL
EXISTING STREET LIGHT	S
SURFACE WATER SEWER	SW
FOUL SEWER	F
PROCESS WATER SEWER	PW
COMBINED SEWER	C
BT OVERHEAD	OT
BT UNDERGROUND	UT
WATER MAIN	W
GAS MAIN	G
ELECTRICITY	E
ELECTRICITY (OVERHEAD)	EO
EXISTING LEVEL	12.304

PROPOSED EXTERNAL LEVELS - 5.75
 PROPOSED INTERNAL LEVELS - 5.90

KEY: PROPOSED DRAINS

PROCESS WASTE WATER GRAVITY DRAIN (IN HATHENWARE THERMACHEM UNLESS OTHERWISE NOTED)	PW
PROCESS WATER PUMPED MAIN	P
FOUL DRAIN	F
FOUL PUMPING MAIN	PF
YARD WATER DRAIN	Y
YARD DRAIN WITH VALVE	YV
ROOF WATER DRAIN	R
MAN-HOLE	S1
CHANNEL DRAINAGE (SURFACE WATER) (FOR DETAILS SEE DRG. NO. AA4814/EW/14)	MG
CHANNEL DRAINAGE (EXTERNAL HIGH RISK AREA) (FOR DETAILS SEE DRG. NO. AA4814/EW/14)	MG
MEGA GULLY @ 600x750mm CATCHPI. (SEE DRG. AA4814/EW/13)	MG
GULLY	G
DOWNPIPE	DP
HIGH RISK AREAS	

Rev.	Amendment	By	Checked	Approved	Date
W	CONCRETE PROTECTION ADDED TO SWALES. TYPICAL SWALE CROSS-SECTION ADDED.				
V	PIENSTOCKS ALTERED. PIPE RUNS MH Y17-Y19, MH Y27-Y28, MH Y30-Y32, MH R6-Y31-Y32, MH Y25-Y26-Y27, MH Y24-Y25-Y34, MH Y31-Y34, & Y34-Y35-Y36 ALTERED. NOTES TO OIL SEPARATORS ALTERED.				
U	HYDROBRAKE SPECIFICATIONS AT EASTERN SWALE & BALANCING POND CORRECTED.				
T	PIPES PW1-PW3, R4-R5A, & Y23-Y24 DELETED. PIPE RUNS Y11-Y15, R1-R2, & PW4-WET WELL ALTERED. CHANNEL AT MH Y24 EXTENDED, CHANNEL AT MH Y11 ADDED. CHANNEL AT MH PW4 ALTERED. RADIUS KERB AT MH Y24 ALTERED. GULLY ADDED TO KEY. CHAMBER SET-UP AMENDED AT VALVE POSITIONS. ITEMS IN ABEYANCE UPDATED.				
S	CHANNEL WITH PLATING ADDED EXTERNAL TO BOILER ROOM. TANK BUND SINGLE UNLOADING STATION LENGTHENED. LOADING/UNLOADING STATIONS LENGTHENED TO 16.4 METRES. MEGA GULLIES ADDED TO CHANNELS IN LIEU OF SUMP GULLIES. VALVE AT Y26 SHIFTED TO Y25.				
R	LAYOUT UPDATED AS PER DRG. AA4814/EW/02W. MINOR ADJUSTMENTS TO PROCESS WATER PIPE POSITIONING AROUND THE TYCO FIREFIGHTING KIOSK AND THE FOUL PIPES AT OFFICES. Y23-Y24 SHIFTED NORTH AS A RESULT OF KERB SHIFT. HIGH RISK AREAS EXTENDED AROUND LOADING/UNLOADING STATIONS. SUMP CONNECTIONS FROM LOADING/UNLOADING STATIONS REMOVED. Y1 & Y14 DELETED. Y25 RELOCATED.				
Q	MINOR ADJUSTMENTS TO YARD WATER DRAINAGE LEVELS. POSITIONING OF DOWNPIPES ON BDI BUILDING ADJUSTED. DOWNPIPE REFERENCES ADDED. ITEM 5 IN ABEYANCE REMOVED. ALL TANK BUND SUMP PUMPS NOW DISCHARGING TO Y26.				

CONSTRUCTION

Client	Status	Appd.	Date
ARGENT ENERGY			

Project
 BIODIESEL FACILITY, PHASE 2
 OIL SITES ROAD,
 ELLESMERE PORT

Title
 EXTERNAL WORKS
 DRAINAGE LAYOUT

Drawn	Date	Checked	Date	Approved	Date
DO	11.09.15	KGA	11.09.15	KGA	11.09.15

Scale: 1:250 @ A0

asher ASSOCIATES
 CIVIL ENGINEERS
 STRUCTURAL ENGINEERS
 PROJECT MANAGERS

Job No. AA4814
 Client Drawing No. AA4814/EW/03
 Drawing No. AA4814/EW/03

NOTE: RUNS Y2-Y3-Y4-Y5: PIPE LIES (IN PART) BELOW EXISTING SITE FORMATION LEVEL. FORMATION TO BE DROPPED TO BELOW PIPE AND TENSAR GEOGRID RUN THROUGH BELOW PIPE