## **Environmental Management System**

Prepared on Behalf of: Keeble Container Services Ltd

Site Name:

**Paynes Lane** 

Nazeing

**Waltham Abbey** 

EN<sub>9</sub> 2EX

Environmental Permit Application Reference: EPR/LB3804LQ/A001

#### **DOCUMENT CONTROL SHEET**

Site:	Paynes Lane
Project:	Bespoke Permit Application
Title:	Environmental Management System
Issue:	1.0
Date:	27.06.23
Status:	Submission Version
Author	Shane Ronald Tasker AssocMCIWM PIEMA EA (IEMA Qualified Auditor)

# **Table of Contents**

1	Intr	oduction
	1.2	Interpretation
	1.3	General Management
	1.4	Implementation and Operation
	1.5	Sufficient Competent Management
	1.6	Checking & Corrective Action
	1.7	Site Infrastructure
2	Env	ironmental Legal Register
3	Оре	erations
	3.1	Specified Waste Management Operations
	3.2	Permitted Wastes6
	3.3	Waste Throughput
4	Оре	erational Flow Diagram
5	Wa	ste Acceptance Procedures
	5.3	Rejection Procedure10
	5.4	Fibrous Asbestos Procedure10
6	Sto	rage Procedures1
7	Des	patch Procedures1
8	Dut	y of Care12
	8.1	Reporting12
	8.2	Notification
	8.3	Avoidance, recovery and disposal of wastes produced by the activities1
	8.4	Site Security1
9	Trai	ning14
10	) <i>N</i>	laintenance1
	10.1	Daily Checks
	10.2	Weekly Checks1
	10.3	Annual Checks19
	10.4	Maintenance Checklist
12	2 Cor	tingency Planning1
13	ß Emi	ssions Management18
	13.2	Monitoring18
	13.3	Dust Emissions19
	13.4	Odour Emissions19

13.5	Noise & Vibration Emissions1	9
13.6	Noise1	9
13.7	Noise Control1	9
13.8	Noise Monitoring20	0
13.9	Scavenging Birds20	0
13.10	Pests20	0
13.11	Litter	.1
13.12	Mud & Debris Management Procedures 2	.1
14 lr	ncident Response Procedures & Instructions2	2
15 Em	ergency Procedures2	2
15.2	Environmental Incident Record Form Procedure2	2
16 C	omplaints2	2
16.2	Complaints Investigation Procedure2	3
17 Lea	kages or Spillages Procedure2	4
18 E	quipment & Machinery Malfunction & Failure Procedure2	5
19 N	Ion-Conformance Procedure2	5
20 P	eriodic Review2	5
Append	lix EMS1: Environmental Incident Record Form20	6
Append	lix EMS2: Complaint Record Form2	7
<u>Append</u>	lix EMS3: Non-Conformance Record Form2	8
Append	lix EMS4: Environment Agency Notification Form20	9
<u>Append</u>	lix EMS5: Accident Investigation Report Form3	0
Append	lix EMS6: Emissions Management Assessment Forms (Noise)3	2
<u>Append</u>	lix EMS7: Site Infrastructure Plan3	3

#### 1 Introduction

1.1.1 This Environmental Management System has been produced in accordance with Environment Agency Guidance 'Develop a management system: environmental permits' latest version.

Table 1: Develop a Management System & Environmental Management System Cross Reference

Develop a Management System Guidance Contents	Environmental Management System Sections
Site Infrastructure	Section 1.7
Site Operations	Sections 3/4/5/6/7
Site Equipment Maintenance Plan	Section 10
Contingency Plan	Section 11
Accident Prevention & Management Plan	Sections 12/13/14/15/16/17/18
Complaints Procedure	Section 15
Managing Staff Competence & Training Records	Sections 1.5 & 9
Keeping Records	Section 8
Review Your Management System	Section 19
Site Closure	Section 11

#### 1.2 Interpretation

1.2.1 'Member of the Management Team' means any person trained and responsible for monitoring and reporting as detailed in this EMS. This may be the responsible Director, Technically Competent Manager, the Site Management (if not the TCM and the Site Supervisor. It excludes general site staff unless they have specific training and responsibilities.

### 1.3 General Management

- 1.3.1 Activities will be operated and managed in accordance with this site-specific Environmental Management System (EMS) and the governing Environmental Permit, using sufficient competent persons and resources
- 1.3.2 All employees having duties that are or may be affected by the matters set out in this EMS will have access to a copy of this document and the governing permit.

  Documentation will be clearly labelled and displayed within the Site Office.

Site: Paynes Lane

Project: Bespoke Permit Application

#### 1.4 Implementation and Operation

- 1.4.1 Sufficient resources essential to the effective implementation and update of this EMS will be put in place and maintained. At least one Member of the Management Team is present when the site is operational.
- 1.4.2 Training needs have been identified so that all personnel whose work may contribute towards the safe and compliant operation of the site have received appropriate training.

#### 1.5 Sufficient Competent Management

- 1.5.1 Sufficient competent management will be maintained and the minimum TCM attendance requirements will be met. Attendance will be recorded in the Site Diary.
- 1.5.2 In the event that the designated TCM is absent for a period of time such that the minimum agreed attendance is unlikely to be achieved, a suitably qualified alternative will be secured.

#### 1.6 Checking & Corrective Action

1.6.1 A Member of the Management Team will be responsible for handling and investigating any incidents that may result in non-compliance with this EMS, taking action to mitigate any impacts caused and for initiating and completing corrective and preventive action. Any such action will be used to inform changes in the documented procedures.

#### 1.7 Site Infrastructure

Table 2: Site Infrastructure Provisions

Provisions	Description
Drainage	Sealed drainage to interceptor.
Site Perimeter	Enclosed site perimeter, with access via main entrance gate.

Site: Paynes Lane

Project: Bespoke Permit Application

# 2 Environmental Legal Register

<u>Table 3:</u> Environmental Legal Register (Not an exhaustive list of requirements)

Legislation Summary/Obligations Compliance Responsibl			Responsible
3	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Documentation	
		Location	
Environmental Permit	Overarching permit that	Copy of permit held	Member of the
	stipulates the conditions	within Office.	Management
	by which the site must	Compliance	Team
	be operated to.	documentation includes	
	'	an Environmental	
		Management System	
Waste Carriers Licence	Waste management	Copy of contractors'	Member of the
	companies moving	registrations held within	Management
	wastes must be	the Office.	Team
	registered as an 'upper		
	tier' waste carrier.		
Environmental	Overarching legislation	Copy of permit held	Member of the
Permitting Regulations	for waste management	within the Office.	Management
2016 (As Amended)	facilities (i.e.		Team
	requirement to have an		
	permit & to comply with		
	conditions).		
The Waste (England and	Overarching legislation	Compliance with the	Member of the
Wales) Regulations 2011	for the management	waste hierarchy is	Management
Waste Hierarchy (As	and handling of waste.	assured by the	Team
Amended)	Ensure waste is	procedures detailed	
	managed as far up the	within this	
	waste hierarchy as	Environmental	
	possible, evidence	Management System &	
	should be retained	Duty of Care	
	within the Company	documentation.	
	Office to support any		
	minor deviations.		
The Environmental	Overarching legislation	All Duty of Care waste	Member of the
Protection Act 1990:	for waste management	transfer notes are held	Management
Copies of all non-	activities. Duty of Care	in Office for two years.	Team
hazardous waste Duty	requirement for the		
of Care waste transfer	movement of all waste,		
notes must be kept	(not required for		
onsite for 2 years.	internal movements or		
	movements within the		
	same company). These		
	must be kept for two		
	years.		

Site: Paynes Lane

Project: Bespoke Permit Application

The Hazardous Waste	Overarching legislation	All Consignment Notes	Member of the
Regulations 2005:	for wastes that are	are kept for three years	Management
Hazardous Waste	classified as hazardous.	within the Office	Team
Consignment Notes	Hazardous waste must		
(Recommendation that	not be mixed with other		
the EA template for	hazardous waste or		
Consignment Notes is	non-hazardous wastes.		
used)	A Consignment Note		
	must accompany all		
	hazardous waste		
	movements; these must		
	be kept onsite for 3		
	years.		

Site: Paynes Lane

Project: Bespoke Permit Application

# **3 Operations**

## 3.1 Specified Waste Management Operations

3.1.1 Waste management operations authorised within the permitted area are listed in Table 4 below.

<u>Table 4: Specified Waste Management Operations</u>

Operational Codes	Activity
R13: Storage of wastes pending any of the	Physical treatment consisting only of the manual &
operations numbered R1 to R12.	mechanical sorting and separation of waste into different
R3: Recycling/reclamation of organic	components for disposal, (no more than 50 tonnes per day)
substances which are not used as solvents	or recovery.
R4: Recycling/reclamation of metals and	No more than 50 tonnes per day of non-hazardous waste to
metal compounds	be treated at the site under a D9 activity.
R5: Recycling/reclamation of other	
inorganic materials	All waste shall be stored and treated on an impermeable
D9 Physical/Physico Treatment	surface with sealed drainage system.
D14 Repackaging prior to submission to any	Specified wastes shall be stored and treated on a
of the operations numbered D1 to D13	hardstanding or on an impermeable surface with sealed
D15: Storage pending any of the operations	drainage system.
number D1 to D14.	
	Subject to any other requirements of this permit wastes shall
	be stored for no longer than 1 year prior to disposal or 3 years prior to recovery.

Site: Paynes Lane

Project: Bespoke Permit Application

## 3.2 Permitted Wastes

3.2.1 Primary waste types that will be received onsite are presented in <u>Table 5</u> below.

Table 5: Waste Types

15 WASTE PAC	KAGING; ABSORBENTS, WIPING CLOTHS, FILTER MATERIALS AND PROTECTIVE CLOTHING NOT OTHERWISE SPECIFIED
15 01	PACKAGING (INCLUDING SEPARATELY COLLECTED MUNICIPAL PACKAGING WASTE)
15 01 01	PAPER AND CARDBOARD PACKAGING
15 01 02	PLASTIC PACKAGING
15 01 03	WOODEN PACKAGING
15 01 04	METALLIC PACKAGING
15 01 05	COMPOSITE PACKAGING
15 01 06	MIXED PACKAGING
15 01 07	GLASS PACKAGING
15 01 09	TEXTILE PACKAGING
16 WASTES NO	OT OTHERWISE SPECIFIED IN THE LIST
16 02	WASTES FROM ELECTRICAL AND ELECTRONIC EQUIPMENT
16 02 14	DISCARDED EQUIPMENT OTHER THAN THOSE MENTIONED IN 16 02 09 TO 16 02 13
16 02 16	COMPONENETS REMOVED FROM DISCARDED EQUIPMENT OTHER THAN THOSE MENTIONED IN 16 02 15
16 06	BATTERIES AND AACUMULATORS
16 06 04	ALKALINE BATTERIES (EXCEPT 16 06 03)
16 06 05	OTHER BATTERIES AND ACCUMULATORS
	TION AND DEMOLITION WASTE (INCLUDING EXCAVATED SOIL FROM CONTAMINATED SITES)
17 01	CONCRETE, BRICKS, TILES AND CERAMICS
17 01 01	CONCRETE
17 01 02	BRICKS
17 01 03	TILES AND CERAMICS
17 01 07	MIXTURES OF CONCRETE, BRICKS, TILES AND CERAMICS OTHER THAN THOSE MENTIONED IN 17 01 06*
17 02	WOOD, GLASS AND PLASTIC
17 02 01	WOOD
17 02 02	GLASS   PLASTIC
17 02 03	BITUMINOUS MIXTURES, COAL TAR AND TARRED PRODUCTS
17 03	BITUMINOUS MIXTURES, COAL TAK AND TAKKED PRODUCTS  BITUMINOUS MIXTURES OTHER THAN THOSE MENTIONED IN 17 03 01
17 03 02 17 04	METALS (INCLUDING THEIR ALLOYS)
17 04 01	COPPER, BRONZE, BRASS
17 04 02	ALUMINIUM
17 04 03	LEAD
17 04 04	ZINC
17 04 05	IRON AND STEEL
17 04 06	TIN
17 04 07	MIXED METALS
17 04 11	CABLES OTHER THAN THOSE MNENTIONED IN 17 04 10
17 05	SOIL (INCLUDING EXCAVATED SOIL FROM CONTAMINATED SITES), STONES AND DREDGING SPOIL
17 05 04	SOIL AND STONE OTHER THAN THOSE MENTIONED IN 17 05 03
17 05 08	TRACK BALLAST OTHER THAN THOSE MENTIONED IN 17 05 07
17 06	INSULATION MATERIALS AND ASBESTOS-CONTAINING CONSTRUCTION MATERIALS
17 06 04	INSULATION MATERIALS OTHER THAN THOSE MENTIONED IN 17 06 01 AND 17 06 03
17 08	GYPSUM-BASED CONSTRUCTION MATERIAL
17 08 02	GYPSUM-BASED CONSTRUCTION MATERIALS OTHER THAN THOSE MENTIONED IN 17 08 01
17 09	OTHER CONSTRUCTION AND DEMOLITION WASTES
17 09 04	MIXED CONSTRUCTION AND DEMOLITION WASTES OTHER THAN THOSE MENTIONED IN 17 09 01, 1709 02 AND 17 09 03
	OM WASTE MANAGEMENT FACILITIES, OFF-SITE WASTEWATER TREATMENT PLANTS AND PREPARATION OF WATER
	R HUMAN CONSUMPTION/INDUSTRIAL USE
19 12	WASTES FROM THE MECHANICAL TREATMENT OF WASTE (FOR EXAMPLE SORTING, CRUSHING, COMPACTING, PELLETISING) NOT OTHERWISE SPECIFIED
19 12 01	PAPER AND CARDBOARD
19 12 02	FERROUS METAL
19 12 03	NON-FERROUS METAL
19 12 04	PLASTIC AND RUBBER
19 12 05	GLASS
19 12 07	WOOD OTHER THAN THAT MENTIONED IN 19 12 06
19 12 08	TEXTILES
19 12 09	AGGREGATE ONLY
19 12 10	COMBUSTIBLE WASTE (REFUSE DERIVED FUEL)

Site: Paynes Lane

Project: Bespoke Permit Application

19 12 12	OTHER WASTES (INCLUDING MIXTURES OF MATERIALS) FROM MECHANICAL TREATMENT OF WASTES OTHER THAN
	THOSE MENTIONED IN 19 12 11
19 13	WASTES FROM SOIL AND GROUNDWATER REMEDIATION
19 13 02	SOLID WASTES FROM SOIL REMEDIATION OTHER THAN THOSE MENTIONED IN 19 13 01
20 MUNICIPA	AL WASTE AND SIMILAR MATERIALS FROM COMMERCE AN INDUSTRY
20 01	SEPARATELY COLLECTED FRACTIONS (EXCEPT 15 01)
20 01 01	PAPER AND CARDBOARD
20 01 02	GLASS
20 01 08	BIODEGRADABLE KITCHEN AND CANTEEN WASTE
20 01 10	CLOTHES
20 01 11	TEXTILES
20 01 34	BATTERIES AND ACCUMULATORS OTHER THAN THOSE MENTIONED IN 20 01 33
20 01 36	DISCARDED ELECTRICAL AND ELECTRONIC EQUIPMENT OTHER THAN THOSE MENTIONED IN 20 01 21, 20 01 23 AND 20 01
	35
20 01 38	WOOD OTHER THAN THAT MENTIONED IN 20 01 37
20 01 39	PLASTIC
20 01 40	METALS
20 02	GARDEN AND PARK WASTES (INCLUDING CEMETERY WASTE)
20 02 01	BIODEGRADABLE WASTE
20 02 02	SOIL AND STONES
20 03	OTHER MUNICIPAL WASTES
20 03 01	MIXED MUNICIPAL WASTE
20 03 07	BULKY WASTE

# 3.3 Waste Throughput

Table 6: Maximum Throughput

Waste Category	Annual Tonnage
To not exceed:	12,000 (Permitted)

Site: Paynes Lane

Project: Bespoke Permit Application

# 4 Operational Flow Diagram




Figure 1: Permitting Operational Flow Diagram

Site: Paynes Lane

Project: Bespoke Permit Application

### **5 Waste Acceptance Procedures**

- 5.1.1 Compliance with the permitted waste types is assured by the following measures:
  - Responsible Persons will ensure a clear description of the waste is ascertained prior to arranging for the wastes to be delivered to site, if the wastes are not suitable they will be diverted to another waste management facility able to manage these waste streams;
  - 2. On delivery to site the driver will hand all paper copies of any Duty of Care Documentation to the Site Office; and
  - 3. Once all Duty of Care Documentation has been approved the wastes will be deposited in the Waste Acceptance Area for inspection, acceptance & processing (machine operatives will spread out the loads to aid the visual inspection process).
- 5.1.2 If any prohibited materials are present the following course of action will be taken:
  - a) Require the individual to load the non-permitted materials back onto the delivery vehicle; or
  - b) Accept, isolate & arrange for removal to an authorised waste management facility.
  - c) Under no circumstances will non-permitted wastes be retained onsite and dealt with as if it is permitted.
  - d) The Agency will be notified if a delivery is rejected.
- 5.1.3 If the prohibited material becomes apparent only after the above waste acceptance checks have been completed the following action will be taken:
  - a) The load will be isolated within the isolation facility (appropriate PPE will be warn if necessary) and removed from site to a suitably permitted facility at the earliest opportunity.
  - b) In each case, the incident will be recorded in the Site Diary (taking note of the vehicle registration, date & time of the incident).
  - c) Under no circumstances will prohibited waste be retained onsite and dealt with as if it is permitted.
  - d) The Agency will be notified if a delivery is rejected.

Site: Paynes Lane

Project: Bespoke Permit Application

#### 5.3 Rejection Procedure

- 5.3.1 Any wastes identified as being unsuitable for disposal at the site will be rejected & recorded in the Site Diary.
- 5.3.2 A record will be kept of the following pieces of information:
  - a) Date & time
  - b) Person rejecting the waste(s)
  - c) Haulier/customer name and address including carriers number
  - d) Vehicle registration number
  - e) Procedure name and address
  - f) EWC number
  - g) Transfer Note Number
  - h) Waste Description

#### 5.4 Fibrous Asbestos Procedure

- 5.4.1 If asbestos is detected the following procedures will be followed:
  - I. Isolate, if safe to do so while using appropriate PPE.
  - II. Dampen down utilising water provisions to prevent fibres/particulates being released.
  - III. Contact a specialist contractor to isolate/remove asbestos from site immediately.
  - IV. In the event of fibre release, the site will be evacuated until a specialist contractor has dealt with the risk. The Environment Agency and the Environmental Health Officer will be notified immediately.
  - V. Notify Regulatory Authorities when the asbestos has been removed offsite and the site has recommenced operations.
  - VI. Complete a Non-Conformance Record Form and an Accident & Incident Investigation Report.
  - VII. Provide written confirmation of the event and outcome to the Agency within 24 hours, completing from in <u>Appendix EMS4</u>.
  - VIII. Details of all such incidents will be recorded in the Site Diary and records of removals are kept within the site office. In each case a record of the incident will be noted including time, description and carrier.

Site: Paynes Lane

Project: Bespoke Permit Application

### **6 Storage Procedures**

6.1.1 Wastes are stored within designated bays/containers/areas until sufficient quantities have accumulated to represent a load requiring removal; removals are undertaken on an ongoing basis.

## **7 Despatch Procedures**

- 1. Wastes stored within bays/containers/areas will be placed within the despatch vehicle using mechanical equipment.
- 2. Containers will be loaded directly onto the collection vehicle.
- 3. Once loaded the vehicle sheeted for despatch.
- 4. All drivers will inspect their loads prior to leaving the site to prevent spillages of waste or debris on the entrance and exit roads of the site.

Site: Paynes Lane

Project: Bespoke Permit Application

## 8 Duty of Care

London Borough of Hillingdon takes its responsibilities seriously under Duty of Care & understands them to require it to:

- 1. Check the authorised status of all waste carriers utilised;
- 2. Wastes are going to a suitably authorised facility;
- 3. Complete compliance status checks from time to time;
- 4. Produce & maintain appropriate records relating to wastes received and removed.

#### 8.1 Reporting

8.1.1 Within one month of the end of each quarter, all information relating to wastes accepted & removed from the site must be submitted to the Environment Agency for the previous quarter.

#### 8.2 Notification

- 8.2.1 Notify the Environment Agency without delay in the event of detecting any of the following:
  - 1. Any malfunction, breakdown or failure of equipment or techniques, accident or emission of a substance not controlled by an emissions limit which has caused, is causing or may cause significant pollution;
  - 2. The breach of a limit specified in the permit;
  - 3. Any significant adverse environmental effects.
- 8.2.2 The Environment Agency will be notified without delay with written confirmation (i.e. an email & telephone conversation with the local Enforcement Officer) of such incidents, which must be submitted within 24 hours.
- 8.2.3 The Environment Agency will be notified at least one month prior to any changes in the actual conduct of the operation from those proposed in the Environmental Management System.
- 8.2.4 The Environment Agency will be notified within 14 days of the occurrence of the following matters except where such disclosure is prohibited by Stock Exchange Rules.

Where the operator is a registered company:

- Any change in the operator's trading name, registered name or registered office address; and
- Any steps taken with a view to the operator going into administration, entering into a company voluntary arrangement or being wound up.

Site: Paynes Lane

Project: Bespoke Permit Application

#### 8.3 Avoidance, recovery and disposal of wastes produced by the activities

- 8.3.1 The requirements laid down by The Waste Regulations 2011 will be complied with as far as possible and in particular:
  - a) Waste managed by the activities; and
  - b) All waste generated by operations conducted onsite will be dealt with in accordance with the waste hierarchy; and
  - c) If disposal is necessary, a manner will be selected which reduces the potential impact on the environment
- 8.3.2 All wastes generated will be quantified & characterised using appropriate competence.
- 8.3.3 Any hierarchy deviations will be justified and recorded.
- 8.3.4 Every three years all arrangements & practices around the management of wastes will be reviewed. Steps identified by such a review will be implemented as necessary & deemed appropriate to operational compliance.

#### 8.4 Site Security

- 8.4.1 Security arrangements include an enclosed site perimeter with a main access gate. CCTV cameras are in operation 24-hours a day. Outside operational hours the site access gates are shut and securely locked.
- 8.4.2 Security arrangements are inspected on a weekly basis. Any necessary repairs are recorded in the Site Diary & will be completed as soon as possible to maintain the sites perimeter, which may result in interim repairs until an external contractor can attend site.
- 8.4.3 The Management Team constantly evaluates all onsite security arrangements.

Site: Paynes Lane

Project: Bespoke Permit Application

## 9 Training

- 9.1.1 New employees' will receive an induction upon commencement of employment, which will involve a Member of the Management Team completing a training needs assessment to ensure all new employees have the required training to complete their day-to-day tasks correctly & safely.
- 9.1.2 Training is tailored depending on an employee's specific needs/ role within the Company; these needs are presented within the <u>Table 7</u> below.
- 9.1.3 Training records are held within the Office.
- 9.1.4 Employees' receive refreshers trainings on all internally provided training as required.
- 9.1.5 External companies provide specialist training to onsite employees as and when it is required with appropriate refreshers as determined by the external trainers.

<u>Table 7:</u> Training Matrix (Training Needs Assessment Example not an exhaustive list)

Training Requirements		Management Team	Admin Staff	Operatives	External Contractors
La La constitución de	Environmental Management System				
Internal Training	Procedures				
('Tool Box Talks')	Emissions Management Procedures				
	Mechanical Equipment				
Externally	First Aider				
Completed Training	Fire Marshall				
	Fire Awareness				



Site: Paynes Lane

Project: Bespoke Permit Application

#### 10 Maintenance

#### 10.1 Daily Checks

- 10.1.1 Operatives will inspect all mechanical equipment on a daily basis prior to the commencement of operations.
- 10.1.2 Defects are raised with a Member of the Management Team & recorded as appropriate.
- 10.1.3 If repairs cannot be completed onsite an appropriate external contractor (dependent on the type of malfunction) will be contacted to affect a repair.

### 10.2 Weekly Checks

- 10.2.1 A Member of the Management Team will undertake a thorough inspection of all critical site infrastructure & equipment on a weekly basis.
- 10.2.2 Repairs will be recorded in the Site Diary where appropriate. If a repair cannot be completed onsite then the faulty item will be isolated and arrangements made for repairs to be effected as soon as practicable.

#### 10.3 Annual Checks

- 10.3.1 Mechanical equipment as defined under the LOLER Regulations will have CTE inspections completed on a yearly basis & all equipment will undergo the manufacturers' or suppliers' recommended frequency for servicing.
- 10.3.2 Routine mechanical maintenance is scheduled against the records kept in the Office. These records determine the frequency by which inspections take place.
- 10.3.3 All records will be kept in the Office.

Site: Paynes Lane

Project: Bespoke Permit Application

## 10.4 Maintenance Checklist

<u>Table 8:</u> Maintenance Checklist (Recommendations)

	Frequency					
Maintenance	Day	Week	Month	Year	5 years	Location of Instructions
		Inter	nal			
Clean up Spills on Surfaced Areas.	0					Office
Inspect Integrity Of Site Security Perimeter	0					Office
Inspect Integrity & State Of Site Surfaces/Access Road	0					Office
Clean Site Surfaces To Prevent 'Track-Out'.	0					Office
Inspect Storage Areas/Bays/Containers	0		М			Office
Inspect Electrical Equipment		М				Office
Inspect Fire Fighting Equipment			М			Office
Inspect Mechanical Equipment	0	М				Office
		Exter	nal			
Operational Fleet (Servicing/Mot)				E		Office
Mechanical Equipment (Loler)				E		Office
Fire Extinguishers				E		Office
Electrical Wiring					E	Office

<u>Key</u>	
Management Team	М
Operative	0
External Contractor	E

Site: Paynes Lane

Project: Bespoke Permit Application

# 12 Contingency Planning

<u>Table 9:</u> Contingency Measures

Eventuality	Procedures/Measures		
Accident	Measures may include: -		
	1. The affected area will be isolated and an appointed 'first aider' will be contacted to attend to any		
	injured party.		
	2. If necessary the emergency services will be contacted.		
	3. A Member of the Management Team will decide on a case-by-case basis if cessation of operations		
	around the affected area and reception of waste is necessary until the appropriate emergency		
	services have arrived.		
	4. A Member of the Management Team will complete an Accident Investigation Report (RIDDOR).		
Seasonality	Measures could include: -		
(Including	1. Confirm current storage times for materials accumulated onsite.		
Transportation	2. Contact outlets for the specified stream and arrange transportation.		
Shortages)	3. Transport all waste accumulated within a designated container, even if it may be economically		
	undesirable to do so, i.e. the container for transportation is not full.		
Supply Chain	Measures could include: -		
Failure	1. Confirm current storage times for materials accumulated onsite.		
(Including	2. Increase monitoring of material stockpiles onsite.		
Transportation	3. Contact outlets for the specified stream and arrange transportation.		
Shortages)	4. If the outlet is not receiving the specified waste stream contact other outlets.		
	5. Conduct investigations into potential alternative outlets, if potential outlets are not accepting		
	specified streams.		
	6. Seek advice from EA.		
Breakdowns	Measures could include: -		
(Mechanical	1. Immediate isolation of the affected machinery.		
Equipment)	2. External repair/servicing contractors are instructed to effect repair.		
	3. Mechanical equipment on the adjacent site will be deployed in interim if available & deemed		
	necessary.		
	4. Hire in relief equipment in interim if needed.		
	5. Suspend the acceptance of wastes that require handling by mechanical equipment & notify the		
	EA.		
	6. Reschedule material despatched to align with scheduled repairs and or relief machinery		
	availability.		
Enforced Shut	Measures could include: -		
Down & Site	1. Appropriate signage will be erected notifying any visitors that operations have been suspended.		
Closure	2. Advise customers of the situation.		
	3. No more wastes will be accepted on to site.		
	4. Contact all potential outlets to ensure that all waste material is managed in accordance with the		
	waste hierarchy where possible.		
	5. Notify EA that customers & receiving outlets have been contacted and provide scheduled dates		
	for material removal.		
	6. Notify EA once stockpiles have been reduced to acceptable level		

Site: Paynes Lane

Project: Bespoke Permit Application

## 13 Emissions Management

- 13.1.1 Control of emissions of substances not controlled by emission limits as follows:
  - 'Emissions of substance not controlled by emissions limits (excluding odour) shall not cause pollution. The operator shall not be taken to have breached this rule if appropriate measures, including, but not limited to, those specified in any approved emissions management plan, have been taken to prevent or where that is not practicable, to minimise, those emissions'.
- 13.1.2 This section of the site EMS addresses any potential emissions that may arise from site operations. It demonstrates the measures taken to prevent or minimise the release of emissions such that they do not cause pollution:

"Pollution" means emissions as a result of human activity, which may: -

- (a) Be harmful to human health or the quality of the environment,
- (b) Cause offence to a human sense,
- (c) Result in damage to material property, or
- (d) Impair or interfere with amenities and other legitimate use of the environment.

#### 13.2 Monitoring

- 13.2.1 Employees will remain mindful of the potential impact the operation could have on the local environment and take all reasonable steps to avoid giving rise to pollution or a nuisance as a consequence of the site operations.
- 13.2.2 In the event of on going issues or concerns being identified these will be investigated and appropriate actions implemented. This may include the formulation of management plans.
- 13.2.3 In the event of an emissions release that has caused, is causing or may cause significant pollution, the Environment Agency will be notified within 24 hours (complete form in <u>Appendix EMS4</u>), advice taken and action recorded.

Site: Paynes Lane

Project: Bespoke Permit Application

#### 13.3 Dust Emissions

13.3.1 Revert to the Dust Emissions Management Plan for onsite controls & procedures with regards to this emissions type.

#### 13.4 Odour Emissions

13.4.1 Revert to the Odour Emissions Management Plan for onsite controls & procedures with regards to this emissions type.

#### 13.5 Noise & Vibration Emissions

- 13.5.1 The overall noise emissions amenity impact is considered to be low, due to the isolated nature of the operation & on site controls/procedures.
- 13.5.2 Noise generated on the site would principally be associated with the operation of mechanical equipment.
- 13.5.3 Maintenance inspections are carried out on all equipment and machinery.

  Any malfunctions or defects are therefore identified at the earliest opportunity.

#### 13.6 Noise

13.6.1 The overall noise emissions amenity impact is considered to be low, due to the nature of adjacent operations & onsite controls/procedures.

#### 13.7 Noise Control

13.7.1 The procedure for deploying the Noise & Vibration suppression system is as follows:

#### **Proactive**

- 1. Check site conditions for Noise & Vibration potential risks;
- 2. Remedial measures put I place to minimise if not eliminate the source; and
- 3. Be prepared to suspend operations giving rise to excessive Noise & Vibration.

#### Reactive

- 1. In the event of Noise & Vibration emissions being amber or red (as detailed within <u>Table 10</u>) enact the following procedures;
- 2. Remedial measures put in place to minimise if not eliminate the source;
- 3. Cease all onsite activities (if emissions escaping the site boundary) until conditions improve;
- 4. Once Noise & Vibration levels reduce, record the incident on a Noise & Vibration Assessment Form in (<u>Appendix EMS6</u>), the file for which is located within the site office; and

Site: Paynes Lane

Project: Bespoke Permit Application

5. Report incident to the Management or Supervisor for further investigation.

Table 10: Noise & Vibration Management Action Levels

Action	Operation	Onsite Procedures
Level	Conditions	
	Normal	No mitigation required, but ongoing monitoring by all staff
	Operating	members.
	Conditions	Daily inspections undertaken by a member of the site
		management team
	Noise &	Ongoing monitoring by all staff members.
	Vibration	Daily inspections undertaken by a member of the site
	emissions arising	management team
	from within the	
	operation	
	Noise &	Remedial measures put in place to minimise if not eliminate the
	Vibration	source.
	emissions	Cease operations giving rise to Noise & Vibration emissions if
	escaping the site	deemed necessary by Management.
	boundary.	Complete a Noise & Vibration Assessment (Appendix EMS6) &
		Complete an Environmental Incident Report ( <u>Appendix EMS2</u> ).

#### 13.8 Noise Monitoring

- 13.8.1 Operatives & Member of the Management Teams will monitor noise levels on an ongoing basis throughout the working day.
- 13.8.2 Observations will be recorded in the Site Diary (as required).

#### 13.9 Scavenging Birds

- 13.9.1 It is not expected that scavenging birds will present any significant problems as the site will not be accepting any putrescible or food wastes.
- 13.9.2 Operatives & Members of the Management Teams will monitor conditions on an ongoing basis throughout the working day. Observations will be recorded in the Site Diary.

#### 13.10 Pests

- 13.10.1 The risk of infestation of pests and vermin is minimised by maintaining general good housekeeping and ensuring that the site is clean and tidy.
- 13.10.2 Operatives & Member of the Management Teams will monitor site conditions of any signs of pest infestation.
- 13.10.3 In the event that flies, or other such problematic insects are introduced to the site with incoming waste, insecticides offering rapid and long-term treatment will be utilised and the offending waste promptly removed from site.

Site: Paynes Lane

Project: Bespoke Permit Application

#### 13.11 Litter

- 13.11.1 The overall impact is consider low due to onsite control measures including netting & palisade fencing deployed along the perimeter of the site.
- 13.11.2 Operatives conduct litter inspections on a daily basis.
- 13.11.3 Any escape of litter will be controlled throughout the working day & cleared immediately on identification
- 13.11.4 Operatives complete a final inspection around the site perimeter at the end of the working day and removal of any fugitive material/debris, access road and operational areas at the end of the working day.

#### 13.12 Mud & Debris Management Procedures

- 1. Operatives conduct regular inspections throughout the working day.
- 2. Debris/mud created by waste material stockpiles is to be returned to the pile.
- 3. On identification the area will be cleared:
  - a. Reaction time: Public highway immediately i.e. within 1 hour of detection and within the permitted boundary as soon as practicably possible by the end of the working day.
- 4. All vehicles leaving the site to be sheeted to prevent any material/debris falling out during transportation.

Site: Paynes Lane

Project: Bespoke Permit Application

## **14 Incident Response Procedures & Instructions**

### **15 Emergency Procedures**

15.1.1 The following procedure applies to All Emergencies:

- 1. A Member of the Management Team will take immediate control of any incident pending handover to the appropriate authority (if currently onsite).
- 2. Gather as much information as possible, including names & addresses of any bystanders & take photos as evidence if possible.
- 3. Appropriate personal protective equipment is to be used at all times (PPE is located within the Company Office).
- 4. Complete an Environmental Incident Record form as shown in <u>Appendix</u> EMS1.

#### 15.2 Environmental Incident Record Form Procedure

- 1. Complete Environmental Incident Record Form as detailed within Appendix EMS1 in the event of any accident/incident with potential environmental implications.
- 2. Pass completed form to a Member of the Management Team for investigation.
- 3. Once investigations are complete any corrective action recommended.
- 4. A copy of any completed forms is held within the Office once actioned for at least three years.

## 16 Complaints

- 16.1.1 In order that any complaints can be substantiated it is imperative that the site is immediately informed either by the complainant themselves or by the Environment Agency or Local Authority.
- 16.1.2 The site telephone number is clearly displayed at the site entrance and local residents are encouraged to immediately contact the site in the event of any off-site issues that might be attributable to site operations being detected.

Site: Paynes Lane

Project: Bespoke Permit Application

#### 16.2 Complaints Investigation Procedure

- 1. Complete a Complaints Record Form (only trained operatives authorised).
- 2. Once completed, the form must be passed onto the Company Director.
- 3. An investigation in undertaken by the Company Director to determine presence/absence, characteristic and intensity of issue. The time of the complaint will be linked with site activities. Review the Site Diary to determine if any abnormal site operations/conditions were at the time of the complaint.
- 4. The Company Director will determine the appropriate action necessary to remedy/mitigate the causes of the identified complaint.
- 5. Specialist advice will be sort if deemed necessary.
- 6. Complete an Environment Incident Record Form (<u>Appendix EMS1</u>) if deemed necessary.
- 7. Any actions taken will be recorded
- 8. Send copy of the completed form (<u>Appendix EMS4</u>) to the Environment Agency Permitting Officer within 24 hours of detection.
- 9. All complaint forms will be available for inspection by representatives of regulatory bodies.
- 16.2.1 All complaint forms will be available for inspection by representatives of regulatory bodies.

Site: Paynes Lane

Project: Bespoke Permit Application

### 17 Leakages or Spillages Procedure

- 17.1.1 On identification of a **Leak or Spillage** the following procedure is to be followed to:
  - 1. Prevent unauthorised access to the affected area
  - 2. Prevent uncontrolled escape of potentially contaminating liquids using supply of absorbent materials to control the flow of liquids.
  - 3. If safe to do so, isolate source of leak/spillage to prevent further losses, which may involve switching off a particular piece of machinery & deploying a containment vessel (i.e. drip trays) underneath the affected area.
  - 4. If necessary initiate controlled evacuation of the site.
  - 5. If the leak/spillage is battery acid, apply a neutralising agent hydrated lime or similar (please note that water in a large quantity will only dilute the acidity & will not neutralise it) on the affected areas (Operatives must use appropriate PPE; gloves, face masks & goggles, whilst handling hydrated limes).
  - 6. All contaminated absorbents, must be placed in a leak proof container, which is labelled & stored pending removal.
  - 7. Seek specialist advice on decontamination of the site surfaces if necessary
  - 8. Complete an Environmental Incident Record Form (See Appendix EMS1)
  - 9. Any actions taken will be recorded in the Site Diary
  - 10. Send copy of the completed form (<u>Appendix EMS4</u>) to the Environment Agency Permitting Officer within 24 hours of detection.
  - 11. Confirm site clean up with the Environment Agency.
  - 12. Replenish supplies of absorbent materials.

Site: Paynes Lane

Project: Bespoke Permit Application

## 18 Equipment & Machinery Malfunction & Failure Procedure

- 18.1.1 On identification of any **Equipment or Machinery Malfunctions or Failures** the following procedure is to be followed to:
  - 1. Cease operations immediately & determine if continuation of use poses a significant risk to health or the environment.
  - 2. If continuation poses a significant risk, switch the piece of equipment off & isolate the affected equipment.
  - 3. Notify a Member of the Management Team who will instruct the appropriate maintenance personnel or external contractor to undertake necessary repairs.
  - 4. Notify Environment Agency Permitting Officer if the malfunction or failure could cause pollutants to escape the permitted boundary.
  - 5. Complete an Environmental Incident Record Form. (See <u>Appendix</u> <u>EMS1</u>)
  - 6. Any actions taken will be recorded in the Site Diary.
  - 7. Send copy of the completed form (<u>Appendix EMS4</u>) to the Environment Agency Permitting Officer within 24 hours of detection.

#### 19 Non-Conformance Procedure

- 1. Non-conformance identified.
- A Non-Conformance Record form is completed (see <u>Appendix EMS3</u>) and passed to a Member of the Management Team
- 3. The Member of the Management Team initiates an investigation of the non-conformance & then ascertains potential impacts on the environment and how serious any potential effects could be.
- 4. Once the non-conformance has been assessed, action will be taken to remedy the cause.
- 5. All actions will be recorded.
- 6. In the event of an emissions release that has caused, is causing or may cause significant pollution, the Environment Agency will be notified within 24 hours, advice taken and actions taken will be recorded in the Site Diary.
- 7. Send copy of the completed form (<u>Appendix EMS4</u>) to the Environment Agency Permitting Officer within 24 hours of detection.

#### 20 Periodic Review

20.1.1 The adequacy of this EMS will be review as necessary as a result of any operational change or in light of any non-conformance.

Site: Paynes Lane

Project: Bespoke Permit Application

# **Appendix EMS1:** Environmental Incident Record Form

Date & time of the incident			
What happened, what was it about?			
Was anyone else aware of this – other witnesses?	If so who?		
What caused it?			
What have you done to make sure that it does not happen again?			
Was there any <b>significant pollution</b> or <b>environmental damage</b> to land, water or protected areas – for example: dust, odour or noise pollution outside the site or spillage of polluting liquids onto the ground, or at a site of special scientific interest, or into a drain or a watercourse? (If so, then complete an incident form)			
Is there a continuing threat? Yes/No			
If there was (or still is), then you must take steps to prevent further damage and notify the Environment Agency on 0800 807 060 and any other relevant regulators ASAP. Have you done so? Yes / No	Who did you phone?  At what time did you phone?		
You must also write or send an email to confirm this to the local office (see your accident management plan for the address) Have you done so?	Yes/No What date did you contact?		
Please print your name, date and sign:			

Site: Paynes Lane

Project: Bespoke Permit Application

# **Appendix EMS2:** Complaint Record Form

Who made the complaint? Name:				
Address				
Phone No				
Date and time they made the complaint				
What happened, what was it about?				
Was anyone else aware of this – other neighbours or your staff? If so who?				
Did the complaint relate to your site? If so, what happened? What went wrong?				
What have you done to make sure that it does not I	nappen again?			
Was there any <b>significant pollution</b> or <b>environmental damage</b> to land, water or protected areas – for example: dust, odour or noise pollution outside the site or spillage of polluting liquids onto the ground, or at a site of special scientific interest, or into a drain or a watercourse? (If so, then complete an incident form)				
If there was, then you must take steps to prevent further damage and notify the Environment Agency on 0800 807 060 and any other relevant regulators ASAP. Have you done so? Yes / No	Who did you phone?  At what time did you phone?			
You must also write or send an email to confirm this to the local office (see your accident management plan for the address) Have you done so?	Yes/No What date did you contact?			
Please print your name, date and sign:				

Site: Paynes Lane

Project: Bespoke Permit Application

# **Appendix EMS3:** Non-Conformance Record Form

Date and time non-conformance identified			
What happened, what was it about and	I what permit condition does it relate to?		
What caused it? i.e. what happened tha happen that should have?	t should not have happened OR what didn't		
What has been done to make sure that	it does not happen again?		
Has the site EMS been reviewed in light of the incident and have any changes to operations and procedures been rolled out in response? Include dates.			
Was there any significant pollution – fo what?	r example: oil entering a surface water drain. If so		
If there was then you must notify the	Yes/No/not applicable		
Environment Agency on o8oo 8o7o6o ASAP. Have you done so?	Time:		
	Date:		
	EA. Incident number:		
Print name, date and sign			

Site: Paynes Lane

Project: Bespoke Permit Application

# **Appendix EMS4:** Environment Agency Notification Form

#### Part A

(a) Notification requirements for any malfunction, breakdown or failure of equipment or		
techniques, accident, or emission of a substance not controlled by an emission limit which		
has caused, is causing or may cause significant pollution		
To be notified within 24 hours of detection		
Date and time of the event		
Reference or description of the location of		
the event		
Description of where any release into the		
environment took place		
Substance(s) potentially released		
Best estimate of the quantity or rate of		
release of substances		
Measures taken, or intended to be taken, to		
stop any emission		
Description of the failure or accident		

(b) Notification requirements for the detection of any significant adverse environmental		
effect		
To be notified within 24 hours of detection		
Description of where the effect on the		
environment was detected		
Substance(s) detected		
Concentrations of substances detected		
Date of monitoring/sampling		

#### Part B-to be submitted as soon as practicable

Any further accurate information on the	
matters for notification under Part A	
Measures taken, or intended to be taken,	
to prevent a recurrence of the incident	
Measures taken, or intended to be taken,	
to rectify, limit or prevent any pollution of	
the environment which has been or may be	
caused by the emission	
The dates of any unauthorised emissions	
from the facility in the preceding 24 months	
Name*	
Post	
Signature	
Date	

<sup>\*</sup>Authorised to sign on behalf of operator

Site: Paynes Lane

Project: Bespoke Permit Application

# **Appendix EMS5:** Accident Investigation Report Form

#### **Site Details:**

Date of Accident:	Time:
Site of Accident:	Site Manager/Supervisor at Time of Event:

## The injured person (If required)

Name of Injured Person:	Date of Birth or Age:		
Nature of Injuries:	Part of Body Injured (Tick as		
	Appropriate)		
	Hands, Wrists, Finger		
	Feet, Ankles, Toes		
	Legs, Knees, Hip, Thigh		
	Eyes		
	Head, Face, Neck		
	Torso		
	Back, Spine		
First Aid Treatment:	First Aid Treatment:		
Hospital Treatment & Contact Address/Telephone:			
Follow Up Treatment (If Any)			

<b>Details of Accident</b>	(Please Detail	Location	Onsite)	):
----------------------------	----------------	----------	---------	----

Site: Paynes Lane

Project: Bespoke Permit Application

#### For Office Use Only:

Time Off Work (Seven Days RIDDOR):					
Recorded in Accident Log Book: Y/N	Accident Log Book Number:				
RIDDOR Reportable: Y/N	RIDDOR Report Number:				
Further Investigation Required: Y/N					
Note: Use the accident log number for investigation.					
Distribution: Office/Site File/Client/Other (Please Specify)					

entered in other boxes:	
Print Name:	Date:

Continuation box for any additional information or information not able to be

POSITION:	Signature:

#### Instructions for reporting accidents:

Dacition.

All work in the immediate area with cease and the working area is to be made safe.

In the event of an accident the extent of the injuries will be immediately assessed by the first aider:

1. If the injuries sustained are of minor nature than the first aid provider will apply first aid to the injuries and make appropriate recommendations to the injured person

If the injuries sustained are of a significant or serious nature than the first aid provider will administer as much first aid that they are capable & comfortable to deliver & make the injured person as comfortable person as possible while the emergency services are contacted

Site: Paynes Lane

Project: Bespoke Permit Application


# <u>Appendix EMS6:</u> Emissions Management Assessment Forms (Noise)

		Noise	& Vibration As	sessment Form				
	AM		PM	Finish Time		AM		PM
Dry		Rain		Fog	Snow		Other	
Hot		Very Warm		Warm	Mild		Cold	
None		Light		Steady	Gusting		Strong	
North		NE		E	SE			
S		SW		W	NW			
o No Noise	1 Faint	2 Intermittent	3 Continuous					
& Vibration								
Present								
Point 1	Point 2	Point 3	Point 4	Point 5				
			1					
	Hot None North S o No Noise & Vibration Present Point 1	Dry Hot None North S O No Noise & Vibration Present Point 1 Point 2	Dry Rain  Hot Very Warm  None Light  North NE  S SW  O No Noise & Vibration Present  Point 1 Point 2 Point 3	AM PM  Dry Rain  Hot Very Warm  None Light  North NE  S SW  O No Noise & Vibration Present  Point 1 Point 2 Point 3 Point 4	Dry Rain Fog  Hot Very Warm Warm  None Light Steady  North NE E  S SW W  O No Noise & Vibration Present  Point 1 Point 2 Point 3 Point 4 Point 5	AM PM Finish Time  Dry Rain Fog Snow  Hot Very Warm Warm Mild  None Light Steady Gusting  North NE E SE  S SW W NW  O No Noise & Vibration Present  Point 1 Point 2 Point 3 Point 4 Point 5	AM PM Finish Time AM  Dry Rain Fog Snow Hot Very Warm Warm Mild  None Light Steady Gusting  North NE E SE  S SW W NW  O No Noise & Vibration Present  Point 1 Point 2 Point 3 Point 4 Point 5	AM         PM         Finish Time         AM           Dry         Rain         Fog         Snow         Other           Hot         Very Warm         Warm         Mild         Cold           None         Light         Steady         Gusting         Strong           North         NE         E         SE           S         SW         W         NW         NW           o No Noise & Vibration Present         1 Faint 2 Intermittent         3 Continuous 3 Continuous         W         NW         W           Point 1         Point 2         Point 3         Point 4         Point 5         W         NA

Site: Paynes Lane

Project: Bespoke Permit Application

# **Appendix EMS7:** Site Infrastructure Plan



Site: Paynes Lane

Project: Bespoke Permit Application