


- Key:**
- Site Boundary
  - Area of overlap of Phase 2 & 3 Earthworks
  - Existing ground level contours
  - Restoration contours
  - Contours in area of P2 and P3 overlap
  - Headland (Lowland Meadow Habitat) Buffer Zone
  - Headland (Neutral Grassland Habitat) Buffer Zone
  - Restored Agricultural Field
  - Retained existing trees
  - Devon Hedgebank
  - Permanent Drainage Swale
  - Temporary Drainage Ditch
  - Haul Route
  - Temporary Drainage Swale
  - Surface Water Feature
  - Topsoil Stockpile
  - Attenuation Pond
  - Culvert
  - DN450 Twinwall Pipe

- Notes:**
1. Total site area: 115,385 m<sup>2</sup>  
 Site area fully restored in Phase 2: 78,091 m<sup>2</sup>  
 Percentage of site fully restored in Phase 2: 67%
  2. Phase 2 volume of engineering fill / geological barrier: 23,260 cu m.
  3. Phase 2 volume of restoration soils: 13,180 cu m.
  4. Phase 2 volume of inert waste: 55,820 cu m.

Rev.	Details	Drawn Chkd.	Date
Project 213189 Lower Hare Farm			
Title Phase 2 Overview Landfill North Restoration			
		<b>AA Environmental Ltd</b> Units 4-8 Cholswell Court Shippon Abingdon Oxon OX13 6HX T: (01235) 536042 F: (01235) 523849 info@aae-ltd.co.uk www.aae-ltd.co.uk	
Scale 1:2,000@A3	Date Apr'22	Drawn KW	Chkd. ML
Drg. No. 213189/D/PH2/001B		Rev.	