

## Quotation

16<sup>th</sup> June, 2017

**Ref:** 121088

Mr Mark Broadhurst  
EMR Group  
Clarel Ave  
Landor St  
Birmingham  
B8 1AF

Dear Mark,

### **Re: 190,000Ltr Galvanised Steel Water Tank With Steel Roof, ladders and Platform**

Thank you for inviting me to look at your proposal for supplying a new Galvanised Steel tank at the B8 1AF Birmingham Site.

Following our conversation, I am pleased to submit my proposal below;

### **Objective**

To supply and install a 190,000L water tank to be used at the EMR Birmingham Site, Landor Street.

This includes the erection of the tank, Steel Cover and fitting of ladders and tank platform, The tank will also be on a bed of sand.

### **Scope Of Works**

- Remove any Sharps and debris from the area
- Lay the sand and evenly distribute for the tank to sit on
- Place liner in the centre of the concrete pad
- Construct the outer shell of the galvanised steel tank
- Bolt down the bottom sections securely to the floor
- Continue to bolt c sections of tank with the help of scaffolding to full height of tank
- Carefully place centre pole in the tank
- Begin to construct galvanised steel roof
- Distribute the liner evenly around head of the tank
- Secure and Fasten all rubber cappings
- Secure additional ball valve, gate valve and copper float
- Attach Ladders, Handrail and Platform
- Check over all areas of tank to make sure it is secure

## Storage Tank (7.31m x 4.5in Tank)



- Steel Kit For 24' x 15'0in Tank ( 190,000Ltr Tank )
- 24' x 15'0" H 1.00mm EPDM liner (7.32 x 4.57m)
- Galv Roof For 24' Dia Tank c/w B/V Hatch + Access Hatch (7.32M)
- Ball Valve HP 2in x 5/8inWW Bronze Seat
- Copper Float 12.00in x 5/8inWW
- Tank Bracket 2in B/Valve c/w Splash Plate
- 2x Tank Outlet 4" x 0.26Mtr MxM c/w 3 flgs+2 rubber gaskets+2 backnuts
- 2x Gate Valve 4.00in Brass Bodied FxF
- Tank Ladder Kit for 15'0" High Tank
- Tank Handrail Kit for 24ft (7.36m) Dia. Tank/Cover
- Ladder Platform Kit for 24ft Roof

**Supply Cost; £13,241.81+ Vat (Supply)**  
**Installation Cost; £7957.00 + Vat (Installation)**

### **Warranties**

Storage Tank and Liner 10 years

### **Installation**

Erection of tank, fitting of liner and Galvanised Steel cover, Tank ladders and platform.

### **Delivery and Off Loading**

Your system will be delivered to your premises by lorry or truck and trailer. An off load facility such as a forklift truck or telehandler will be required to lift the equipment off.

### **Disclaimers:**

This quote is subject to a site survey and has been priced on the assumption that the existing Concrete is flat, will not require a digger on site or construction of concrete pad.

### **What we require from you;**

Suitable 3 phase electricity supply

A plan showing any buried services such as water, electricity, gas, telecoms etc.

A clear site for work to commence.

A designated area for storage of plant and materials.

Confirmation that **NO** storm water will enter the designated work area

I hope this meets with your approval. If you do not understand any part of this quotation, or have any other queries please do not hesitate to contact me. Thank you once again for allowing me to quote for these works and I look forward to hearing from you in due course.

Yours sincerely

**Charlie Trenholme**

Charlie Trenholme (DD No. 0121 224 8304 or Mobile No. 07760677394)

**Cotterill Drainage Limited**

**Hermitage Farm, Wishaw, Sutton Coldfield, West Midlands, B76 9QJ**  
**Telephone: 0121 351 3230 Fax: 0121 351 3245**  
**Web: [www.cotterillcivils.co.uk](http://www.cotterillcivils.co.uk) Email: [enquiries@cotterillcivils.co.uk](mailto:enquiries@cotterillcivils.co.uk)**

**Registered in England No: 05214478**