

FICHTNER

Consulting Engineers Limited



**MedwayOne Energy
Hub**



Medway Energy Recovery Limited

Fire Prevention Plan

Document approval

	Name	Signature	Position	Date
Prepared by:	Michael Stevens		Project Engineer	14/03/2024
Checked by:	James Sturman		Lead Consultant	14/03/2024

Document revision record

Revision no	Date	Details of revisions	Prepared by	Checked by
0	18/11/2023	For Client	MS	JRS
1	03/01/2024	For approval	MS	JRS
2	17/01/2024	Updated following Client comments	MS	JRS
3	14/03/2024	For issue	MS	JRS

© 2024 Fichtner Consulting Engineers. All rights reserved.

This document and its accompanying documents contain information which is confidential and is intended only for the use of Medway Energy Recovery Limited. If you are not one of the intended recipients any disclosure, copying, distribution or action taken in reliance on the contents of the information is strictly prohibited.

Unless expressly agreed, any reproduction of material from this document must be requested and authorised in writing from Fichtner Consulting Engineers. Authorised reproduction of material must include all copyright and proprietary notices in the same form and manner as the original and must not be modified in any way. Acknowledgement of the source of the material must also be included in all references.

Contents

- 1 Introduction.....6
 - 1.1 Site location and description7
 - 1.1.1 Site address.....7
 - 1.2 Who this plan is for7
- 2 Types of combustible materials8
 - 2.1 Combustible waste.....8
- 3 Using this Fire Prevention Plan10
 - 3.1 Where the plan is kept and how staff know how to use it10
 - 3.2 Testing the plan and staff training10
 - 3.3 Roles and responsibilities.....11
- 4 Fire Prevention Plan contents12
 - 4.1 Activities at the site.....12
 - 4.2 Site plans and drawings13
 - 4.3 Plan of sensitive receptors near the site.....13
 - 4.4 Meteorological conditions14
- 5 Managing common causes of fire15
 - 5.1 Arson or Vandalism15
 - 5.2 Plant and equipment.....15
 - 5.3 Electrical faults including damaged or exposed electrical cables.....15
 - 5.4 Discarded smoking materials16
 - 5.5 Hot works safe working practices16
 - 5.6 Industrial heaters16
 - 5.7 Hot exhausts and engine parts17
 - 5.8 Ignition sources17
 - 5.9 Leaks and spillages of oils and fuels.....17
 - 5.10 Build-up of loose combustible waste, dust and fluff18
 - 5.11 Reactions between wastes18
 - 5.12 Deposited hot loads18
 - 5.13 Hot and dry weather19
- 6 Preventing self-combustion20
 - 6.1 General self-combustion measures20
 - 6.2 Managing storage time20
 - 6.2.1 Methods used to record and manage the storage of all waste on site.....20
 - 6.2.2 Stock rotation policy.....20
 - 6.3 Monitoring and control temperature20
 - 6.3.1 Monitoring and controlling temperature20
 - 6.3.2 Reducing exposed metal content and proportion of fines.....22
 - 6.3.3 Dealing with hot weather and heating from sunlight22
 - 6.3.4 Waste bale storage22
- 7 Manage waste piles.....23
 - 7.1 Storing waste materials in their largest form23

- 7.2 Maximum pile sizes23
- 7.3 Waste stored in containers23
- 8 Prevent fire spreading24**
 - 8.1 Separation distances24
 - 8.2 Fire walls construction standards24
 - 8.3 Storing waste in bays25
- 9 Quarantine areas.....26**
 - 9.1 Quarantine areas – location and size.....26
 - 9.2 How to use the quarantine areas if there is a fire26
 - 9.3 Procedures to remove material stored within the quarantine areas27
- 10 Detecting fires28**
 - 10.1 Detection systems in use28
- 11 Suppressing fires31**
 - 11.1 Suppression systems in use.....31
 - 11.1.1 Fire hose reel system31
 - 11.1.2 Fire hydrants and mains31
 - 11.1.3 Fire extinguishers.....32
 - 11.1.4 Additional suppression systems32
- 12 Certification for the systems33**
- 13 Firefighting techniques.....34**
 - 13.1 Active firefighting.....34
 - 13.2 Alternative fire detection and suppression measures34
- 14 Water supplies.....35**
- 15 Managing fire water36**
- 16 During and after an incident38**
 - 16.1 Dealing with issues during a fire38
 - 16.2 Notifying residents and businesses.....38
 - 16.3 Clearing and decontamination after a fire.....39
 - 16.4 Making the site operational after a fire39
- Appendices40**
 - A Plans and Drawings41
 - A.1 Site Location Plan41
 - A.2 Site Layout Plan.....41
 - A.3 Materials and Waste Storage Areas Plan.....41
 - A.4 Access Points Around the Perimeter to Assist Fire-Fighting.....41
 - A.5 Indicative Locations of Fire Hydrants.....41
 - A.6 Indicative Locations of Fire Walls.....41
 - A.7 Indicative location of quarantine area.....41
 - A.8 Fire Receptor Plan.....41
 - A.9 Areas of natural or unmade ground41
 - A.10 Indicative Firewater Storage and Containment41

B Wind roses from Gravesend Broadness meteorological station42

1 Introduction

Medway Energy Recovery Limited is applying to the Environment Agency (EA) under the Environmental Permitting Regulations (EPR's) for an Environmental Permit (EP) to operate the MedwayOne Energy Hub (the Facility). The Facility will comprise a twin line waste incineration plant and associated infrastructure (including battery storage), and will be located at MedwayOne, Kent. A detailed description of the Facility is presented within section 1.4 of the Supporting Information.

As the Facility will accept and store potentially combustible wastes, a Fire Prevention Plan (FPP) must be developed for its operation.

The objective of this report is to provide a preliminary FPP for the Facility and identify the provisions considered during the development phase of the Facility to prevent, detect, and mitigate against fire. In addition, provisional operational measures in relation to fire have been identified where these are available. This FPP will be subject to review and update following completion of detailed design of the Facility.

This FPP has been developed in accordance with Environment Agency guidance note: *Fire Prevention Plans: Environmental Permits* and the associated report template, as published on the UK government website. The requirements of the FPP will be integrated within the emergency plans and procedures for the Facility, to ensure that they are consistent and compatible with other management systems associated with the operation of the Facility.

This document and the measures to mitigate the risk and impact of fires within the Facility have been (and will continue to be) developed in accordance with the requirements of the following. It is also intended to share the FPP with the local fire and rescue service.

- Environment Agency guidance – '*Fire Prevention Plans: Environmental Permits*' (updated 11 January 2021);
- Building Regulations – '*Approved Document B (Fire Safety)*';
- National Fire Protection Association '*NFPA 850: Recommended Practice for Fire Protection for Electric Generating Plants and High Voltage Direct Current Converter Stations*'; and
- The insurer's requirements where structures or equipment fall outside published guidance or recommended practice.

The EA's Fire Prevention Plan guidance has been designed with 3 objectives in mind:

1. minimise the likelihood of a fire happening;
2. aim for a fire to be extinguished within 4 hours; and
3. minimise the spread of fire within the site and to neighbouring sites.

The Facility will meet these objectives as follows:

1. The use of suitable management procedures and fire detection systems will minimise the likelihood of a fire happening – refer to sections 6, 7 and 10.
2. Active firefighting measures will be implemented should a fire break out – refer to section 11, 13 and 14. Utilising these measures, the Facility aims to extinguish a fire within 4 hours.
3. Fire walls and other prevention methods will minimise the spread of fire within the site and to neighbouring sites – refer to section 8 and 9.

Utilising these measures, the Facility has been designed with the aim of extinguishing a fire within 4 hours.

1.1 Site location and description

The Site is located within the wider MedwayOne development which is being developed on the site for the former Kingsnorth Power Station. Access to the Site is via Eschol Road to the west.

The Site is located on the Hoo Peninsula in Medway, Kent, immediately south of the Damhead Creek CCGT power station. The Site is located approximately 4 km east of Hoo St Werburgh, and approximately 15km northeast of Chatham.

The Damhead Creek Gas-fired Power Station is located to the north of the site, with the Kingsnorth industrial estate lying to the northeast of the site. Damhead Creek runs to the east of the Site and connects with the estuary for the River Medway.

The MedwaOne site is a mix of brownfield and greenfield land on which the former Kingsnorth coal-fired power station was located prior to demolition, and has a varied topography. The plot which the Facility is being developed on has been subject to limited development and was farmland prior to it being developed as a sports field for the former Kingsnorth Power Station.

A site location plan and Installation Boundary drawing are presented in Appendix A.1 and A.2, respectively.

1.1.1 Site address

Medway Energy Hub
MedwayOne at Former Kingsnorth Power Station
Medway
Kent
ME3 9NQ

1.2 Who this plan is for

The Fire Prevention Plan will be easily accessible for all staff and will form part of the documented management systems for the site. People who will have access to the plan will include, but not be limited, to the following:

- site staff;
- fire officers; and
- contractors.

2 Types of combustible materials

2.1 Combustible waste

The Facility will be used to recover energy from waste, with European Waste Catalogue (EWC) Codes as presented in Table 1. The Facility will primarily accept refuse derived fuel (RDF) and solid recovered fuel (SRF), which typically have higher NCVs than non-treated waste.

Table 1: Waste to be processed in the Facility

EWC Code	Description of Waste
Waste packaging; absorbents, wiping cloths, filter materials and protective clothing not otherwise specified	
15 01	Packaging (including separately collected municipal packaging waste)
15 01 01	Paper and cardboard packaging which is contaminated and would otherwise be destined for landfill
15 01 03	Wooden packaging which is contaminated and would otherwise be destined for landfill
15 01 05	Composite packaging
15 01 06	Mixed packaging which is contaminated and would otherwise be destined for landfill
15 01 09	Textile packaging
Construction and demolition wastes (including excavated soil from contaminated sites)	
17 02	Wood, glass, and plastic
17 02 01	Wood which is contaminated and would otherwise be destined for landfill
Wastes from waste management facilities, off-site wastewater treatment plants and the preparation of water intended for human consumption and water for industrial use	
19 02	Wastes from physical/chemical treatments of waste (including dechromatation, decyanidation, neutralisation)
19 02 03	Premixed wastes composed only of non-hazardous wastes
19 05	Wastes from aerobic treatment of solid wastes
19 05 01	Non-composted fraction of municipal and similar wastes (which is otherwise contaminated or unsuitable for recycling)
19 05 02	Non-composted fraction of animal and vegetable waste (which is otherwise contaminated or unsuitable for recycling)
19 05 03	Off-specification compost (which is otherwise contaminated or unsuitable for recycling)
19 06	wastes from anaerobic treatment of waste
19 06 04	digestate from anaerobic treatment of municipal waste (which is otherwise contaminated or unsuitable for recycling)
19 06 06	digestate from anaerobic treatment of animal and vegetable waste (which is otherwise contaminated or unsuitable for recycling)
19 12	Wastes from the mechanical treatment of waste (for example sorting, crushing, compacting, pelletising) not otherwise specified

EWC Code	Description of Waste
19 12 01	Paper and cardboard which is contaminated and would otherwise be destined for landfill
19 12 07	Wood other than that mentioned in 19 12 06
19 12 08	Textiles
19 12 10	Combustible waste (refuse derived fuel)
19 12 12	Other wastes (including mixtures of materials) from mechanical treatment of wastes other than those mentioned in 19 12 11
Municipal wastes (household waste and similar commercial, industrial and institutional wastes) including separately collected fractions	
20 01	Separately collected fractions (except 15 01)
20 01 10	Clothes
20 01 11	Textiles
20 01 38	Wood other than that mentioned in 20 01 37 (rejects from materials recovery plants only)
20 02	Garden and park wastes (including cemetery waste)
20 02 01	Biodegradable waste (which is otherwise contaminated or unsuitable for recycling)
20 03	Other municipal wastes
20 03 01	Mixed municipal waste
20 03 02	Waste from markets

3 Using this Fire Prevention Plan

3.1 Where the plan is kept and how staff know how to use it

This FPP will form part of the documented management systems for the Facility. The FPP will be available in both electronic and hard copies at easily accessible locations. Staff induction programmes will be location and job role specific; however, they will include awareness training on the documented management systems at the site as a minimum. All staff will be able to easily access the documented management systems, including this FPP.

Visitors and contractors will be informed about fire prevention measures adopted at the Facility as part of site induction procedures and will be able to access the FPP if required. The FPP will also be made available to local Fire Officers. A Premises Information Box or similar at the gatehouse will be made available to the fire and rescue service which will contain a copy of the FPP, contact numbers and also information on control features such as shut-off valves, hydrant controls etc.

3.2 Testing the plan and staff training

All site staff (and contractors) will be trained in emergency response procedures. Operational staff will be trained in a range of firefighting equipment. Training records will be maintained in accordance with the documented management systems for the Facility, with fire response procedures incorporated within the site's management systems. It is expected that fire drills (including procedures for emergency evacuation of the site) will be exercised at least twice per year.

This FPP will be subject to regular review and updating by senior management following the commencement of operation of the Facility. The first review is expected to be undertaken during the commissioning phase of the waste processing activities prior to full operation, to incorporate any mitigation measures proposed during detailed design and construction of the Facility. The FPP will be periodically reviewed and updated where necessary to ensure that the stated control techniques remain appropriate. Scenarios for when the FPP will be periodically reviewed and updated, will include the following:

- immediately following any major fire incidents;
- following a near miss of a fire;
- if there are any significant technical or managerial changes at the Facility;
- the local environment changes, e.g., a school or residential development is built nearby; or
- if the EA asks for the FPP to be revised.

Regular reviews will be captured through both the FPP and any fire risk assessments as part of Medway's Energy Recovery Limited documented management systems.

Fire prevention messages will be reinforced around the site using signs. Furthermore, visitors to the Facility will be informed of the correct safety and fire prevention procedures – information will be provided at the site entrance and by appropriate located signage on-site.

On a periodic basis, testing of the emergency procedures will be undertaken. The intention of the testing is to verify that all staff and contractors are aware of the emergency procedures. Following all tests, the implementation of the procedures will be reviewed. If appropriate, the procedures will be amended, or additional training provided to all staff and contractors.

The effectiveness of the emergency response procedures will be reviewed following any emergency incidents on-site. The procedures will be updated if required, and staff trained in the updated procedures.

3.3 Roles and responsibilities

A Fire Safety Manager (FSM) will be assigned. The FSM will take overall responsibility for establishing and maintaining a safe working environment in which fires are prevented from starting, or if they do, from developing beyond a minor event. The FSM will be responsible with overseeing the production of fire risk assessments at the site and ensuring that any recommendations for improvements/mitigation measures from the assessments are addressed/implemented. Risk assessments will be reviewed on an annual basis. The FSM will also be responsible to ensure that the FPP is reviewed regularly and remains appropriate to the site.

In addition to the FSM, a sufficient number of fire wardens will be assigned to ensure a safe and timely evacuation in the event of a fire. The fire wardens will be suitably trained and competent to carry out the role, with any training recorded as part of the documented management systems. The fire wardens will undertake fire watch site inspections and raise alarm/activate call points if smoke, odour or flame indicates a potential fire source. They will be responsible for investigating the location of the fire (if safe to do so, i.e., if determined using an automatic detection system) and utilising fire suppression equipment such as fire extinguishers if deemed safe to do so. They will liaise with the FSM if they are not already present on the site.

All employees (and contractors) will have a number of additional responsibilities in relation to fire safety, which are set out as follows:

- never leave obstructions in corridors, stairways, stair landings or other escape routes;
- never block fire exits or place objects in front of fire doors;
- never leave open fire doors which are required to be kept shut to prevent fire spreading, and ensure these doors are closed behind them;
- never interfere with fire detection or suppression equipment unless authorised to do so;
- report any damages identified to fire detection or suppression equipment;
- maintain safe working practices with electrical equipment;
- do not smoke on site unless in an approved area;
- familiarise themselves with fire emergency procedures; and
- book in and out of the site using the correct systems in place.

4 Fire Prevention Plan contents

4.1 Activities at the site

The Facility will consist of a combination of Schedule 1 installation activities (as defined in the Environmental Permitting Regulations) (EPR) and directly associated activities. The site consists of an waste incineration process comprising two incineration lines to recover energy from waste, enabling:

1. generation of power for export to the National Grid and the potential to export heat;
2. production of an inert bottom ash material that will be transferred off-site to an IBA processing facility; and
3. generation of an air pollution control residue that will be transferred off-site to a suitably licensed hazardous waste facility for disposal or recovery.

The Schedule 1 activities (as defined in the Environmental Permitting Regulations), and the Directly Associated Activities (DAA's) which will be undertaken at the Facility are listed in Table 2.

Table 2: Scheduled and directly associated activities

Type of Activity	Schedule 1 Activity	Description of Activity	Limits of specified activity
Installation	Section 5.1 Part A(1) (b)	The incineration of non-hazardous waste in a waste incineration plant with a capacity of 3 tonnes per hour or more	From receipt of waste to treatment and emission of exhaust gas and disposal of any residues arising and processing of incinerator bottom ash.
Directly associated activities			
Directly associated activities		Energy generation	Generation of up to 49.9 of electrical power using a steam turbine, with electricity exported to the National Grid, and the potential to export heat to local heat users from energy recovered from the flue gases
Directly associated activities		Back-up diesel generator	For providing emergency electrical power to the plant in the event of supply interruption. Operation for no more than 50 hours per year for testing purposes (unless in emergency situations).
Directly associated activities		Surface water management	From collection of uncontaminated surface water drainage for discharge to the MedwayOne surface water drainage system.

4.2 Site plans and drawings

The following plans and drawings are included within Appendix A of this report:

- site location plan (Appendix A.1);
- site layout plan (Appendix A.2);
- waste and materials storage areas plan (Appendix A.3);
- access points (Appendix A.4);
- indicative locations of fire hydrants (Appendix A.5);
- indicative locations of fire walls (Appendix A.6);
- indicative location of quarantine area (Appendix A.7);
- fire receptor plan (Appendix A.8);
- areas of natural and unmade ground (Appendix A.9); and
- indicative firewater storage and containment (Appendix A.10).

Detailed design will be undertaken following appointment of a technology provider. Therefore, the information in relation to some of the drawings identified above must be considered to be indicative until detailed design of the Facility has been completed. Following completion of detailed design, the following drawings will also be included within the updated FPP, in accordance with the EA's FPP guidance:

- the location of drain covers, and any pollution control features such as drain closure valves and firewater containment systems;
- a detailed site drainage plan;
- the location of gas cylinders and mobile plant;
- a plan showing permanent ignition sources at the site; and
- the location of plant (including mobile plant), protective clothing and pollution control equipment and materials (such as spill kits).

Wind roses indicating the direction of prevailing winds for the Facility from 2014 to 2018, taken from Gravesend-Broadness meteorological station, are presented in Appendix B.

4.3 Plan of sensitive receptors near the site

The following section details the local sensitive receptors which are considered to be sensitive to the effects of a fire event at the Facility. In the unlikely event of a fire, the site personnel, and the infrastructure and equipment at the Facility itself, will be most at risk. A fire at the Facility will potentially have a temporary localised impact on the operation of the Facility, or a wider impact on surrounding receptors, depending on meteorological conditions at the time of any incident. Meteorological conditions are discussed further in section 4.4.

According to the EA's FPP guidance, examples of sensitive receptors include:

- schools, hospitals, nursing and care homes, residential areas, workplaces;
- protected habitats, watercourses, groundwater, boreholes, wells and springs supplying water for human consumption; and
- roads, railways, bus stations, pylons (on or immediately adjacent to the site only), utilities, airports.

According to the guidance, receptors up to 1 km from the site should be included, as these are considered to be most at risk of impacts from a fire.

The receptors which could be impacted by a fire at the Facility are presented in Table 3.

Table 3: Human Sensitive Receptors

ID	Name	Location		Distance from the stack (km)
		x	y	
R1	Burnt House Farm	580288	172393	0.79
R2	Abbots Court Nursing Home	579373	172152	1.73
R3	Property on Jacobs Lane	580024	172707	1.02
R4	8 Sturdee Cottages	579241	172929	1.83
R5	2 Beluncle Farm Cottages	580111	173376	1.20
R6	1 Stoke Cottages, Tunbridge	580514	173955	1.44
R7	White Hall Farm House	580870	173930	1.33
R8	Property on Stoke Road	581224	174207	1.60
R9	Property on Stoke Road near r/way	581579	174000	1.48
R10	The Lodge, Tudor Farm	581638	174563	2.04
R11	Dingley Dell, Dickenson Close	582355	174957	2.68
R12	Yew Tree Lodge Care Home	578961	172732	2.08
R13	1 Primrose Cottages, Ratcliffe Highway	578533	173928	2.83
R14	Neyfyn House	577761	173334	3.36
R15	Four Elms Hill AQMA	576315	172100	4.75
R16	Gillingham AQMA	578340	169223	4.34

A plan showing the location of receptors surrounding the site (a Fire Receptor Plan), as required by the EA’s FPP guidance, is presented within Appendix A.8.

4.4 Meteorological conditions

The Environment Agency recommends that 5 years of data are used to take into account inter-annual fluctuations in weather conditions. The period 2014 to 2018 has been used as this is the most recent 5 year period available from Gravesend Broadness meteorological station.

Wind roses for each year are presented in Appendix B. As shown in the wind roses, the predominant wind direction is north-easterly.

5 Managing common causes of fire

5.1 Arson or Vandalism

Robust security measures will prevent access to the Facility by members of the public, thereby reducing the risk of arson attacks or vandalism. The Facility will be surrounded by security fencing, and a barrier will be present at the entrance and exit of the site to restrict vehicular access. It is expected that the Facility control room will always be manned, and CCTV cameras will be visible from both the gatehouse entrance and control room. As such, only authorised visitors will be able to enter the site.

Emergency response procedures will be developed for the Facility prior to the commencement of operations, as part of the documented management systems. The procedures will detail the response to a number of different emergency situations on site, including unauthorised personnel accessing the Facility.

The design and location of the CCTV systems and security alarms will be undertaken during detailed design of the Facility and labelled on a site plan accordingly.

The Facility will be operational and manned 24 hours a day, 7 days a week, with the CCTV system monitored in the control room by trained and competent operators. CCTV will cover areas where waste is unloaded, with waste deliveries supervised by operational staff. The shift team leaders will be responsible for security on the site, including delivery vehicles as they travel around the site.

5.2 Plant and equipment

An operating and maintenance manual (O&M manual) will be developed and completed through the commissioning phase of the Facility. The O&M Manual will set out detailed operating and maintenance instructions for all plant and equipment which requires maintenance.

Maintenance procedures and work instructions will be developed to cover all plant and equipment within the Facility. As part of these, the risk of fire will be considered, and appropriate activities included within the maintenance procedures and work instructions to reduce the risk of fire in all plant and equipment.

As part of the maintenance system, responsibilities for retaining records of all maintenance undertaken and any actions taken following a problem will be defined.

There will be frequent visual checks of waste processing equipment, including the crane and bunker arrangement, to allow the prompt identification of any 'unsuitable' or 'unacceptable' wastes which includes hot loads. Waste processing equipment will be subject to regular preventative maintenance in accordance with the documented management systems in place, and will be fitted with suitable fire suppression systems, further details of which are provided within section 11.

5.3 Electrical faults including damaged or exposed electrical cables

The risk of electrical faults at the Facility will be minimised by the use of qualified electricians and will comply with the relevant British Standards for the design and installation of electrical equipment and supplementary bonding/earthing. The site will be constructed and operated in accordance with recognised standards for fire prevention, detection and control within electrical control systems.

Testing will be carried out on electrical equipment by fully and appropriately qualified electricians, when required. The inspection of electrical cabling at the Facility will be included in the documented maintenance programmes. Electrical circuits on both mobile plant and static equipment will be checked in accordance with the manufacturer's recommendations.

All portable electrical appliances will be PAT tested annually, with a label attached to the plug (or the cable) to confirm the item has been tested.

The exact types of fire detection and suppression systems for electrical control systems will be subject to detailed design. However, it is expected that the following measures will be implemented in accordance with current best practice for this type of facility:

- All rooms with concentrations of electrical equipment such as switchgear rooms, low voltage rooms, distributed control system (DCS) rack room, uninterruptible power supply (UPS) / battery rooms, and crane control cabinet rooms will be fitted with suitable fire detection systems. Fire detection will be by means of a 'double knock' system, composing of ionisation (or heat and smoke) detectors to minimise the risk of false activation. Furthermore, Manual Call Points will be installed in all areas. The detection systems will be designed for ease of regular testing to demonstrate correct operation.
- Electrical equipment will be installed within electrical rooms or e-housing rooms of steel construction with dedicated fire detection and suppression systems.
- Suitable automatic fire protection systems will be located within the rooms. For electrical rooms, it is expected that inert gas suppression systems will be used. These will be installed and operated in accordance with a recognised standard, such as EN 15004. Gaseous supply bottles and local control/isolation panels for the systems will be located outside the enclosed area (i.e., the electrical e-housing room) being protected by the system.
- All cable trays or piping systems passing through fire barriers will be fitted with fire stops. Cable spreading rooms and cable tunnels which are long, or otherwise difficult to access for firefighting, will be protected with appropriate automatic fire suppression systems (such as automatic gaseous extinguishing systems, or sprinklers or water spray systems).

5.4 Discarded smoking materials

Smoking will be prohibited in operational areas at the Facility. External areas within the site boundary that are designated for smoking will be identified, and suitable facilities will be provided for staff.

5.5 Hot works safe working practices

Staff and contractors will follow safe working practices which will include a permit to work system when carrying out hot works such as welding or cutting at the Facility. A fire watch will be carried out for a suitable period after hot works have ended, and at the end of a working day (i.e., after each shift).

5.6 Industrial heaters

It is currently expected that industrial heaters will not be installed at the Facility, however, this will be confirmed during detailed design of the Facility. If applicable, the hot work management system will be extended to include the use of industrial heaters and the necessary safeguards required in each instance will be assessed and implemented to ensure their use is safe.

5.7 Hot exhausts and engine parts

A fire watch system will be implemented at the Facility to detect signs of fires from dusts settling on hot exhausts (including those associated with mobile plant). This will be developed as part of the operating procedures. This will include regular visual checks of dusts settling on hot exhausts as part of operational checks by staff – it is expected that these checks will be undertaken at the end of each shift and so will be daily. Maintenance work instructions will be raised for any items identified as requiring maintenance.

5.8 Ignition sources

A review under the Dangerous Substances and Explosive Atmospheres Regulations (DSEAR) will be completed during the detailed design of the Facility, with any risk areas identified on DSEAR zonal drawings. This is required for installations which use dangerous substances, including pressurised gases.

Vehicles and electrical items necessary for the operation of the Facility will be regularly inspected for electrical faults. Mobile plant serving the Facility will be fitted with fire extinguishers and dust filters where appropriate.

Naked sources of ignition will be controlled through a hot work management system. This system will cover both staff and contractors working at the Facility. The hot work management system will also include requirements to train and authorise 'hot work risk assessors' for the purposes of eliminating, reducing and managing the risks associated with hot work. The hot work system will include for a period of fire watch following the hot works being undertaken.

As part of the hot work management system, the potential for sources of ignition to cause fires will be managed on a case-by-case basis. The guidance of keeping all sources of ignition at least 6 metres away from any combustible or flammable waste will be followed as part of this management where possible (i.e., this separation distance may not be possible when using or transporting mobile plant or when driving site vehicles). The management system will include ensuring that the location of stored mobile plants, which is subject to detailed design of the Facility, will be stored at least 6 metres away from combustible wastes. In the unlikely event that this separation distance cannot be maintained, there will be suitable fire detection and protection measures installed in this area to minimise the risk of a fire spreading, the design of which is subject to the recommendations of the final fire strategy which will be completed during the detailed design phase of the project and agreed with the fire risk insurers.

5.9 Leaks and spillages of oils and fuels

Emergency response procedures will be developed for the Facility. The procedures will include actions to be undertaken to respond to spills and leaks of chemicals. This will include actions to be undertaken to prevent liquids leaking or trailing from site vehicles. In addition, oil interceptors will treat surface water runoff prior to discharge from the site, further reducing the potential for off-site contamination.

Mobile plant and vehicle operators will be provided with suitable training for the equipment they are operating. Supervision of mobile plant operation and regular site inspections will ensure that any leaks or trailing from vehicles are quickly identified and suitably maintained to prevent leaks. Where specific responsibilities are given to specific staff, training will be provided to those employees. Training records in the emergency response procedures for all staff and contractors will be retained on-site.

Should a spill occur at the site, contained drainage systems in process areas will ensure that any contaminated effluent is not released to the aquatic environment. Storage of liquid chemicals (for example ammonia and fuel oil) will be within bunded areas with the secondary containment having sufficient capacity to contain a spill. Regular inspections will be undertaken of storage vessels as part of regular preventative maintenance procedures.

Spill kits will be made easily available at different locations throughout the site. The location of spill kits will be marked up on a site plan following detailed design of the Facility. The documented management procedures for the Facility will include for accident management measures and will set out procedures to be followed in a spill event. All staff and contractors would be trained in site-wide emergency response procedures.

5.10 Build-up of loose combustible waste, dust and fluff

The Facility will be designed to prevent the accumulation of dusts by designing structural steelwork such that their shape or method of installation minimises the surface area where dust can settle.

As part of the design of the Facility, the control of dust and fluff has been considered. This includes:

- the use of an enclosed fuel reception/unloading building; and
- mechanical ventilation of the waste reception and storage areas to prevent fugitive emissions from the building facade.

These systems will be checked as part of the planned maintenance regime as required in the detailed operating manuals for each piece of equipment.

On a daily basis, inspections will be undertaken to identify the build-up of loose combustible materials, such as waste, dust and fluff. Where inspections identify that there has been a build-up of loose combustible materials, appropriate cleaning (such as washdown using hoses) will be undertaken to clean this material from the surfaces. Good housekeeping practices will be employed at the Facility to ensure that dusts and litter do not build up and pose a fire risk.

5.11 Reactions between wastes

Waste acceptance procedures will be in place which will minimise the risk of incompatible wastes coming into contact with each other, or unstable wastes being accepted at the Facility.

In the unlikely event that waste identified as 'unacceptable' is received, quarantine areas will enable segregation of the waste prior to transfer off-site or extinguishing of a hot load (refer to section 9).

5.12 Deposited hot loads

Documented waste pre-acceptance and waste acceptance procedures will be in place at the Facility, which will enable the identification of any 'unacceptable' wastes or the presence of hot loads. Waste acceptance and pre-acceptance procedures will meet the requirements of EA Guidance S5.06, to ensure that only the permitted waste codes are accepted.

Further details on the dedicated quarantine areas are presented in section 9. Should a 'hot load' be delivered to site, a 'hot load procedure' will be followed. The requirements of the hot load procedure will be incorporated into the waste acceptance procedures.

Hot loads are often identified due to smoke being emitted from the vehicle. If identified prior to transfer to the bunker (if not immediately rejected) the vehicle will be sent to an external quarantine area and extinguished.

Hot loads may be identified visually due to smouldering waste or using thermal imaging fire detection within the waste bunker. Hot items may be removed from the bunker, if safe to do so, using the waste grab and loaded directly into the combustion chamber. Should a fire propagate within the waste bunker or waste feed chute it would be extinguished by water cannon/hoses installed around the waste bunker and above the waste feed chute.

5.13 Hot and dry weather

Incoming loose waste, stored within the bunker at the Facility, will be provided with protection from direct sunlight as the main waste storage areas will not be fitted with external windows. Periods of hot weather have the potential to increase the risk of fires; however, as loose waste will be stored within the main buildings, this will reduce the risk of overheating.

6 Preventing self-combustion

6.1 General self-combustion measures

It is acknowledged that some wastes can self-combust under certain conditions. Self-combustion can be managed through preventative measures, carefully managing storage times, pile volumes and height, and the temperature of the wastes. These are described further within the following sections.

6.2 Managing storage time

6.2.1 Methods used to record and manage the storage of all waste on site

In the event that either facility is not able to receive waste due to an unplanned incident, forcing a full shutdown of the facility, waste deliveries will be stopped and/or diverted to a suitably licenced waste management facility. Typically, in the event that an unplanned shutdown lasts for more than 14 days, waste within the bunker may be backloaded into lorries for transport to a suitably licensed waste management facility, unless operations are expected to recommence imminently. The rate at which waste will be removed from each facility will depend on the status of operation and expected recommencement of operations at each facility. In addition, environmental factors such as weather (e.g., hot weather posing odour risks) may contribute to the urgency to remove waste from the facility.

The capacity of the waste bunker will be clearly stated and not exceeded. The waste storage capacity of the bunker will be approximately 8,700 tonnes (or 25,000 m³), equivalent to approximately 6 days fuel supply. However, allowing for extended periods of shutdown, the maximum amount of time that waste will be stored in the bunker is expected to be up to 4 weeks.

Prior to any planned shutdowns of the Facility, waste deliveries will be stopped and/or diverted to alternative waste management facilities. The waste within the bunker will be combusted to minimise the quantity of waste remaining in the bunker prior to the shutdown commencing. This will ensure that there is only a small residue in the bunker during the period of shutdown. The duration of planned shutdowns will vary significantly, dependent on the nature of the work required, and will typically will not extend beyond four weeks.

6.2.2 Stock rotation policy

Following the recommencement of waste deliveries after a period of shutdown, deliveries of 'new' waste will be mixed with residual quantities of waste within the bunker in accordance with the bunker management procedures – refer to section 6.3.1. This will ensure that older waste is not 'buried' within the bunker. It is not expected that there will be seasonal variations in the demand or supply of waste.

6.3 Monitoring and control temperature

6.3.1 Monitoring and controlling temperature

As part of the detailed design and construction of the Facility, the fire system design will be designed and installed by an experienced fire engineering company, which employs appropriately

qualified persons. Systems will be developed in collaboration with the local fire officer, the fire risk insurers and any relevant standards and codes of practice.

All waste delivered to the Facility will be supervised by operational staff, who will be responsible for the inspection and monitoring of waste deliveries. Operational staff will be briefed on the need for monitoring for the early signs of fires.

The frequency of inspection of waste storage areas (and other parts of the site) will be increased during a full shutdown, and a checklist utilised to ensure a complete record of issues and comments that may require further action, such as assessing the presence of hotspots within waste storage areas.

The fire detection and protection system will be developed in accordance with NFPA 850 (an industry standard for fire protection systems for power generating facilities) or equivalent standard. The waste bunker and all main process areas will have CCTV to allow remote monitoring from the control rooms on a continuous basis.

Thermal imaging cameras or infrared (IR) flame detectors will be fixed around the perimeter of the bunker to provide the crane driver with a continuous thermal 'map' of the bunker. This is standard practice in UK waste incineration plants. The temperature of waste in the bunker will continue to be monitored even during periods of shutdown.

During daytime operations, the bunker will be visually monitored by control personnel, such as the crane operator. At night-time, the control personnel will visually monitor the thermal imaging system as part of their responsibilities for operating the Facility. Therefore, they will be able to identify and react to hot areas in the bunker and undertake the mixing or feeding of waste as appropriate.

Bunker management procedures will be adopted to ensure that there is a regular turnover of waste within the bunker, preventing hotspots or anaerobic conditions developing within the bunker. The turning of waste within the bunker is standard practice at waste incineration plants in the UK. As well as helping to mix the waste (to produce a more homogenous fuel which is better for control of the combustion process), it helps to prevent the formation of hotspots. Turning of the waste within the bunker helps to release heat that has built up in the waste. By taking grabs of waste and then spreading it over a wider area, it dissipates the entrained heat and removes thermal inertia within the waste. It also increases the evaporation of water, which is a heat absorbing process. These factors help to minimise the risk of self-heating and ignition. In addition, mixing the waste with the crane enables waste from the base of the bunker to be brought to the surface, reducing the risk of anaerobic conditions developing and ensuring older waste does not remain 'buried' at the base of the bunker. The crane will be sized to allow for mixing and rotating the waste within the bunker, whilst providing appropriate quantities of waste within the feed hopper to maintain operation of the waste combustion process. The size of the crane will ensure that the mixing of waste is feasible in relation to the amount of waste present in the bunker. The crane operator will be trained in careful waste handling and crane operation as to maintain the integrity of the bunker structure itself.

In extreme cases, firewater cannons (refer to section 11.1.4) may be used to extinguish any smouldering or burning waste that is identified within the bunker. The thermal imaging cameras and/or IR flame detectors will be set with two trigger alarms at different temperatures within the bunker. The fire water cannons will be activated if the 'high-high' temperature alarm is reached.

IBA produced from the Facility will be transferred to the ash storage area via conveyor before being transferred off-site to an IBA processing facility. Due to the high thermal temperatures in which the IBA has been combusted, it is not expected to contain any combustible materials which are able to self-combust from the elevated temperatures within the IBA. In addition, the quenching of the ash

will ensure it has been suitably cooled prior to processing/storage, and the moisture within the IBA from quenching of the ash will ensure that the IBA will not combust.

APCr is not expected to contain any combustible materials which could self-combust from elevated temperatures associated with the handling and storage of APCr.

6.3.2 Reducing exposed metal content and proportion of fines

As the waste received will be pre-processed residual waste, it is not expected that there will be large quantities of metals within the waste. Furthermore, it is not expected that a large quantity of fines will be present within the waste. Therefore, the FPP guidance requirement to reduce exposed metal content and proportions of fines does not apply.

6.3.3 Dealing with hot weather and heating from sunlight

Waste at the Facility will be stored in enclosed buildings, and therefore won't be exposed to direct sunlight and external heating.

6.3.4 Waste bale storage

Waste bales will not be stored at the Facility.

7 Manage waste piles

7.1 Storing waste materials in their largest form

Incoming waste will not undergo any further 'treatment' upon receipt at the Facility prior to incineration.

7.2 Maximum pile sizes

It is understood that the EA's maximum waste pile sizes are not applicable to waste stored within a waste bunker. Therefore, the pile sizes in the FPP Guidance do not apply to waste stored at the Facility.

7.3 Waste stored in containers

The only waste which will be stored in 'containers' is APCr which will be stored within silos. The design of the silos is subject to detailed design; however, it is expected that the total storage capacity for APCr will be approximately 250 m³. The APCr silos will have sufficient capacity for the storage of approximately 5 days of APCr, assuming that the Facility operates continuously at the nominal capacity.

As stated in section 6.3.1, the APCr is not expected to contain any combustible materials which could self-combust from elevated temperatures within the APCr.

8 Prevent fire spreading

8.1 Separation distances

Following previous consultation with the EA, it is understood that the storage requirements relating to pile separation distances (i.e., storing combustible waste piles with a separation distance of at least 6 metres) only applies to the external storage of wastes.

All wastes delivered to the Facility will be stored within buildings and will primarily be stored within the waste bunker. It is understood that pile separation distances do not apply to the waste bunker.

8.2 Fire walls construction standards

Fire walls will be installed within the buildings as required by the fire risk insurers and in accordance with Buildings Regulations. The location and specification for fire walls will be subject to detailed design, and will be dependent on the 'final' layout developed by the EPC Contractor. Indicative locations for the fire walls are presented in Appendix A.6.

Subject to the location of the process equipment, operational areas at the Facility will be segregated into fire zones (the "Fire Zones"). In accordance with NFPA 850, certain specific Fire Zones, such as the waste bunker and boiler hall, will be separated from each other by fire barriers with a minimum of 2-hour fire resistance rating, spatial separation, or by other approved means. The specific Fire Zones to which this applies, and the means of separation, will be subject to agreement with the fire risk insurers.

As part of the detailed design process, a fire risk assessment will be undertaken for each Fire Zone within the Facility to identify the appropriate fire detection and protection systems in association with appropriate civil work design principles to control:

- the risk of fire propagation;
- the spread of fumes and smoke;
- firewater flooding; and
- to maintain the integrity of dedicated fire partition walls in the event of fire.

The fire zoning will be subject to the approval of Low Carbon and the fire risk insurers.

The dividing wall between the waste bunker hall and boiler hall at the Facility and all other walls within the bunker will be suitably constructed in concrete, block work or a suitably rated cladding system up to roof level to form a continuous 2-hour fire rated barrier for the full width and height of the building structure. In addition, the base of the bunker will be constructed of reinforced concrete, and the whole structure will be designed as a water retaining structure. The structural design and construction of the dividing wall shall be such that the integrity of the fire barrier is maintained in the event of the collapse of the bunker hall roof due to a fire in the bunker. The walls and the base of the bunker will be resistant to crane grab impact and the impingement of water cannon jets. Therefore, the structure of the waste bunker will provide adequate fire resistance/containment.

All openings in fire barriers will be provided with fire doors, including fire dampers, penetration seals (fire stops), or other approved means having a fire protection rating consistent with the designated fire resistance rating of the barrier. Windows in fire barriers (e.g., control rooms, observation windows, computer rooms, etc.) will be provided with appropriate fire protection to maintain the integrity of the fire barrier, e.g., by means of a fire shutter, automatic water curtain,

window sprinkler system, etc. All cable trays or piping systems passing through fire barriers will be fitted with fire stops. In addition, the glass partition in the control room/crane cabin will be 2-hour fire rated, and hence resistant to fire. Therefore, the operational staff will be able to continue operating the crane for a limited amount of time in the event of a fire, depending on severity.

8.3 Storing waste in bays

Waste which is delivered to the Facility will not be stored in bays, with incoming waste stored within the waste bunker. Therefore, the requirements for the storage of waste within bays will not apply.

9 Quarantine areas

9.1 Quarantine areas – location and size

When depositing waste in the quarantine areas at the Facility, the operatives will attempt to place the waste so that a reasonable separation distance is maintained around the waste, and does not lie directly adjacent to any walls. Suitable fire detection and suppression systems will be installed in the quarantine area to reduce fire risk within this area. When it is not being used for the storage of unacceptable waste, the quarantine area will be kept clear.

Following completion of detailed design, plans showing the location of all quarantine areas will be developed. The plans will show the size of the quarantine area, clearance areas around the perimeter, and infrastructure associated with the quarantine area. A drawing which shows the indicative location of the quarantine area at the Facility is presented in Appendix A.7 of this report.

A suitable area for the quarantine of unacceptable waste will be designated as part of the detailed design stage; however, it is anticipated that this will be a designated area within the tipping hall. The quarantine area will be designed in accordance with the requirements of the FPP Guidance, i.e., it will:

- hold at least 50% of the waste delivery load; and
- where practicable, have a separation distance of at least 6 metres, or alternative equivalent measure (such as a thick concrete wall between the bunker and the quarantine bay, or provision of containers or skips in the quarantine area), around the quarantined waste.

With regards the first requirement, this is stated in the FPP guidance as holding “*at least 50% of the volume of the largest pile, row or block of containers*” at the Facility. As pile size requirements and separation distances do not apply to the waste bunker, the waste stored within the bunker is not considered to fall under the definition of a waste ‘pile’ as per the FPP guidance. The largest pile or container of waste will be waste contained within delivery vehicles. The quarantine area will have sufficient capacity to hold at least one waste delivery vehicle load. This will allow the segregation of the whole waste delivery should a hot load be identified upon arrival at the Facility.

With regards the second requirement, depending on the size of the waste pile requiring quarantine, it may not be possible to maintain a separation distance of 6 m around the quarantined waste. However, in the unlikely event that there is more than one pile of waste (for example, two loads requiring storage in the quarantine area), skips will be used within the quarantine area to maintain appropriate separation between the wastes.

In addition to the quarantine area within the waste reception hall, there will be a separate hot loads area which will be used for quarantining waste deliveries which are identified as containing hot loads.

9.2 How to use the quarantine areas if there is a fire

The quarantine area will be used to temporarily store, if needed, any unacceptable waste prior to removal from site. Unacceptable waste is broadly defined as waste which does not meet the requirements set out in the waste supply agreements, or waste which is otherwise unsuitable for incineration at the Facility, and/or is not compliant with the EWC codes stated in the EP.

In the event that the unacceptable waste is a hot load, this would be extinguished and stored in the quarantine area for a short period of time before being transferred off-site. At the Facility, where unacceptable waste is identified inside the bunker, it will be back-loaded from the bunker into the

back-loading bay/quarantine area using the waste crane, for examination and/or removal from the site to a suitably licensed waste treatment facility.

Any waste placed within the quarantine area will be removed in a timely manner (i.e., typically within 24 hours), so it is highly unlikely for a situation to arise whereby the quarantine area is already 'full' and another load needs to be placed within the quarantine area. Any hot loads would be placed in a location within the quarantine area which is away from any loads which have already been transferred to this area. If the waste is burning when it is transferred to the quarantine area, it will be extinguished immediately upon placing in the quarantine area to prevent the spread of fire to any loads already within the quarantine area. Containers will be provided in the quarantine area to allow loads to be segregated.

Depending on the location of the fire, there may be a requirement for an alternative quarantine area, particularly when it has been identified as unsafe or not practical for hot loads to be transferred to the dedicated quarantine area. In this situation, the FSM or deputy FSM will undertake a dynamic risk assessment should additional quarantine areas be required. The dynamic risk assessment will take into account the potential for contaminated firewater runoff resulting from water suppression; the location of fire suppression systems; and the potential for the spread of fire.

9.3 Procedures to remove material stored within the quarantine areas

Hot loads stored within the quarantine areas will be removed as soon as possible (i.e., within 1 hour of a fire starting). Appropriate fire detection and protection measures (e.g., smoke/flame detectors, hose reel, sprinklers, fire extinguishers) will be installed in the quarantine areas. Therefore, if a fire was to occur within the quarantine areas, it will be extinguished prior to the waste being transferred off-site. If required, the emergency services would be called for assistance.

Unacceptable waste will be segregated from all other incoming waste, allowing it to be collected and loaded into appropriate road vehicles for removal off-site, once deemed safe to do so.

Unacceptable waste will typically not be stored within the quarantine areas for more than 24 hours. The waste supplier would be contacted immediately upon identification of an unacceptable load, and provisions will be made for the waste to be collected and removed from the site. However, to allow for extended periods where waste deliveries are not occurring (such as bank holidays), the maximum time that waste could remain in the quarantine area will be up to 7 days. Low Carbon will co-ordinate with the waste supplier to ensure that unacceptable waste is removed from the site as soon as possible. This will reduce the risk of two separate loads requiring storage in the quarantine area. Notwithstanding this, contingency measures are in place in the event that more than one load requires storage in the quarantine area, through the use of skips located in the quarantine area – refer to section 9.1.

Typically, unacceptable loads would be identified immediately upon tipping into the bunker at the Facility. In this case, the waste delivery driver would be asked to remain at the site, the load would be rejected and the waste backloaded into the delivery vehicle for transfer off-site. Should the delivery driver have left the site, waste would be removed from the bunker using a crane, and deposited within the respective quarantine area.

10 Detecting fires

Procedures will be in place at the Facility to detect a fire in its early stages, in order to reduce the impact of the fire. The choice of fire detection systems (smoke/heat/flame detectors) to be installed within the Facility will be subject to detailed design. The fire detection systems will be covered by a UKAS-accredited third-party certification scheme or equivalent. The details of the fire detection systems will be confirmed prior to the commencement of commissioning.

During detailed design, appropriate fire detection systems will be proposed for the different areas of the Facility. The chosen fire detection systems will be appropriate to the waste treatment activities undertaken. Following completion of detailed design, a plan showing the fire detection systems in each area will be included in this FPP.

10.1 Detection systems in use

Fire detection and alarm systems will cover all of the waste processing areas. The fire alarm systems will include the following:

- local detectors/transducers and call points;
- sounders/high intensity flashing beacons;
- cabling and containment systems;
- local control and indication panels; and
- remote control and indication panel (incorporating integral printers) will be in the control rooms.

All fire detection systems will be installed in accordance with BS 5839, Part 1 (2002) and subsequent amendments to give level P1 + M coverage in accordance with the requirements of the Loss Prevention Council ("LPC") guidance, or equivalent standard. A category P1 system relates to the protection of property and involves installing detectors in all areas of the building. A category M system is a manual-operation only system which has call points on all exits, as well as corridors where call points are spaced a minimum of 45 m apart for access. In low fire risk areas, such as the Boiler Hall, the requirements for a P1 detection system may be relaxed.

All automatic fire detection and alarm systems will be designed and maintained by a suitably qualified, experienced and registered fire protection engineer. Detailed design calculations, risk assessments and system drawings to demonstrate compliance with the requirements of the building control officer, fire officer and the insurer's requirements will be produced during detailed design.

In areas which are identified as having a low fire risk, the fire detection method(s) will be agreed with the requirements of the fire service and fire risk insurer. The fire detection, protection and alarm systems will comply with the requirements of the fire service and fire risk insurer. All fire detection systems will be design, installed and maintained in accordance with an appropriate UKAS-accredited third-party certification scheme or equivalent.

Procedures will be developed in the operation of the fire detection systems. Training will be provided to the relevant staff in the different fire detection systems. Training records in the operation of the fire detection systems will be retained on-site. It will be the responsibility of the operators and shift managers to monitor fire alarms.

It is anticipated that the following fire detection systems will be incorporated into the design of the Facility:

1. Tipping hall fire detection will be provided by flame or temperature detectors in accordance with an appropriate risk study. Fire suppression in the tipping hall will likely be provided by an automatic sprinkler system or similar, to protect roofing and steelwork, with fire hose reels used manually in the case of vehicle fires or similar ground-level fires. The tipping hall fire detection and suppression systems will be subject to detailed design of the Facility.
2. Waste bunker fire detection will be provided by thermal imaging cameras and/or flame detectors which will be fixed around the perimeter of the bunker with automatic scanning of the entire fire zone. The thermal imaging cameras will provide a continuous thermal 'map' of the surface of the waste within the bunker. The thermal mapping will be displayed in the control room and will be used by the crane operator to manage temperatures within the bunker. The staff within the control room, as well as the crane operator, will be trained in the identification and implementation of corrective measures in the event of elevated temperatures within the bunker. The thermal imaging cameras will enable the crane operator and/or the control room staff to identify and react to hot areas in the bunker and undertake mixing or feeding of waste as appropriate. In extreme cases, the use of firewater cannons which covers the entire extent of the waste bunker to extinguish any smouldering/burning waste may be required.
 - Water cannons and manual fire hoses are considered to be the primary means of fighting a bunker fire.
 - To proactively prevent fires, it is anticipated that the fire detection systems will be configured to sound an alarm based on certain conditions. This would involve the thermal imaging cameras being set with two alarms at two different 'trigger' temperatures. These are described below.
 - Temperature set-points would be determined during detailed design of the Facility and in consultation with the fire service. It is understood that the system will be designed so that trigger temperatures can be amended if required.
 - High temperature alarms in other UK waste incineration plants operate with a trigger temperature of approximately 90 °C, with high-high temperature alarms operating with a trigger temperature of approximately 120 °C. The trigger temperatures for the fire detection systems will be subject to detailed design and will be set in consultation with the Fire Service – it is assumed that they will be similar to other UK waste incineration plants. The system can be designed so that the trigger temperatures for the fire detection systems can be amended if required from operational experience.
 - Following activation of the high temperature alarm in an area within the bunker, the area with an elevated temperature can be readily identified and, if possible, extinguished based on operator action through mixing within the bunker or fed into the hopper to be incinerated.
 - Following activation of the high-high temperature alarm in an area within the bunker, the area with an elevated temperature will be targeted and the firewater cannons will be activated to reduce the temperature in the area where self-heating has occurred.
 - Furthermore, the crane will be sized appropriately so that the time for waste mixing, feeding and management is within an acceptable time range for feeding waste to the feed hopper.
3. Feed hopper area fire detection will be provided by the waste feed hopper supervision camera or other suitable detection system, and a deluge system or firefighting nozzles to flood the feed hoppers if required.
4. In the boiler house the main cable trays and other fire sensitive areas will be protected with a sprinkler system or other suitable/equivalent fire suppression system. There will be suitable fire detection measures in place (e.g., a wire and fusible link system or heat detector and solenoid

valve) so that in the event of an external or internal fire, the local fuel supply isolation valve (fuel oil) is automatically closed.

5. Electrical rooms with significant concentrations of electrical equipment will be fitted with appropriate suitable fire detection systems and suppression systems (such as a gaseous extinguishing system).
6. All oil-filled transformers shall be located outdoors wherever possible. Dry type transformers are preferred for indoor installations. Oil type transformer protection will comply with the requirements of NFPA 850 or have an equivalent level of fire protection. If appropriate, enclosures for dry-type transformers will be provided with suitably designed fire detection systems.
7. The fire sensitive areas of turbine-generator and ancillaries will be protected by a dedicated fire detection and automatic sprinkler fire protection system or equivalent.

11 Suppressing fires

The suppression systems for the Facility will be subject to detailed design. The main features of the fire suppression systems are described in section 11.1. Active firefighting techniques are detailed in section 13.1, with further details on the water supplies for the fire suppression systems provided in section 14.

11.1 Suppression systems in use

There will be a fire suppression system installed in the locations considered by the fire strategy to be at risk of fire. The automatic fire suppression systems will be designed and maintained by a suitably qualified, experienced and registered fire protection engineer. The fire suppression systems will be covered by a recognised (typically UKAS) third party certification scheme.

Detailed design calculations, risk assessments and system drawings to demonstrate compliance with the requirements of the building control officer, fire officer and the insurer's requirements will be retained on site throughout the lifetime of the Facility.

11.1.1 Fire hose reel system

Hose stations will be designed in accordance with NFPA 14, Standard for the Installation of Standpipe, Private Hydrants and Hose Systems, or BS equivalent (e.g., EN 671). Fire hydrant systems equipment will be provided at strategic positions within the Facility for firefighting in fire risk areas.

For firefighting purposes, hose reels and extinguishers will be provided within the main buildings at the Facility.

The positioning of hose points will take into account the following:

- location and physical protection as to avoid potential damage by vehicles;
- size and number to be determined for the specific works layout (e.g., push wall positions);
- ease of use, maintenance, and storage, such as through the use of continuous-flow, non-collapsible hose reels; and
- protection from freezing in unheated areas.

Following detailed design of the Facility, a plan identifying the location of the fire hose reels will be developed.

11.1.2 Fire hydrants and mains

Fire hydrants will be designed in accordance with NFPA 14 Standard for the Installation of Standpipe, Private Hydrants, and Hose Systems (or BS equivalent – refer to section 12) and will be connected to a ring main at strategic positions around the Facility to provide firewater supplies to external fire risk areas. The fire hydrants will be designed in accordance with the requirements of the Building Regulations and the fire service. Fire hydrants shall be positioned such that all hydrants are no more than 90 m from a building entrance (in accordance with BS 9990) and within 12 m of the building.

The location of hose reels and hydrants will be subject to detailed design and will be agreed with the fire risk insurers and the fire officer. The positioning of fire hydrants will take into account:

- location and physical protection as to avoid potential damage by vehicles;
- size and number to be determined for the specific layout; and

- protection from freezing.

The fire hydrants will be fed from the fire water storage tank(s) and maintain the required pressure in accordance with the requirements of the fire service.

Following completion of detailed design, a plan identifying the location of the fire hose reels and hydrants will be developed. An indicative drawing showing the possible locations of fire hydrants is presented in Appendix A.5 of this report.

11.1.3 Fire extinguishers

Fire extinguishers will be strategically located throughout the operational areas of the Facility in accordance with the requirements of BS 5306 (or NFPA equivalent).

The location of the fire extinguishers will be subject to implementation of the recommendations of the fire officer for the Facility. Following completion of detailed design, a plan identifying the location of the fire extinguishers will be developed.

11.1.4 Additional suppression systems

As described within section 10.1, thermal imaging cameras will be installed over the waste bunker to detect any hot spots in the waste. If the temperature of any hot spot exceeds a defined set-point, water cannons installed around the bunker can be used to prevent the potential for fire spreading within the bunker. The water cannons will be located in positions to optimise the horizontal and vertical coverage of spray for total firefighting suppression across the entire area of the bunker.

Through detailed design of the waste bunker, the number and position of the fire monitors and cannons will be established, alongside the manual and/or automatic remote-control systems. Thermal imaging screens will be installed within the control room.

In addition to the fire suppression systems outlined within sections 11.1.1 to 11.1.3, and the bunker cannons as described above, it is anticipated that the fire suppression systems at the Facility will also include the following:

- automatic sprinkler/water deluge systems for the fuel reception areas, waste bunker, waste feed hopper, fire pump container and the emergency diesel generator;
- automatic systems for the turbine generator and lube oil systems, auxiliary burners; and
- inert gas suppression and carbon dioxide gas suppression for the electrical rooms and CEMS container.

12 Certification for the systems

The Facility will be designed and operated in accordance with relevant standards and guidelines, or alternative recognised international standards where they are available. This may include, but not be limited to, the following:

- BS EN 54: Fire detection & alarm systems
- EN 671: Fixed firefighting systems. Hose systems.
- BS 750: Specification for underground fire hydrants and surface box frames and covers.
- EN 1028: Fire-fighting pumps. Fire-fighting centrifugal pumps with primer.
- BS 5041: Fire hydrant systems equipment.
- BS 5266: Emergency lighting
- BS 5306: Fire extinguishing installations
- BS 5839: Fire detection & alarm systems for buildings
- BS 7273: Operation of fire protection measures
- BS 7974: Application of fire safety engineering principles to the design of buildings.
- BS 9990: Non automatic fire-fighting systems in buildings.
- BS 9997: Fire risk management systems.
- BS 9999: Code of Practice for Fire Safety in the design, management and use of Buildings.
- EN 12101-2: Smoke and heat control systems. Natural smoke and heat exhaust ventilators.
- EN 12259: Fixed firefighting systems. Components for sprinkler and water spray systems.
- EN 12845: Fixed Firefighting systems. Automatic sprinkler systems. Design, installation and maintenance.
- EN 13565: Fixed firefighting systems. Foam systems.
- EN 14384: Pillar fire hydrants.
- EN 14710: Fire-fighting pumps. Fire-fighting centrifugal pumps without primer.
- EN 14972: Fixed firefighting systems. Water mist systems.
- EN 15004: Fixed firefighting systems. Gas extinguishing systems.
- NFPA 850: Recommended practice for fire protection for electric generating plants and high voltage (for the Facility), in addition to other relevant NFPA standards as applicable.
- Requirements/guidance from the Insurer.

Records associated with the certification of the fire prevention and suppression systems will be retained on site throughout the lifetime of the Facility.

13 Firefighting techniques

13.1 Active firefighting

An immediate firefighting response will be allowed to be made by staff if the following criteria have been met:

- the fire alarm has been raised;
- the fire is identified to be 'small' and it has been deemed safe by the individual to attempt fire suppression; and
- such firefighting action (e.g., use of a single fire extinguisher) is deemed safe and likely to have a direct and immediate effect on the fire.

Team firefighting (i.e., more than one member of staff operating firefighting equipment at once) will be permitted in the event of a larger fire by the use of multiple fire extinguishers and the fire hose reels if the following criteria are met:

- the fire alarm has been raised;
- the FSM (or deputy FSM) is in attendance;
- a sufficient number of trained staff are available;
- an escape route is always available;
- staff are not deemed to be at risk of smoke inhalation, significant heat exposure or other relevant fire risks; and
- such firefighting action is deemed safe and likely to have a direct and immediate effect on the fire.

13.2 Alternative fire detection and suppression measures

In addition to the fire detection and suppression systems identified in sections 10 and 11, the design of the Facility will include 'additional measures' to prevent the spread of fire, such as fire walls (section 8.2).

It is acknowledged that the Facility is not designed strictly in accordance with all of the requirements of the FPP guidance (specifically, the provision of water for firefighting, refer to section 14). However, the overall design of the Facility, including the fire detection and fire suppressions systems, where applicable, have been designed to achieve the requirements of the guidance, namely:

- minimising the likelihood of a fire happening;
- aim for a fire to be extinguished within 4 hours; and
- minimise the spread of fire within the site and to neighbouring sites.

In addition, in the event of a significant fire within the waste bunker, the plant can be shut-down which will include the shut-down of the induced draft (ID) fan and the extraction of combustion air from within the bunker. The plant shutdown will reduce the risk of fire spread between the 'fire compartments' within the building.

14 Water supplies

The Facility will have a firewater storage tank designed in accordance with the requirements of BS 5306 (or equivalent standard). The firewater storage tank will be connected to the local water supply and will be installed with a suitable system to prevent freezing. It is anticipated that the firewater storage tank will be fitted with a local external water level indicator as well as with remote water level control and level alarm indication to the distributed control system (DCS).

It is proposed that the design of the systems for the provision and containment of firewater at the Facility are confirmed via a pre-operational condition or similar.

It is estimated that the size of the firewater storage tank will be approximately 1,400 m³. The exact size of the firewater tank will be confirmed following detailed design. The firewater tank will be designed to ensure the required fire water capacity is always available for fire protection. When specifying the exact sizing for the firewater tank, it will be based on early fire detection and automatic fire suppression systems in the waste reception and storage areas such that any fire can be rapidly contained and extinguished.

The FPP Guidance requires a supply of firewater of 2,000 l/min for 3 hours for a 300 m³ pile of waste, but this is based on an open pile of waste with free run off, rather than storage in a bunker which contains the water. For a waste bunker with a waste storage capacity of 20,400 m³, the guidance implies the need for a 24,480 m³ fire water tank, which is larger than the capacity of the bunker. The potential volume of firewater required to extinguish a fire in the bunker will be considerably less than the total 'airspace' volume of the bunker, as the waste present in the bunker will reduce the available volume.

The provisions for the supply of firewater for the Facility are not in accordance with the EA's FPP guidance; however, the proposed management systems; the design considerations of the Facility; and the provision of the fire prevention and fire-fighting measures detailed within this FPP are considered to be in excess of the requirements of the FPP guidance. Therefore, the requirements of the EA's FPP guidance should not apply to the Facility.

The waste bunker will be a contained concrete structure, with thick fire-resistant concrete walls. The provisions for firefighting in this area will be in accordance with NFPA 850 and as required by the fire risk insurers. In addition, subject to detailed design, foam may be used as an additive in the firewater system which will reduce the quantity of water required for firefighting. Early fire detection methods and fast suppression will mean that the full contents of the firewater tank are unlikely to be required. The requirements for firewater provision in the FPP guidance have been discussed with the EA previously and it has been acknowledged that they would not apply.

15 Managing fire water

Firewater resulting from external areas at the Facility would be collected in the site surface water drainage systems. An attenuation pond will be provided at the site, which will have a capacity of approximately 2,300 m³. The attenuation pond will be pumped into Damhead Creek. Therefore, in the event of a fire the pump will be inhibited, which will prevent the discharge of contaminated surface water off-site in the event of a fire or other emergency.

1. It is acknowledged that the capacity of the surface water attenuation pond will be reduced by the quantity of water already present within the system; however, it is not anticipated that the attenuation systems will regularly store large amounts of water, as the required attenuation capacity was calculated assuming a 'worst case flow' (i.e., allowing for SUDS and climate change requirements). Therefore, there should be sufficient capacity available to hold excess firewater in the event of a fire. Furthermore, additional capacity from site raised kerbing (of 100 mm depth) and hardstanding will ensure that there is sufficient capacity to store used firewater resulting from external areas, following a full discharge of the contents of the firewater tank (with specific capacities to be confirmed following detailed design of the drainage systems). Taking this into consideration, the full volume of the firewater tank will be able to be contained within the site surface water drainage systems and site kerbing.
2. The surface water attenuation pond is expected to be lined and will be designed as a water retaining structure, thereby preventing the release of any contamination should the surface water attenuation pond be required to retain used firewater.

In addition to containment of fire water within the attenuation pond, in the event that there is a fire within the waste bunker of waste reception area, the bunker will provide fire water containment. Furthermore, the waste water pit will provide containment of fire water within process areas.

Measures to prevent the discharge of contaminated firewater off-site are presented in Appendix A.8 (Indicative Firewater Storage and Containment). An isolation valve will prohibit the discharge of contaminated firewater from the site surface drainage systems. The water used for firefighting will be sampled and analysed to identify whether it is suitable to be used as process water or suitable for discharge offsite, or if treatment/disposal is required. If the firewater is considered to be contaminated, it will be transferred off-site, via tanker, to a suitably licensed waste management facility.

A plan showing the proposed landscaping to surround the site (which shows the locations of natural and unmade ground surrounding the Facility) is presented in Appendix A.9 of this report.

The waste bunker will be design and constructed as a water retaining structure in accordance with BS EN 1992-3. This will protect against the leak of contaminated firewater from the bunker and minimise the risk of contamination of groundwater in the event of a fire within the bunker.

Drainage systems will be designed for the prevention of flooding of equipment. Fire water retention at the Facility will be accomplished through the installation of one or a combination of:

- waste bunker;
- process water tank/pit;
- floor drains/floor trenches;
- surface water drainage system (including attenuation storage);
- areas of hardstanding and kerbs for containing or directing drainage; and/or
- pits, sumps, and sump pumps.

It is anticipated that the provisions for drainage and any associated drainage facilities will be sized to accommodate the concurrent flow due to operation of the following components (in accordance with NFPA 820):

- the spill of the largest single container of any flammable or combustible liquids in the area, where the bund around oil tanks should be large enough to contain the oil and the water from suppression systems;
- the maximum expected number of fire hose lines (31.5 L/sec (500 gal/min) minimum) operating for a minimum of 10 minutes (i.e., firewater resulting from all hoses operating at once for at least 10 minutes); and
- the maximum design discharge of (maximum amount of firewater resulting from) fixed fire suppression systems operating for a minimum of 10 minutes (fixed fire suppression systems include sprinklers and water cannons).

There are three different types of firewater flows which will be required to be contained in the event of a fire:

1. Firewater resulting from treating fires in the bunker and tipping hall area. Firewater will be routed to the bunker which is watertight and hence can contain large amounts of firewater. The total below-ground volume of the bunker will be approximately 5,000 m³, however, it is acknowledged that the containment capacity will be reduced by the waste stored within the bunker.
2. Firewater from inside any other process building. This is expected to be a rare event, and the quantities of firewater will be small. This drainage will be contained, to prevent contaminated water discharging off-site. Whilst it is subject to detailed design, it is anticipated that the wastewater pit (process water pit) will have a capacity of approximately 50 m³.
 - Under normal operation, process effluents will be re-used in the process and only temporarily stored within the wastewater pit prior to reuse. Therefore, at any one time, there will only be a small amount of process effluent being stored within the wastewater pit. In the unlikely event that excess process effluents are generated (e.g., resulting from emptying the boilers), these will either be discharged to sewer in accordance with a Trade Effluent Consent or tankered offsite. Therefore, large quantities of process effluent are not likely to be stored within the wastewater pit at any one time. Emptying of any excess process effluents offsite will be co-ordinated with periods of planned maintenance, as part of the documented management systems in place at the site. This will ensure that when excess process effluents are generated (e.g., during maintenance activities), they are not stored for significant periods of time, and they are removed in a timely manner. Taking the above into consideration, it is considered that the process drainage system (including the wastewater pit) will have sufficient capacity to store the small quantities of firewater that would be generated as a result of fires in process areas at the site. This capacity will be maintained through regular emptying of the wastewater pit as part of planned maintenance procedures at the site.
3. Firewater from outside any building – will be contained in the attenuation pond.

16 During and after an incident

16.1 Dealing with issues during a fire

Documented emergency response procedures will be developed during the construction and commissioning phase of the Facility. The emergency procedures will include, but not be limited to:

- fire identification and reporting procedures;
- an evacuation plan;
- emergency communication procedures;
- responding to chemical spillages;
- containment of firewater;
- requirements for diverting incoming waste; and
- notification of any adjacent residential properties and businesses which may be impacted by the incident.

The effectiveness of the emergency response procedures will be reviewed following any emergency incidents on-site. Following an emergency incident, the procedures will be updated if required, and staff trained in the updated procedures.

A copy of the emergency procedures will be maintained at the gate house, or other suitable location, and may include the fire system mimic panel to allow co-ordination of the emergency response to a fire in the event that the main offices are unavailable.

On a periodic basis, testing of the emergency procedures will be undertaken. The intention of the testing is to verify that all staff and contractors are aware of the emergency procedures. Following all tests, the implementation of the procedures will be reviewed. If appropriate, the procedures will be amended, or additional training provided to all staff and contractors.

In the event of an incident resulting in the Facility not being capable to receive waste, waste deliveries will be stopped or diverted to a suitably licensed alternative waste management facility. Deliveries of waste will not be recommenced until it has been deemed safe for waste processing activities to be restarted following the incident. During a complete shutdown, the fire detection systems will remain operational.

16.2 Notifying residents and businesses

The Facility will be operated in accordance with an Environmental Management System (EMS) certified to the ISO 14001 standard. The EMS will include procedures for the response to and documentation of emergency situations. A documented emergency response procedures will be developed which will detail specific actions which must be carried out in the event of a fire.

Depending on the nature and scale of any incidents, it may be necessary to notify local residents and adjacent businesses of the incident. Prior to commencement of operation of the Facility, and as part of the development of the documented management systems associated with the operation of the Facility, suitable external communication procedures will be developed and implemented.

In the event of a significant fire, the EA will be notified as soon as practically possible. Following any fire incidents, the FSM will advise the EA what remedial measures or actions have been taken to prevent any further incidents.

16.3 Clearing and decontamination after a fire

Following a fire which requires the presence of the emergency services; materials, building structures, furnishings, vehicles, equipment and raw materials could be damaged. Once the fire has been fully extinguished and the emergency services given approval to enter the Facility, an assessment will be undertaken by the management team for the Facility, insurance assessors, structural engineers and fire damage/salvage specialists to assess the extent of the damage.

Once a full inventory of the damage and equipment has been completed under the strict supervision of specialist structural engineers, any building or structure will be made safe. Severely damaged equipment or building materials will be removed from site by a licenced waste/scrap company. Building structures that are deemed safe will be cleaned, as necessary.

Waste within the bunker which is not suitable to be incinerated will be backloaded into HGV's and removed from site by a licenced waste carrier. Affected areas will be cleaned and washed before equipment and structural repairs will take place.

16.4 Making the site operational after a fire

If there was a significant fire requiring a full shutdown of the Facility, the Facility would not restart operations until the relevant regulatory authorities (Fire Service, Health and Safety Executive, Environment Agency, etc.), as well as the fire risk insurers, advised that it was safe to do so.

Records will be maintained of the following:

- fire incidents including post-incident investigation;
- feedstock management;
- training of site operatives;
- site inspections and monitoring;
- maintenance activities;
- testing of firefighting equipment; and
- complaints.

Records will be maintained in accordance with the requirements of the EP and any documented management systems.

Appendices

A Plans and Drawings

- A.1 Site Location Plan
- A.2 Site Layout Plan
- A.3 Materials and Waste Storage Areas Plan
- A.4 Access Points Around the Perimeter to Assist Fire-Fighting
- A.5 Indicative Locations of Fire Hydrants
- A.6 Indicative Locations of Fire Walls
- A.7 Indicative location of quarantine area
- A.8 Fire Receptor Plan
- A.9 Areas of natural or unmade ground
- A.10 Indicative Firewater Storage and Containment

B Wind roses from Gravesend Broadness meteorological station

ENGINEERING  CONSULTING

FICHTNER

Consulting Engineers Limited

Kingsgate (Floor 3), Wellington Road North,
Stockport, Cheshire, SK4 1LW,
United Kingdom

t: +44 (0)161 476 0032

f: +44 (0)161 474 0618

www.fichtner.co.uk