



Cambois Data Centre Campus

Enabling Works Phase A

Phase A Addendum to Proposed Drainage Strategy

Document Ref. 4.4, Rev 01

Cambois Data Centre Campus

Addendum to Proposed Drainage Strategy – Enabling Works Phase A

Renaissance Land Limited




Job No: 1043152
Doc ref: NCL1-RMAPA-STE-UG-RP-C-00-02
Revision: P01
Revision date: 25 April 2025

Project title	Cambois Data Centre Campus	Job number
Report title	Addendum to Proposed Drainage Strategy – Enabling Works Phase A	1043152

Document revision history

Revision ref	Issue date	Purpose of issue / description of revision
P01	25 April 2025	Issue for RMA Submission

Document validation (latest issue)

23/04/2025	23/04/2025	23/04/2025
X 	X 	X 
Principal author	Checked by	Verified by
Signed by: Barrie O'Neill-Williams	Signed by: d.dungworth	Signed by: d.dungworth

© Cundall Johnston & Partners LLP ("Cundall") owns the copyright in this report and it has been written for the sole and confidential use of Renaissance Land Limited. It must not be reproduced in whole or in part or relied upon by any third party for any use whatsoever without the express written authorisation of Cundall. If any third party whatsoever comes into possession of this report, they rely on it at their own risk and Cundall accepts no duty or responsibility (including in negligence) to any such third party.

Executive summary

This document outlines the surface water drainage strategy for the enabling works Phase A on Cambois Data Centre Campus. This is an addendum to “Cambois Data Centre Campus – Drainage Strategy – Technical Document 4.13 Rev 01”

In summary - three platforms are proposed in the enabling works, and they discharge surface through filter drains to a pond. This pond discharges to Cow Gut at less than greenfield runoff for the equivalent catchment, and this does not increase flood risk to Cow Gut.

The level of treatment to the surface water drainage is sufficient for the proposed land use.

Contents

1.0	Introduction	2
1.1	LLFA Conditions	2
2.0	The Site	5
3.0	Existing Drainage	7
3.1	Existing Watercourse	7
3.2	Existing Off-Site inflow	8
4.0	Proposed Drainage	16
4.1	Full Site	16
4.2	Enabling Works Phase A	17
4.3	Enabling Works Drainage Summary	35
Appendices		37
Appendix A	Existing Drainage Plan	37
Appendix B	Proposed Drainage Plan	38
Appendix C	Proposed Details	39
Appendix D	Drainage Phasing	40
Appendix E	Impermeable Area Plan	41
Appendix F	Exceedance Flows	42
Appendix G	Greenfield Runoff Calculation	43
Appendix H	Infodrainage Calculations	44

1.0

Introduction

1.0 Introduction

This document outlines the drainage strategy for the enabling works to phase A of Cambois Data Centre Campus. For the proposed drainage strategy for Cambois Data Centre Campus refer to Drainage Strategy (Revision 01) – Technical Document 4.13, issued in January 2025.

This phase of work is to enable the site ahead of the main construction.

Part of the enabling works drainage is temporary in nature and expected to be in place for a period of approximately 1 year. It should be noted that some of the permanent drainage to the project will be constructed as part of the enabling works – most notably the southern pond that discharges to Cow Gut.

The enabling works drainage consists of;

- The permanent southern pond that discharges to Cow Gut
- A length of permanent buried drainage that connects the pond to the relevant enabling works platforms
- Enabling works drainage to three areas (DC1 and DC2 piling Mat, Substation Platform and the Construction Laydown Platform). This drainage will not form part of the final permanent drainage regime.
- Works to complete the Cow Gut Diversion

The contractor will submit a separate construction phase surface water management plan for the construction works.

1.1 LLFA Conditions

This report aims to discharge the following conditions relevant to the development;

Condition	Comment
33. Prior to commencement, including site set up works, a plan shall be submitted to and approved by the Local Planning Authority in writing that details the drainage phasing plan, including a build order shall be provided. The development shall then be carried out in accordance with these agreed details.	Please refer to Figure 4-1 and Appendix D for the proposed phasing to the development
34 Prior to commencement of development, including clearance works, a scheme to dispose of surface water from the development shall be submitted to and approved by the Local Planning Authority in writing. This scheme shall:	This report outlines the surface water drainage strategy to the enabling works phase A of the development.
34 A. Restrict discharge from the development to the Cow Gut and to the Maw Burn as per section 5.6 of Document 1043152 NCL1-DCZZ-STE-UG-RP-C-00-01 P rev V02 by Cundall for all rainfall events up to and including the 1 in 100 year + climate change storm event, unless otherwise agreed by LLFA and the Local Planning Authority.	Only discharge to Cow Gut is demonstrated for enabling works phase A – There is no discharge to Maw Burn for this phase. Flows are restricted to 1:1 year greenfield runoff for the equivalent catchment for this phase of works, which is less than in the original strategy. This is discussed in section 4.2.5. Flows are summarised in Table 4-3
34 B. Provide details of attenuation on site for the 1 in 100 year plus climate change event, at the time of submission of the reserved matters.	The enabling works phase A attenuation details are provided in the drainage strategy appendix C (drainage detail sheet 3 – Pond)

34 C. Provide cross sections of all SuDS features	SuDS features relevant to the enabling works phase A are provided in the drainage strategy appendix C (drainage detail sheet 3 – Pond)
34 D. Provide a cross section of the flow control	The enabling works phase A flow control is provided in the drainage strategy appendix C (drainage detail sheet 1)
34 E. Incorporate vegetated sustainable drainage techniques throughout the development wherever possible and practicable, justification for alternatives should be by means of a 3 viability assessment in the event vegetated sustainable drainage systems are not proposed.	The southern pond that discharges to Cow Gut is vegetated, with details provided in Appendix C (drainage detail sheet 3 – Pond)
34 F. Provide full hydraulic modelling calculations	Hydraulic modelling calculations for the enabling works phase A are provided in appendix H
34 G. Provide an exceedance flow route plan	The enabling works phase A exceedance flow route plan is provided in section 4.2.6 and appendix F
34 H. Confirm how the basins will be accessed for maintenance	Pond maintenance access is discussed in section 4.2.8 and the strategy illustrated in Figure 4-17
39 Prior to commencement of any works on site, including clearance works, details of the disposal of surface water from the development through the construction phase shall be submitted to and agreed with the Local Planning Authority in writing. The development shall then be carried out in accordance with these agreed details throughout the construction phase	Section 4.2.11 provides an outline of what will be included in the construction phase surface water management plan that will be submitted by the contractor.

Table 1-1 LLFA Conditions

2.0

The Site

2.0 The Site

The site layout for the enabling works Phase A is shown in Figure 2-1.




Figure 2-1: Enabling Works Site Layout

The enabling works phase A consists of a number of zones, described below;

- Zone A – this consists of two footprints under what will become the Phase 1 buildings. During the enabling works, this zone consists of a piling platform.
- Zone B – During the enabling works, obstacles will be removed and the ground re-instated for the phase 1 works.
- Zone C – This zone will be the Phase 1 substation. During enabling works the existing ground will be turned over to natural ground level and obstacles removed. A structural platform will be constructed in preparation for the phase 1 substation
- Zone D – During the enabling works, obstacles will be removed and an earthworks platform prepared for the phase 1 works. Inside this zone there is the footprint for the phase 1 construction compound – during the enabling works a structural earthworks platform will be constructed in preparation for the phase 1 construction compound.
- Zone E – The permanent pond discharging to Cow Gut will be installed in Zone E during the enabling works phase.
- Zone F – In this zone mounds will be removed in preparation of the phase 1 buried utility installation.

3.0

Existing Drainage

3.0 Existing Drainage

Existing drainage is discussed in detail in the report Cambois Data Centre Campus – Drainage Strategy – Technical Document 4.13. In this report, existing drainage in the enabling works boundary is discussed.

3.1 Existing Watercourse

Two watercourses cross the Site, the larger Cow Gut running from west to the southeast and Maw Burn, running from the northwest of the Site to the eastern boundary. Both watercourse discharge into the sea within 300m of the Site, with Cow Gut discharging into Blyth Estuary and Maw Burn to the sea at Cambois Beach.

The Maw burn collects surface water from a relatively small area of the site, it predominantly conveys surface water from the north-west to the eastern outfall.

The Cow Gut has historically been used for the collection of storm water for the majority of the Site. According to records available, the culverted section of Cow Gut downstream of the site boundary is a 900mm pipe, followed by a 1200mm inverted siphon with a drop in level of approximately 3m in the siphon.

Figure 3-1 shows the key existing drainage features on site, as well as features that are to be removed during the enabling works phase A (coloured red).




Figure 3-1: Enabling Works Phase A - Existing Drainage Plan

3.2 Existing Off-Site inflow

The enabling works drainage is intended to discharge to Cow Gut.

In order to determine the existing flow in Cow Gut as it discharges from the current site, the existing upstream and on-site flow rate into Cow Gut needs to be established.

3.2.1 Cow Gut Upstream Catchment

LIDAR composite digital terrain model data was downloaded from the Environment Agency website and imported into QGIS software. The LIDAR data, downloaded as 4 .TIF files, were converted to vector shape files and the GRASS plugin was used to create watershed routes in the existing surface water catchments in and around the site. Analysing the existing topographical survey of the Site, some catchment area extents within QGIS were amended to account for culvert routes, blocking structures and the project Site boundary to improve watershed route accuracy and discount any area within project boundary extents.

The Maw Burn and Cow Gut both have contributing catchments upstream of the proposed development. The extent of these can be seen in Figure 3-2. The Maw Burn upstream catchment is shown in Yellow and the Cow Gut upstream catchment is shown in Blue.



Figure 3-2: Watercourse Catchment Areas

These outcome catchment areas were grouped and quantified to provide a total off-site catchment area draining to the Site, of 52.65 ha for Cow Gut and 47.34 ha for Maw Burn.

3.2.2 Cow Gut On-Site Catchment

Figure 3-3 shows the enabling works on site catchment areas discharging to Cow Gut. The total existing on-site catchment to Cow Gut is 76.6Ha.




Figure 3-3: Enabling Works on site catchment areas discharging to Cow Gut

3.2.3 Determination of existing discharge flows to Cow Gut

A model has been developed in Infodrainage to determine the existing (baseline) flows that discharge to Cow Gut at the downstream boundary of the site.

The FEH Web Service was used to download FEH22 catchment rainfall data, and this was input into Infodrainage, as shown in Figure 3-4.




Figure 3-4: FEH data applied to catchments in Infodrainage

A model has been produced for the discharge from Cow Gut from the site boundary. Upstream and on-site catchment areas have been assigned to discharge to the model at the downstream site boundary.




Figure 3-5: Extent of baseline model to determine Cow Gut existing flows

Figure 3-6 shows a plan view of the infodrainage model. The upstream catchment of 52.65Ha and on-site catchment of 76.6Ha (also refer to Figure 3-3) are highlighted. Two smaller catchments downstream of the site, as showing in Figure 3-3 are also modelled. Record information has been used to model the pipework to the discharge to the sea (refer to Figure 3-9 and Figure 3-10).




Figure 3-6: Infodrainage Model - Plan




Figure 3-7: Upstream catchment applied to Cow Gut




Figure 3-8: On site catchment to Cow Gut




Figure 3-9: Existing off site culvert




Figure 3-10: Pipework long section

The catchments generate a hydrograph for each storm, see Figure 3-11 for an example.




Figure 3-11: Hydrograph for on-site catchment - 100 year +45% climate change 480 minute winter storm

Cow Gut discharges to the south of the Site via a concrete headwall with an invert level of 1.65mAOD. The connection to the sea includes an inverted siphon. The invert level of Cow Gut at the limit of the Site is lower than the current Mean High Water Springs (MHWS) of 2.52mAOD and therefore the tidal boundary condition shall restrict flows. Table 3-1 indicates the increase in sea level allowance for the Northumbria River basin in mm for the higher central and upper end events. The higher central indicates a 70th percentile projection and upper end a 95th percentile. For tidal consideration, an overall design life has been assumed of 60 years, so the 2085 scenario has been considered. The higher central allowance gives an increase in sea level of 0.588m and MHWS of 3.108m. As a conservative assumption for, this level has been applied as the downstream boundary condition at the outfall in the drainage model for the duration of the storm (refer to Figure 3-12 for the modelled submerged outfall level).

Allowance	2000 to 2035 (mm)	2036 to 2065 (mm)	2066 to 2095 (mm)	2096 to 2125 (mm)
Higher central	4.6	7.5	10.1	11.2
Upper end	5.8	10	14.3	16.5

Table 3-1: Sea level allowances for the Northumbria River basin district for each epoch in mm for each year (based on a 1981 to 2000 baseline). Source: Environment Agency




Figure 3-12: Submerged outfall

A summary of the base model results is provided in Table 3-2

Return Period (Years)	Maximum Flow (l/s)	Flooded Volume at existing watercourse (m ³)	Comments
1	368.7	None	
10	658.6	None	
100	1157	None	
100 + 45% Allowance for climate change	1787	604m ³	This is the total volume flooding from the open channel to the Cow Gut Diversion and the flooded volume at the inlet manhole where Cow Gut Discharges from the site

Table 3-2: Summary of existing discharge flows to Cow Gut

4.0

Proposed Drainage

4.0 Proposed Drainage

4.1 Full Site

The full site drainage strategy was submitted for outline planning. Refer to Cambois Data Centre Campus – Drainage Strategy – Technical Document 4.13 for the full site drainage strategy. This document outlines the strategy for the enabling works phase A only.

Figure 4-1 shows the phasing strategy for the site and the boundary to the phase A enabling works. It also highlights the permanent drainage that will be constructed as part of the enabling works package.




Figure 4-1: Drainage Phasing

As illustrated in the figure, the southern pond that discharges to Cow Gut will be constructed as part of the enabling works, as well as a length of pipework that extends to the phase 1 buildings to the west of the pond.

4.2 Enabling Works Phase A

4.2.1 Enabling Works Drainage Layout

Refer to drawing NCL1-RMAPA-STE-XX-DR-C-01-33, as well as Figure 4-2 for the enabling works phase A drainage layout.




Figure 4-2: Phase A enabling Works Drainage Layout

A summary of the key features is illustrated in Figure 4-2, and described in the following paragraphs.

4.2.2 Works to existing Cow Gut Diversion

As part of the enabling package, works will be carried out to complete the Cow Gut Diversion.

Site investigation surveys indicate that the inlet from Cow Gut to the Cow Gut Diversion were not completed in the previous project. As part of the enabling package, the inlet is to be connected to the diversion. A snip of these works from the drainage layout drawing NCL1-RMAPA-STE-XX-DR-C-01-33 is presented in Figure 4-3.




Figure 4-3: Works to the Inlet to Cow Gut Diversion

Site investigation surveys also indicate that the most downstream ditch to the Cow Gut Diversion was not completed. This will be completed as part of the enabling works package. A snip from the drainage layout drawing for these works is presented in Figure 4-4.




Figure 4-4: Works to the most downstream ditch to the Cow Gut Diversion

4.2.2.1 Permanent Storm Drainage Pipework

A length of the permanent works drainage will be constructed as part of the enabling works package, as highlighted in Figure 4-2. This drainage allows the enabling works drainage to the piling platform in Zone A, the substation platform in Zone C and the Construction Laydown Area in Zone D to discharge to the Southern Pond.

Where appropriate, stubs of pipework will be installed to allow for the connection of future phases.

4.2.2.2 Zone A – Drainage to piling Platform

Figure 4-5 shows a plan of the drainage to the piling platform. Inside this zone, perforated pipework inside a filter drain is proposed to drain the platform (Figure 4-6). This drainage is temporary in nature and will not form part of the permanent site drainage. It does discharge into the permanent drainage pipework to be constructed as part of the enabling works phase A package.




Figure 4-5: Zone A Drainage to Piling Platform




Figure 4-6: Proposed Filter Drain Detail

4.2.2.3 Zone C – Drainage to Substation Platform

Figure 4-7 shows the plan arrangement of the substation platform drainage. As with Zone A, this drainage is proposed to consist of filter drains to the platform and will not form part of the permanent works. Also, as per Zone A, the substation enabling works drainage will tie into the permanent works drainage that will be installed with the enabling works.




Figure 4-7: Zone C - Drainage to substation

4.2.2.4 Drainage to construction laydown platform

Figure 4-8 shows the plan arrangement of the construction laydown platform drainage. As with Zone A and C, this drainage is proposed to consist of filter drains to the platform and will not form part of the permanent works drainage. Also, as per Zone A and C, the construction laydown enabling works drainage will tie into the permanent works drainage that will be installed with the enabling works.




Figure 4-8: Drainage to construction laydown platform

4.2.2.5 Pond

The permanent works pond that discharges to Cow Gut will be installed as part of the enabling works package. Figure 4-9 shows the pond plan layout. As per the plan, the pond has a sediment forebay to allow the sediment to be captured from a defined area within the ponds for removal. The pond has a permanent water level, and this combined with the sediment forebay allows for the first flush to be treated within the pond.




Figure 4-9: Pond Layout – Plan

Figure 4-10 shows a section to the pond inlet. As per the section, the pond has a permanent water level of 3.800m. During a 1 in 10 year storm, this water level will increase to 130mm during the enabling works phase. Because the permanent pond is being constructed in the enabling works phase, and the enabling works phase catchment is small compared to the full site, the pond attenuation volume is not highly utilised.

The pond has a shallow aquatic bench to its perimeter. This enables a zone for mass planting to provide a level of treatment to surface water runoff. The pond is clay lined.




Figure 4-10: Section at Pond Inlet

In the middle of the pond, there is a submerged berm to separate the sediment forebay from the rest of the pond (Figure 4-11). This is to be planted.




Figure 4-11: Section at pond berm

The pond outfalls to a flow control manhole. The flow control manhole is discussed in more detail in section 4.2.2.6. This manhole then discharges to the existing Cow Gut watercourse, as shown in Figure 4-12




Figure 4-12: Section at pond outlet

Refer to NCL1-RMAPA-STE-XX-DR-C-05-05, Enabling Works – Phase A Drainage Details Sheet 3 for the pond detail drawing.

4.2.2.6 Flow Control Manhole

There is a manhole to the outlet to the pond, where an orifice plate will be installed to restrict flow during the enabling works phase to greenfield runoff. Figure 4-13 and Figure 4-14 show the manhole in plan and section.

The manhole is to be constructed to allow the plate to be removed as the works progress and replaced with alternative flow controls to suit the relevant phase of works. The manhole cover slab is to be constructed at ground level to enable removal of the slab to allow the flow control to be adjusted as required.




Figure 4-13: Flow Control Manhole - Plan




Figure 4-14: Flow Control Manhole – Section

4.2.2.7 Silt Fence

As part of the enabling works, a silt fence will be constructed where there is runoff from the enabling works platforms to Cow Gut. This is to capture sediment from the enabling works prior to discharge to Cow Gut.

4.2.2.8 Filter strip to emergency access route

A 5m wide filter strip is provided to the temporary emergency access route to the north of the enabling works, to provide a level of treatment to the surface water runoff prior to discharge to Maw Burn.

4.2.3 Enabling Works Design Return Period

The enabling works drainage is temporary in nature, and expected to be in place for a period of approximately 1 year. As such, a design return period of 1 in 10 years for the enabling works drainage has been selected. The pipework has been designed to ensure there is no flooding to the enabling works drainage in this return period.

4.2.4 Infiltration

Infiltration testing was undertaken as part of planning application 21/000818/FULES. Testing concluded that the ground was impermeable ($<10^{-6}$ i.e. Not viable) and offered minimal infiltration potential. No further infiltration testing has been commissions as part of ground investigation works as the geotechnical investigations determined the entire site was underlain with impermeable clay resulting in ineffective infiltration rates. Unless further testing contradicts previous results, this has been discounted.

Summary of acceptable infiltration rates for development surface water drainage (m/sec)		
		Tests to undertake
$> 10^{-6}$	Appropriate for soakaways	Infiltration tests to BRE 365 standards and information of the ground conditions and groundwater levels.
$= 10^{-6}$	Borderline	Infiltration tests to BRE 365 standards, plus a comprehensive ground investigation report, with groundwater levels. Subject to approval
$< 10^{-6}$	Not Viable	Seek alternative means of disposal of surface water

Table 4-1: Summary of acceptable infiltration rates

4.2.5 Enabling Works Flow Restriction

For the enabling works phase A, discharge from the pond to Cow Gut has been limited to greenfield runoff for the equivalent return period event.

Refer to Figure 4-15 for the impermeable area plan (gravel platforms) for the enabling works, showing that the catchment to the pond is 10.2 Ha.




Figure 4-15: Impermeable Area Plan

Greenfield runoff for the site has been determined to be 37.79 l/s for a 1 in 1 year return and 43.94 l/s for Qbar (Refer to Appendix for HR Wallingford Greenfield Runoff Rate Estimation).

A 150mm orifice plate on the flow control manhole is to be constructed as part of the enabling works, and this limits the flow to 29.7 l/s for the critical 1 in 10 year storm.

Although the enabling works drainage has been designed for a 1 in 10 year storm, a check on the pond outflow rate has been carried out on the 1 in 100 year +45% climate change storm. During a 1 in 100 +45% allowance for climate change storm, the discharge from the pond is limited to 37.2 l/s, which is less than both the 1 in 1 year and Qbar greenfield runoff for the catchment area.

4.2.6 Exceedance flows

Figure 4-16 shows the overland exceedance flow route for the enabling works phase. New temporary cut off trenches have been formed to the north of the enabling works area to capture overland flow. Areas that have flow going to Maw Burn and Cow Gut pre development maintain an overland flow route to their respective watercourse during the enabling works phase A.




Figure 4-16: Exceedance flow route during enabling works

4.2.7 Surface Water Treatment

Water treatment to the full site drainage is as per Cambois Data Centre Campus – Drainage Strategy – Technical Document 4.13.

The Simple Index Approach as per the SuDS manual has been used to verify the water treatment regime during the enabling works phase.

For the construction phase of these works, the contractor will submit a separate construction phase surface water management plan for the construction works surface water treatment.

4.2.7.1 Platforms in Zones A, C and D

Platforms in Zones A, C and D discharge through a filter drain through a gravity pipe network to a pond. This pond then discharges to Cow Gut.

During the enabling works phase, the permanent southern pond will be constructed, and this provides a mitigation index of 0.7 Total Suspended Solids, 0.7 Metals and 0.5 Hydrocarbons as defined in the SuDS manual Simple Index Approach.

Outside of construction works, these platforms are not trafficked. However, to check the level of treatment, a land use description of “Low Traffic Roads” has been selected.

As per Table 4-2, there is a sufficient level of treatment provided to these platforms.

Pollution Hazard Index for the Runoff Area discharging to the proposed SuDS Scheme				
Runoff Area Land Use Description	Hazard Level	Pollution Hazard Indices		
		Suspended Solids	Metals	Hydrocarbons
Low traffic roads (< 300 traffic movements/day)	Low	0.5	0.4	0.4
Pollution Mitigation Index for the proposed SuDS components				
SuDS Component Description	Pollution Hazard Indices			
	Suspended Solids	Metals	Hydrocarbons	
Filter drain (where the trench is not designed as an infiltration component)	0.4	0.4	0.4	
Pond or Wetland	0.7	0.7	0.5	
Aggregated Surface Water Pollution Mitigation Index	0.75	0.75	0.65	
Sufficiency of Pollution Mitigation Indices				
	Suspended Solids	Metals	Hydrocarbons	
	Sufficient	Sufficient	Sufficient	

Table 4-2 Surface Water Treatment to Platforms in Zones A, C and D

4.2.7.2 Emergency Access Road

A new emergency access route is proposed to the north western side of the site. Surface water from this road discharges to Maw Burn via a filter strip.

This road is expected to have extremely low traffic – it is for emergency access only and is expected to only have a few trips over its life. For this purpose a filter strip with mitigation indices of 0.4 for suspended solids, 0.4 for metals and 0.5 for hydrocarbons is proposed for treatment and is considered sufficient for this land use description.

4.2.8 Maintenance

Maintenance to the full site drainage is as per Cambois Data Centre Campus – Drainage Strategy – Technical Document 4.13.

For the construction phase, the contractor will submit a separate construction phase surface water management plan for the construction works maintenance.

The proposed pond arrangement has a 10m wide, flat zone to the top for maintenance access, and the side slopes are limited to 1 in 5 down to a dry bench.




Figure 4-17 Pond Maintenance Access

4.2.9 Modelling features

A model has been prepared in infodrainage for the enabling works surface water drainage. A plan is shown in Figure 4-18.



Figure 4-18: Enabling works model - plan

The model consists of;

- Surface water drainage to the proposed building piling platform and substation platform
- The pond discharging to Cow Gut
- The outfall from the pond to the sea
 - This includes on site and off site catchments to the cow-gut diversion.

These are discussed separately below.

4.2.9.1 Surface water drainage to piling and substation platform

The surface water drainage to the piling platform is modelled as a series of soakaways discharging to buried pipework. Figure 4-19 shows a typical plan arrangement, and Figure 4-20 shows the model properties of a typical soakaway.




Figure 4-19: Piling Platform Drainage Model – Plan




Figure 4-20: Typical Soakaway Model Properties

4.2.9.2 Pond discharging to cow gut

As part of the enabling works package, the full pond in the South-East of the site, discharging to Cow Gut, is proposed to be constructed. The modelled details of the pond are illustrated in Figure 4-21 and Figure 4-22. The pond outfalls to a manhole with a 150mm orifice to limit the discharge of the enabling works phase to Q_{bar}. The orifice plate model properties are shown in Figure 4-23.




Figure 4-21: Pond layout in model – Plan




Figure 4-22: Pond Model Properties




Figure 4-23: Pond outfall - orifice properties

4.2.9.3 Outfall from the pond to the sea

The discharge route from the pond is modelled to its discharge to the sea, as indicated in Figure 4-24.




Figure 4-24: Discharge from pond to the sea - long section in infodrainage model

The greenfield catchment to cow gut is discharged to the network using two catchment areas – one for the on site and one for the offsite catchment. Refer to Figure 4-15 and 1043152-C-SK-EW002 in appendix F for the details of the on-site catchment. In summary, 10.2ha discharges to the pond and 66.4 ha is discharged to Cow Gut as an on-site catchment. The offsite catchment is 52.65 ha as per Figure 3-2.




Figure 4-25: On and Off site contribution areas to catchment

The on and off site catchment properties are shown in Figure 4-26 and Figure 4-27, and a typical hydrograph shown in Figure 4-28.

On Site Catchment

Name: On Site Catchment

Runoff | Pollution | Advanced | Rainwater Tank

Area (ha): 66.40

Preliminary Sizing

Volumetric Runoff Coefficient: 0.750

Percentage Impervious (%): 100

Time of Concentration (mins): 5

Dynamic Sizing

Runoff Method: FEH

Version: 1999

Site Location: GB 430100 584200 NZ 30100 84200

Areal Reduction Factor: 1.000

SAAR (mm): 649.0

CWI: 95.820

SPRHOST (%): 39.61

DPSBAR (1:X): 69.444

DPLBAR (m): 970.000

PROPWET: 0.330

URBEXT: 2000

URBEXT: 0.0049

URBCONC: 0.00000

Base Flow Details

LAG (mins): 0

Base Flow (L/s): 0.0

OK Cancel Apply

Name Help

Figure 4-26: On site catchment properties

Off Site Catchment

Name: Off Site Catchment

Runoff | Pollution | Advanced | Rainwater Tank

Area (ha): 52.65

Preliminary Sizing

Volumetric Runoff Coefficient: 0.750

Percentage Impervious (%): 100

Time of Concentration (mins): 5

Dynamic Sizing

Runoff Method: FEH

Version: 1999

Site Location: GB 430100 584200 NZ 30100 84200

Areal Reduction Factor: 1.000

SAAR (mm): 649.0

CWI: 95.820

SPRHOST (%): 39.61

DPSBAR (1:X): 69.444

DPLBAR (m): 970.000

PROPWET: 0.330

URBEXT: 2000

URBEXT: 0.0049

URBCONC: 0.00000

Base Flow Details

LAG (mins): 0

Base Flow (L/s): 0.0

OK Cancel Apply

Name Help

Figure 4-27: Off site catchment properties




Figure 4-28: Typical catchment hydrograph

These discharge to a pond modelled to represent the lower end of the cow gut diversion works, and then this discharges to the downstream network – see Figure 4-29




Figure 4-29: Plan of cow gut diversion connection to downstream pipework

4.2.10 Modelling results

Table 4-3 provides a summary of the stormwater modelling results for the enabling works drainage, and a commentary where appropriate.

Return Period (Years)	Greenfield Runoff (l/s)	Maximum Flow From Pond (l/s)	Maximum Increase in Water Depth in Pond (m)	Flooding in Network with comments
1 in 1	37.79	27.1	0.071	No Flooding
1 in 10	43.94 (Taken as Qbar)	29.7	0.130	No Flooding
1 in 100	91.39	33.2	0.229	Flooding at enabling works platforms. This is acceptable for these works. Very low chance of this occurring during the expected 1 year life of the enabling works drainage. No flooding to the Cow Gut watercourse.
1 in 100 plus 45% climate change	133.29 (Taken by increasing 1 in 100 year by 45%)	37.2	0.359	Note that climate change uplift is not relevant to the expected 1 year life of the enabling works drainage. As per 1 in 100 year storm – acceptable flooding to enabling works platform. There is 370m ³ of flooding to the Cow Gut Watercourse in this scenario. In the baseline scenario (ie no development to the site), the Cow Gut watercourse floods 604m ³ . Therefore the drainage to the site is a betterment when compared to the baseline.

Table 4-3: Summary of Stormwater Modelling Results

4.2.11 Construction Phase Surface Water Management

The main surface water to dispose of during the construction phase will be surface water runoff during rainfall and dewatering of excavations. The main pollution type will be suspended solids – silt, sediments, “muddy” water. The primary receptor to be protected from the suspended solids will be the surface water feature of Cow Gut.

As part of the Enabling Works Phase A construction phase, additional surface water management will be implemented. The layout and detail of these features will be submitted as part of a Construction Phase Surface Water Management Plan and agreed prior to commencement of the works.

The primary features will be a series of cut off ditches and/or bunds around stock piles and working areas to contain and direct surface water to detention and settlement ponds. Additional measures will be deployed to filter storm water using hay bales and/or filter fabric wrapped gravel bunds within the existing concrete channels and temporary ditches around the site. Silt fences will be added to mitigate sediment running off directly into watercourses. Grip trenches will be used to direct water away from excavations, however dewatering may be required in deeper excavations and these will be pumped to the site features described above for treatment prior to discharge to the Cow Gut. Where existing site drainage features may present an outlet, such as gullies or drains, inlet controls will be provided to intercept flow/sediment.

Features will be designed in line with best practice guides such as:

CIRIA C532 Control of water pollution from construction sites: Guidance for Consultants and Contractors

CIRIA C648 Control of Water Pollution from Linear Construction Projects – Technical Guidance

CIRIA C649 Control of Water Pollution from Linear Construction Projects – Site Guide

CIRIA C741 Environmental Good Practice – Site Guide

CIRIA C753 The SuDS Manual

4.3 Enabling Works Drainage Summary

Surface water drainage is proposed for the enabling works phase A of Cambois Data Centre Campus.

Three platforms discharge through filter drains to a pond. This pond discharges to Cow Gut at less than greenfield runoff for the equivalent catchment, and this does not increase flood risk to Cow Gut.

The level of treatment to the surface water drainage is sufficient for the proposed land use.

Appendices

Appendices

Appendix A Existing Drainage Plan

QTS

**MEP, STRUCTURAL, CIVIL, SECURITY, TECHNOLOGY,
CONTROLS, FIRE & GEOTECHNICAL**

CUNDALL

ARCHITECT

CORGAN

LANDSCAPE



SHEET NOTES

1. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS, ARCHITECTS AND OTHER CONSULTANTS DOCUMENTATION.
2. SOME DRAWINGS MAY NEED TO BE PRINTED IN COLOUR TO PRESERVE INFORMATION INDICATED IN COLOUR ON THE DRAWINGS.
3. DO NOT SCALE, WORK TO FIGURED DIMENSIONS ONLY.
4. ALL DIMENSIONS STATED IN mm UNLESS OTHERWISE NOTED

LEGEND

EXISTING BURIED SURFACE WATER DRAINAGE TO BE RETAINED DURING ENABLING WORKS - SURVEY NEEDED

EXISTING BURIED SURFACE WATER DRAINAGE TO BE RETAINED DURING ENABLING WORKS

EXISTING BURIED SURFACE WATER
DRAINAGE TO BE REMOVED DURING
ENABLING WORKS

AREAS OF SITE NOT INCLUDED WITHIN ENABLING WORKS PACKAGE

 ENABLING WORKS PHASE A
SITE BOUNDARY

SSER CABLE ROUTE
EXCLUSION ZONE/WORKING ZONE

EXISTING OFF-SITE
CULVERTED WATERCOURSE

OUTLINE PLANNING
BOUNDARY

REFER TO CIVIL AND GEOTECHNICAL DRAWINGS :
NCL1-ENA1-STE-XX-DR-C-01-01 EXISTING SERVICES
NCL1-ENA1-STE-XX-DR-C-01-02 EXISTING SITE
CONSTRAINTS
NCL1-DCZZ-XXX-UG-DR-B-01-11 REMEDIATION AND
EARTHWORKS STRATEGY-CONSTRAINTS PLAN

DRAWING ISSUES

KEY PLAN

The map shows the city of Valencia, Spain, with a grid of 32 sampling points labeled S01 through S28. The points are distributed across the city, with a higher density in the central and northern areas. The Mediterranean Sea is visible to the east of the city. The map also shows major roads and urban areas.

PROJECT

CAMBOIS DATA CENTRE CAMPUS

Land at the Former Power Station Site
on the Northern Side of Cambois,
Cambois, Northumberland

DWG. TITLE
ENABLING WORKS - PHASE A
EXISTING SITE DRAINAGE
AND SURVEY SCHEDULE

PROJECT NO: 1043152

DWG. NO:

STATUS: ISSUED FOR REVIEW

SCALE: A0: 1:2000

Appendix B Proposed Drainage Plan

OWNER

QTS

MEP, STRUCTURAL, CIVIL, SECURITY, TECHNOLOGY,
CONTROLS, FIRE & GEOTECHNICAL

CUNDALL

One Carter Lane
London
EC4A 3DF
United Kingdom
www.cundall.com

ARCHITECT

CORGAN

100 Park St
Tottenham
London
N15 4JF
United Kingdom
www.corgan.com

LANDSCAPE

ARCADIS

55 Finchbury Street
City of London
London
EC2M 4BY
United Kingdom
www.arcadis.com

SHEET NOTES

- THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS, ARCHITECTS AND OTHER CONSULTANTS DOCUMENTATION.
- SOME DRAWINGS MAY NEED TO BE PRINTED IN COLOUR TO PRESERVE INFORMATION INDICATED IN COLOUR ON THE DRAWINGS.
- DO NOT SCALE. WORK TO FIGURED DIMENSIONS ONLY.
- ALL DIMENSIONS STATED IN mm UNLESS OTHERWISE NOTED


LEGEND

- EXISTING BURIED SURFACE WATER DRAINAGE TO BE RETAINED DURING ENABLING WORKS - SURVEY NEEDED
- EXISTING BURIED SURFACE WATER DRAINAGE TO BE RETAINED DURING ENABLING WORKS
- EXISTING SURFACE WATER DRAINAGE FEATURES TO BE RETAINED DURING ENABLING WORKS
- PROPOSED SURFACE WATER DRAINAGE - PERMANENT TO SERVE FUTURE PHASE PERMANENT WORKS
- PROPOSED SURFACE WATER DRAINAGE - ENABLING NOTE: ADDITIONAL CONSTRUCTION PHASE DRAINAGE WILL BE REQUIRED (CONTRACTOR DESIGN)
- SILT FENCE
- ENABLING WORKS PHASE A SITE BOUNDARY
- OUTLINE PLANNING BOUNDARY
- AREAS OF SITE NOT INCLUDED WITHIN ENABLING WORKS PACKAGE

Rev	Description	Date	Chk'd	App'd
P01	ISSUE FOR RMA SUBMISSION	25/04/25	YCM	WVW
Rev	Description	Date	Chk'd	App'd

DRAWING ISSUES

KEY PLAN



PROJECT

CAMBOIS DATA CENTRE CAMPUS

Land at the Former Power Station Site
on the Northern Side of Cambois,
Cambois, Northumberland

DWG. TITLE
ENABLING WORKS - PHASE A
DRAINAGE LAYOUT

PROJECT NO:

1043152

DWG. NO:

NCL1-RMAPA-STE-XX-DR-C-01-33

STATUS:

ISSUED FOR
REVIEW

SCALE @ A0:

1:2000

True North

0

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293


294

295


Appendix C Proposed Details

SCHEDULE OF ROCKER PIPE DIMENSIONS.	
PIPE DIA. (mm.)	EFFECTIVE ROCKER LENGTH (m.)
150-600	0.600m
675-750	1.000m
825<	1.250m

SCHEDULE OF MIN. CHAMBER DIMS.	
NOMINAL INTERNAL PIPE DIAMETER OF LARGEST PIPE IN MANHOLE (mm)	MINIMUM NOMINAL INTERNAL DIMENSION OF MANHOLE (mm)
LESS THAN 375mm.	1200
375-450	1350
500-700	1500
750-900	1800
GREATER THAN 900	PIPE DIAMETER + 1200




CROSS SECTION




CROSS SECTION


PRECAST CONCRETE MANHOLE: 3m MAXIMUM DEPTH
SCALE 1:20




PLAN



FILTER DRAIN CATCH PIT
SCALE 1:20




SECTION A-A



SECTION D-D

SECTION E-E



DEEP PRECAST CONCRETE MANHOLE:
FROM 3m TO 6m DEPTH
SCALE 1:20

ORIFICE FLOW CONTROL CHAMBER DETAIL
SCALE 1:20

OWNER

QTS

MEP, STRUCTURAL, CIVIL, SECURITY, TECHNOLOGY,
CONTROLS, FIRE & GEOTECHNICAL

CUNDALL

One Carter Lane
London
EC4A 3ER
United Kingdom
www.cundall.com

ARCHITECT

CORGAN

105 Park St
Temple Barade
London
EC4M 4BY
United Kingdom
www.corgan.com

LANDSCAPE

ARCADIS

80 Fenchurch Street
City of London
London
EC3M 4BY
United Kingdom
www.arcadis.com

SHEET NOTES

1. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS, ARCHITECTS AND OTHER CONSULTANTS DOCUMENTATION.
2. SOME DRAWINGS MAY NEED TO BE PRINTED IN COLOUR TO PRESERVE INFORMATION INDICATED IN COLOUR ON THE DRAWINGS.
3. DO NOT SCALE. WORK TO FIGURED DIMENSIONS ONLY.
4. ALL DIMENSIONS STATED IN mm UNLESS OTHERWISE NOTED

Rev	Description	Date	Chk'd	App'd
P01	ISSUE FOR RMA SUBMISSION	25/04/25		

DRAWING ISSUES

KEY PLAN

S01	S02	S03	S04
S05	S06	S07	S08
S09	S10	S11	S12
S13	S14	S15	S16
S17	S18	S19	S20
S21	S22	S23	S24
S25	S26	S27	S28

PROJECT

**CAMBOIS DATA
CENTRE CAMPUS**

Land at the Former Power Station Site
on the Northern Side of Cambois,
Cambois, Northumberland

DWG. TITLE

ENABLING WORKS - PHASE A

DRAINAGE DETAILS

SHEET 1

PROJECT NO:

1043152

DWG. NO:

NCL1-RMAPA-STE-XX-DR-C-05-03

STATUS:

ISSUED FOR
REVIEW

SCALE @ A0:

AS SHOWN

OWNER

QTS

MEP, STRUCTURAL, CIVIL, SECURITY, TECHNOLOGY,
CONTROLS, FIRE & GEOTECHNICAL

CUNDALL

One Carter Lane
London
EC4A 3ER
United Kingdom
www.cundall.com

ARCHITECT

CORGAN

105 Park St
Tottenham
London
EC2M 4BY
United Kingdom
www.corgan.com


LANDSCAPE

ARCADIS


80 Fenchurch Street
City of London
London
EC3M 4BY
United Kingdom
www.arcadis.com

SHEET NOTES


1. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS, ARCHITECTS AND OTHER CONSULTANTS DOCUMENTATION.
2. SOME DRAWINGS MAY NEED TO BE PRINTED IN COLOUR TO PRESERVE INFORMATION INDICATED IN COLOUR ON THE DRAWINGS.
3. DO NOT SCALE. WORK TO FIGURED DIMENSIONS ONLY.
4. ALL DIMENSIONS STATED IN mm UNLESS OTHERWISE NOTED




PROPOSED CUT OFF TRENCH DETAIL
SCALE 1:20




INDICATIVE CROSS SECTION TO EXTENDED DITCH
AT COW GUT
SCALE 1:20




TYPICAL HEADWALL
WITH FLAP VALVE
SCALE 1:20




DIMENSIONS FOR THE HEADWALL
ARE ALTHON H10C PRODUCT
SPECIFIC. ALTERNATIVE PRODUCTS
CAN BE CONSIDERED AND ARE
SUBJECT TO APPROVAL



SLOPED GRATING



BEDDING CLASS S
RIGID PIPES (CONCRETE)
VEHICLE AREAS GREATER
THAN 1.2m COVER
PEDESTRIAN AREAS GREATER
THAN 0.9m COVER



CLASS T DETAIL
SCALE 1:20

(plastic pipes shall comply with WIS 4-35-01 and shall be kitemarked)

NOMINAL PIPE DIA (mm)	SINGLE SIZED (mm)	GRADED (mm)
100	10	Not permitted
110 to 150	10 or 14	14 to 5 graded
160 to 300	10, 14 or 20	Either 20 to 5 graded or 14 to 5 graded
310 to 500	14 or 20	Either 20 to 5 graded or 14 to 5 graded
Over 550	14, 20 or 40	Either 40 to 5 graded or 20 to 5 graded or 14 to 5 graded

GRANULAR BEDDING MATERIAL
Extract from Table A2 WIS 4-08-02
(all aggregates to table 4 of BS 882-1983)

PLASTIC PIPE (u-PVC) TRENCH BEDDING DETAILS

NOM PIPE DIA (mm)	MIN TRENCH WIDTH (mm)
150	450
225	525
300	Two times nom. diameter
And above	

THE FOLLOWING UPVC PIPES ARE ACCEPTABLE FOR USE

UPONOR ULTRA DRAIN	110 & 160 (O.D.)
HEPNORTH PLASTIDRAIN	110 & 160 (O.D.)
WAVIN OSMA DRAIN	110 & 160 (O.D.)
WAVIN OSMA ULTRA RIB	150 & 225 (I.D.)
MARLEY SOLID WALL	110 & 160 (O.D.)
MARLEY QUANTUM	150 & 225 (I.D.)
POLYPIPE RIGIDSEWER	150 & 225 (I.D.)
POLYPIPE UNDERGROUND DRAIN	110 & 160 (O.D.)

BEDDING & BACKFILL SPECIFICATIONS FOR FLEXIBLE PIPES

PEDESTRIAN AREAS:-

- WITH COVER TO SOFFIT > 0.9m - CLASS T (UPVC)
- WITH COVER TO SOFFIT < 0.9m - CLASS Q (UPVC)
- WITH COVER TO SOFFIT > 0.9m - CLASS S (CONCRETE)
- WITH COVER TO SOFFIT < 0.9m - CLASS Z (UPVC OR CONCRETE)

VEHICULAR AREAS:-

- WITH COVER TO SOFFIT > 1.2m - CLASS T (UPVC)
- WITH COVER TO SOFFIT < 1.2m - CLASS Q (UPVC)
- WITH COVER TO SOFFIT > 1.2m - CLASS S (CONCRETE)
- WITH COVER TO SOFFIT < 1.2m - CLASS Z (UPVC OR CONCRETE)


LANDSCAPING AREAS:-

- CLASS Q (UPVC)
- CLASS S (CONCRETE)


BUILDING AREAS:-

- WITH COVER TO SOFFIT > 0.3m - CLASS W (UPVC)
- WITH COVER TO SOFFIT < 0.3m - CLASS Y (UPVC)


USE CLASS Z CONCRETE SURROUND WHERE PIPELINES CROSS WITHIN 300mm AND FOR WHERE PIPELINES PASS THROUGH STRUCTURES AND RUN NEAR FOUNDATIONS.



TIMBER FENCE FOR HEADWALL
SCALE 1:20



INDICATIVE 3D VIEW OF
TIMBER FENCE




SILT FENCE
SCALE 1:20

Rev	Description	Date	Chk'd	App'd
P01	ISSUE FOR RMA SUBMISSION	25/04/25		

DRAWING ISSUES

KEY PLAN



PROJECT

CAMBOIS DATA CENTRE CAMPUS

Land at the Former Power Station Site
on the Northern Side of Cambois,
Cambois, Northumberland

DWG. TITLE

ENABLING WORKS - PHASE A
DRAINAGE DETAILS
SHEET 2

PROJECT NO:

1043152

DWG. NO:

NCL1-RMAPA-STE-XX-DR-C-05-04

STATUS:

ISSUED FOR
REVIEW

SCALE @ A0:

AS SHOWN

OWNER

QTS

MEP, STRUCTURAL, CIVIL, SECURITY, TECHNOLOGY,
CONTROLS, FIRE & GEOTECHNICAL

CUNDALL

One Carter Lane
London
EC4A 3ER
United Kingdom
www.cundall.com

ARCHITECT

CORGAN

105 Park St
Temple Bar
London
EC4M 4BY
United Kingdom
www.corgan.com





LANDSCAPE

ARCADIS

80 Fenchurch Street
City of London
London
EC3M 4BY
United Kingdom
www.arcadis.com

SHEET NOTES


1. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS, ARCHITECTS AND OTHER CONSULTANTS DOCUMENTATION.
2. SOME DRAWINGS MAY NEED TO BE PRINTED IN COLOUR TO PRESERVE INFORMATION INDICATED IN COLOUR ON THE DRAWINGS.
3. DO NOT SCALE. WORK TO FIGURED DIMENSIONS ONLY.
4. ALL DIMENSIONS STATED IN mm UNLESS OTHERWISE NOTED



Rev	Description	Date	Chk'd	App'd
P01	ISSUE FOR RMA SUBMISSION	25/04/25	Y. Smith	Y. Smith

DRAWING ISSUES

KEY PLAN



PROJECT

**CAMBOIS DATA
CENTRE CAMPUS**

Land at the Former Power Station Site
on the Northern Side of Cambois,
Cambois, Northumberland

DWG. TITLE

ENABLING WORKS - PHASE A
DRAINAGE DETAILS
SHEET 3

PROJECT NO:

1043152

DWG. NO:

NCL1-RMAPA-STE-XX-DR-C-05-05

STATUS:

ISSUED FOR
REVIEW


SCALE @ A0:

AS SHOWN

Appendix D Drainage Phasing

P01	ISSUE FOR RMA SUBMISSION	25/04/25		
Rev	Description	Date	Chk'd	Apr'd

KEY PLAN




WG. TITLE
ENABLING WORKS - PHASE A
SURFACE WATER DRAINAGE PHASING

043152


C-SK-EW001

ALE A0:

000



Appendix E Impermeable Area Plan



Notes

A3

P01	18.03.25	FIRST ISSUE	BW	MLC	DD
Issue	Date	Description	By	Chkd	Verfd

Project

Cambois Data Centre Campus

Client

Renaissance Land Limited

Title

IMPERMEABLE
AREA PLAN -
PHASE A ENABLING

Drawing No.
1043152-C-SK-EW002

Drawing Status
SKETCH

Job No.
1043152

Scale
N.T.S.

CUNDALL

4th Floor, Partnership House
Regent Farm Road,
Gosforth,
Newcastle NE3 3AF
Telephone: +44 (0)191 213 1515
Website: www.cundall.com

Appendix F Exceedance Flows

Appendix G Greenfield Runoff Calculation

Calculated by:	Barrie ONeill Williams
Site name:	QTS Enabling
Site location:	Cambois

This is an estimation of the greenfield runoff rates that are used to meet normal best practice criteria in line with Environment Agency guidance "Rainfall runoff management for developments", SC030219 (2013), the SuDS Manual C753 (Ciria, 2015) and the non-statutory standards for SuDS (Defra, 2015). This information on greenfield runoff rates may be the basis for setting consents for the drainage of surface water runoff from sites.

Site Details

Latitude:	55.14395° N
Longitude:	1.52425° W
Reference:	530329563
Date:	Mar 18 2025 14:37

Runoff estimation approach

IH124

Site characteristics

Total site area (ha):	10.2
-----------------------	------

Methodology

Q _{BAR} estimation method:	Calculate from SPR and SAAR
SPR estimation method:	Calculate from SOIL type

Notes

(1) Is Q_{BAR} < 2.0 l/s/ha?

When Q_{BAR} is < 2.0 l/s/ha then limiting discharge rates are set at 2.0 l/s/ha.

Soil characteristics

	Default	Edited
SOIL type:	4	4
HOST class:	N/A	N/A
SPR/SPRHOST:	0.47	0.47

(2) Are flow rates < 5.0 l/s?

Where flow rates are less than 5.0 l/s consent for discharge is usually set at 5.0 l/s if blockage from vegetation and other materials is possible. Lower consent flow rates may be set where the blockage risk is addressed by using appropriate drainage elements.

Hydrological characteristics

	Default	Edited
SAAR (mm):	635	635
Hydrological region:	3	3
Growth curve factor 1 year:	0.86	0.86
Growth curve factor 30 years:	1.75	1.75
Growth curve factor 100 years:	2.08	2.08
Growth curve factor 200 years:	2.37	2.37

(3) Is SPR/SPRHOST ≤ 0.3?

Where groundwater levels are low enough the use of soakaways to avoid discharge offsite would normally be preferred for disposal of surface water runoff.

Greenfield runoff rates

Default

Edited

Q_{BAR} (l/s):	43.94	43.94
1 in 1 year (l/s):	37.79	37.79
1 in 30 years (l/s):	76.89	76.89
1 in 100 year (l/s):	91.39	91.39
1 in 200 years (l/s):	104.13	104.13

This report was produced using the greenfield runoff tool developed by HR Wallingford and available at www.uksuds.com. The use of this tool is subject to the UK SuDS terms and conditions and licence agreement , which can both be found at www.uksuds.com/terms-and-conditions.htm. The outputs from this tool are estimates of greenfield runoff rates. The use of these results is the responsibility of the users of this tool. No liability will be accepted by HR Wallingford, the Environment Agency, CEH, Hydrosolutions or any other organisation for the use of this data in the design or operational characteristics of any drainage scheme.

Appendix H Infodrainage Calculations

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Storm Phase: Phase	Company Address:		



Name	Junction Type	Easting (m)	Northing (m)	Cover Level (m)	Depth (m)	Invert Level (m)	Chamber Shape	Diameter (m)
Manhole (9)	Manhole	429778.829	583892.702	9.600	3.600	6.000	Circular	1.200
Manhole (10)	Manhole	429794.100	583804.134	8.740	4.050	4.690	Circular	1.200
Manhole (11)	Manhole	429832.342	583768.165	8.280	3.680	4.600	Circular	1.200
Manhole (12)	Manhole	429870.758	583732.041	7.980	3.470	4.510	Circular	1.200
Manhole (13)	Manhole	429903.336	583701.393	7.890	3.460	4.430	Circular	1.200
Manhole (14)	Manhole	429983.327	583701.393	7.850	3.560	4.290	Circular	1.200
Manhole (15)	Manhole	429991.991	583638.074	7.115	2.935	4.180	Circular	1.200
Manhole (16)	Manhole	430000.687	583574.525	7.435	3.365	4.070	Circular	1.200
Manhole (17)	Manhole	430108.203	583570.169	6.245	2.380	3.865	Circular	1.200
Manhole (36)	Manhole	429853.153	583866.866	9.000	1.400	7.600	Circular	1.200
Manhole (37)	Manhole	429827.106	583839.197	9.000	1.560	7.440	Circular	1.200
Manhole (38)	Manhole	429891.380	583830.881	9.000	1.400	7.600	Circular	1.200
Manhole (39)	Manhole	429865.334	583803.212	9.000	1.560	7.440	Circular	1.200
Manhole (40)	Manhole	429929.524	583794.808	9.000	1.400	7.600	Circular	1.200
Manhole (41)	Manhole	429903.561	583767.226	9.000	1.560	7.440	Circular	1.200
Pond Outfall	Manhole	430329.715	583541.581	6.100	2.650	3.450	Circular	2.600
Manhole (43)	Manhole	430359.315	583540.673	4.000	1.000	3.000	Circular	1.200
38	Manhole	430391.684	583408.662	3.690	1.870	1.820	Circular	1.200
ExMH5	Manhole	430402.770	583370.408	4.500	8.500	-4.000	Circular	1.200
ExMH4a	Manhole	430401.648	583356.602	4.500	8.610	-4.110	Circular	1.200
ExMH4	Manhole	430411.105	583347.312	4.500	8.720	-4.220	Circular	1.200
ExMH	Manhole	430423.307	583298.821	4.500	5.167	-0.667	Circular	1.200
S	Manhole	430437.629	583275.640	4.300	5.045	-0.745	Circular	1.200
Manhole (44)	Manhole	430386.077	583275.948	4.000	1.500	2.500	Circular	1.200
Manhole (45)	Manhole	430507.332	583375.221	4.000	7.175	-3.175	Circular	1.200
Manhole	Manhole	429681.529	583956.198	10.030	3.390	6.640	Circular	1.200
Manhole (1)	Manhole	429683.378	583993.989	10.100	3.260	6.840	Circular	1.200
Manhole (2)	Manhole	429583.498	583998.876	10.600	1.400	9.200	Circular	1.200
Manhole (3)	Manhole	429783.259	583989.103	10.600	1.400	9.200	Circular	1.200
Manhole (4)	Manhole	429585.941	584048.816	10.600	1.400	9.200	Circular	1.200
Manhole (5)	Manhole	429685.822	584043.930	10.100	3.000	7.100	Circular	1.200
Manhole (6)	Manhole	429785.702	584039.043	10.600	1.400	9.200	Circular	1.200
Manhole (7)	Manhole	429588.384	584098.757	10.600	1.400	9.200	Circular	1.200
Manhole (18)	Manhole	429688.265	584093.870	10.100	2.720	7.380	Circular	1.200
Manhole (19)	Manhole	429788.145	584088.983	10.600	1.400	9.200	Circular	1.200
Manhole (20)	Manhole	429590.828	584148.697	10.600	1.400	9.200	Circular	1.200
Manhole (21)	Manhole	429690.708	584143.810	10.100	2.450	7.650	Circular	1.200
Manhole (22)	Manhole	429790.589	584138.923	10.600	1.400	9.200	Circular	1.200
Manhole (23)	Manhole	429593.271	584198.637	10.600	1.400	9.200	Circular	1.200
Manhole (24)	Manhole	429693.151	584193.750	10.100	2.180	7.920	Circular	1.200
Manhole (25)	Manhole	429793.032	584188.864	10.600	1.400	9.200	Circular	1.200
Manhole (26)	Manhole	429595.714	584248.577	10.600	1.400	9.200	Circular	1.200
Manhole (27)	Manhole	429695.595	584243.691	10.100	2.000	8.100	Circular	1.200
Manhole (28)	Manhole	429795.475	584238.804	10.600	1.400	9.200	Circular	1.200

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Storm Phase: Phase	Company Address:		



Name	Lock
Manhole (9)	None
Manhole (10)	None
Manhole (11)	None
Manhole (12)	None
Manhole (13)	None
Manhole (14)	None
Manhole (15)	None
Manhole (16)	None
Manhole (17)	None
Manhole (36)	None
Manhole (37)	None
Manhole (38)	None
Manhole (39)	None
Manhole (40)	None
Manhole (41)	None
Pond Outfall	None
Manhole (43)	None
38	None
ExMH5	None
ExMH4a	None
ExMH4	None
ExMH	None
S	None
Manhole (44)	None
Manhole (45)	None
Manhole	None
Manhole (1)	None
Manhole (2)	None
Manhole (3)	None
Manhole (4)	None
Manhole (5)	None
Manhole (6)	None
Manhole (7)	None
Manhole (18)	None
Manhole (19)	None
Manhole (20)	None
Manhole (21)	None
Manhole (22)	None
Manhole (23)	None
Manhole (24)	None
Manhole (25)	None
Manhole (26)	None
Manhole (27)	None
Manhole (28)	None

Inlets

Junction	Inlet Name	Incoming Item(s)	Bypass Destination	Capacity Type
Manhole (9)	Inlet	Pipe (6)	(None)	No Restriction
Manhole (10)	Inlet	Pipe (9)	(None)	No Restriction
	Inlet (1)	Pipe (36)	(None)	No Restriction
Manhole (11)	Inlet	Pipe (10)	(None)	No Restriction
	Inlet (1)	Pipe (38)	(None)	No Restriction
Manhole (12)	Inlet	Pipe (11)	(None)	No Restriction
	Inlet (1)	Pipe (40)	(None)	No Restriction
Manhole (13)	Inlet	Pipe (12)	(None)	No Restriction
Manhole (14)	Inlet	Pipe (13)	(None)	No Restriction
Manhole (15)	Inlet	Pipe (14)	(None)	No Restriction
Manhole (16)	Inlet	Pipe (15)	(None)	No Restriction
	Inlet	Pipe (16)	(None)	No Restriction

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Storm Phase: Phase	Company Address:		



Junction	Inlet Name	Incoming Item(s)	Bypass Destination	Capacity Type
Manhole (17)	Inlet (1)	Laydown Area	(None)	No Restriction
Manhole (36)	Inlet (1)	Pipe (67)	(None)	No Restriction
Manhole (37)	Inlet	Pipe (35)	(None)	No Restriction
	Inlet (1)	Pipe (66)	(None)	No Restriction
Manhole (38)	Inlet	Pipe (69)	(None)	No Restriction
Manhole (39)	Inlet	Pipe (37)	(None)	No Restriction
	Inlet (2)	Pipe (68)	(None)	No Restriction
Manhole (40)	Inlet (1)	Pipe (71)	(None)	No Restriction
Manhole (41)	Inlet	Pipe (39)	(None)	No Restriction
	Inlet (2)	Pipe (70)	(None)	No Restriction
Pond Outfall	Inlet	Pipe (42)	(None)	No Restriction
Manhole (43)	Inlet	Pipe (43)	(None)	No Restriction
38	Inlet	Trapezoidal Channel	(None)	No Restriction
	Inlet (3)	Pipe (79)	(None)	No Restriction
ExMH5	Inlet	Pipe (72)	(None)	No Restriction
	Inlet (1)	Pipe (78)	(None)	No Restriction
ExMH4a	Inlet	Pipe (73)	(None)	No Restriction
ExMH4	Inlet	Pipe (74)	(None)	No Restriction
ExMH	Inlet	Pipe (75)	(None)	No Restriction
S	Inlet	Pipe (76)	(None)	No Restriction
	Inlet (1)	Pipe (77)	(None)	No Restriction
Manhole (44)	Inlet	Catchment Area (29)	(None)	No Restriction
Manhole (45)	Inlet	Catchment Area (28)	(None)	No Restriction
Manhole	Inlet (1)	Pipe (5)	(None)	No Restriction
Manhole (1)	Inlet	Pipe (4)	(None)	No Restriction
	Inlet (1)	Pipe (21)	(None)	No Restriction
	Inlet (2)	Pipe (27)	(None)	No Restriction
	Inlet (3)	Catchment Area (12)	(None)	No Restriction
Manhole (2)	Inlet	Pipe (28)	(None)	No Restriction
Manhole (3)	Inlet	Pipe (48)	(None)	No Restriction
Manhole (4)	Inlet	Pipe (29)	(None)	No Restriction
Manhole (5)	Inlet	Pipe (3) Pipe (20)	(None)	No Restriction
	Inlet (1)	Pipe (26)	(None)	No Restriction
	Inlet (2)	Catchment Area (13)	(None)	No Restriction
Manhole (6)	Inlet	Pipe (47)	(None)	No Restriction
Manhole (7)	Inlet	Pipe (30)	(None)	No Restriction
Manhole (18)	Inlet	Pipe (2) Pipe (19)	(None)	No Restriction
	Inlet (1)	Pipe (25)	(None)	No Restriction
	Inlet (2)	Catchment Area (14)	(None)	No Restriction
Manhole (19)	Inlet	Pipe (46)	(None)	No Restriction
Manhole (20)	Inlet	Pipe (31)	(None)	No Restriction
Manhole (21)	Inlet	Pipe (1)	(None)	No Restriction
	Inlet (1)	Pipe (18)	(None)	No Restriction
	Inlet (2)	Pipe (24)	(None)	No Restriction
	Inlet (3)	Catchment Area (15)	(None)	No Restriction
Manhole (22)	Inlet	Pipe (45)	(None)	No Restriction
Manhole (23)	Inlet	Pipe (32)	(None)	No Restriction
Manhole (24)	Inlet	Pipe Pipe (17)	(None)	No Restriction
	Inlet (1)	Pipe (23)	(None)	No Restriction
	Inlet (2)	Catchment Area (16)	(None)	No Restriction
Manhole (25)	Inlet	Pipe (44)	(None)	No Restriction
Manhole (26)	Inlet	Pipe (33)	(None)	No Restriction
Manhole (27)	Inlet	Pipe (7)	(None)	No Restriction
	Inlet (1)	Pipe (22)	(None)	No Restriction

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Storm Phase: Phase	Company Address:		



Junction	Inlet Name	Incoming Item(s)	Bypass Destination	Capacity Type
	Inlet (2)	Catchment Area (17)	(None)	No Restriction
Manhole (28)	Inlet	Pipe (34)	(None)	No Restriction

Outlets

Junction	Outlet Name	Outgoing Connection	Outlet Type
Manhole (9)	Outlet	Pipe (9)	Free Discharge
Manhole (10)	Outlet	Pipe (10)	Free Discharge
Manhole (11)	Outlet	Pipe (11)	Free Discharge
Manhole (12)	Outlet	Pipe (12)	Free Discharge
Manhole (13)	Outlet	Pipe (13)	Free Discharge
Manhole (14)	Outlet	Pipe (14)	Free Discharge
Manhole (15)	Outlet	Pipe (15)	Free Discharge
Manhole (16)	Outlet	Pipe (16)	Free Discharge
Manhole (17)	Outlet	Pipe (41)	Free Discharge
Manhole (36)	Outlet	Pipe (35)	Free Discharge
Manhole (37)	Outlet	Pipe (36)	Free Discharge
Manhole (38)	Outlet	Pipe (37)	Free Discharge
Manhole (39)	Outlet	Pipe (38)	Free Discharge
Manhole (40)	Outlet	Pipe (39)	Free Discharge
Manhole (41)	Outlet	Pipe (40)	Free Discharge
Pond Outfall	Outlet	Pipe (43)	Orifice
	Diameter (m)	0.150	
	Coefficient of Discharge	0.600	
	Invert Level (m)	3.450	
Manhole (43)	Outlet	Trapezoidal Channel	Free Discharge
38	Outlet	Pipe (72)	Free Discharge
ExMH5	Outlet	Pipe (73)	Free Discharge
ExMH4a	Outlet	Pipe (74)	Free Discharge
ExMH4	Outlet	Pipe (75)	Free Discharge
ExMH	Outlet	Pipe (76)	Free Discharge
Manhole (44)	Outlet	Pipe (77)	Free Discharge
Manhole (45)	Outlet	Pipe (78)	Free Discharge
Manhole	Outlet	Pipe (6)	Free Discharge
Manhole (1)	Outlet	Pipe (5)	Free Discharge
Manhole (2)	Outlet	Pipe (21)	Free Discharge
Manhole (3)	Outlet	Pipe (27)	Free Discharge
Manhole (4)	Outlet	Pipe (20)	Free Discharge
Manhole (5)	Outlet	Pipe (4)	Free Discharge
Manhole (6)	Outlet	Pipe (26)	Free Discharge
Manhole (7)	Outlet	Pipe (19)	Free Discharge
Manhole (18)	Outlet	Pipe (3)	Free Discharge
Manhole (19)	Outlet	Pipe (25)	Free Discharge
Manhole (20)	Outlet	Pipe (18)	Free Discharge
Manhole (21)	Outlet	Pipe (2)	Free Discharge
Manhole (22)	Outlet	Pipe (24)	Free Discharge
Manhole (23)	Outlet	Pipe (17)	Free Discharge
Manhole (24)	Outlet	Pipe (1)	Free Discharge
Manhole (25)	Outlet	Pipe (23)	Free Discharge
Manhole (26)	Outlet	Pipe (7)	Free Discharge
Manhole (27)	Outlet	Pipe	Free Discharge
Manhole (28)	Outlet	Pipe (22)	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Pond

Type : Pond

Dimensions

Exceedance Level (m)	6.100
Depth (m)	3.300
Base Level (m)	2.800
Freeboard (mm)	0
Initial Depth (m)	1.000
Porosity (%)	100
Average Slope (1:X)	9.645
Total Volume (m³)	37504.599

Depth (m)	Area (m²)	Volume (m³)
0.000	4800.00	0.000
1.000	10500.00	7466.432
3.300	15800.00	37504.599

Inlets

Inlet

Inlet Type	Point Inflow
Incoming Item(s)	Pipe (41)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (42)
Outlet Type	Free Discharge

Advanced

Perimeter	Circular
Length (m)	199.699
Friction Scheme	Manning's n
n	0.03

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Cow Gut Diversion

Type : Pond

Dimensions

Exceedance Level (m)	4.000
Depth (m)	1.000
Base Level (m)	3.000
Freeboard (mm)	0
Initial Depth (m)	0.000
Porosity (%)	100
Average Slope (1:X)	11.284
Total Volume (m³)	433.333

Depth (m)	Area (m²)	Volume (m³)
0.000	100.00	0.000
1.000	900.00	433.333

Inlets

Inlet

Inlet Type	Point Inflow
Incoming Item(s)	Off Site Catchment
Bypass Destination	(None)
Capacity Type	No Restriction

Inlet (1)

Inlet Type	Point Inflow
Incoming Item(s)	On Site Catchment
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (79)
Outlet Type	Free Discharge

Advanced

Perimeter	Circular
Length (m)	78.580
Friction Scheme	Manning's n
n	0.04

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (20)

Type : Soakaway

Dimensions

Exceedance Level (m)	8.850
Depth (m)	1.000
Base Level (m)	7.850
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	35.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	8.750

Inlets

Inlet (1)

Incoming Item(s)	Catchment Area (22)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (66)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (21)

Type : Soakaway

Dimensions

Exceedance Level (m)	8.850
Depth (m)	1.000
Base Level (m)	7.850
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	37.134
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	9.283

Inlets

Inlet (1)

Incoming Item(s)	Catchment Area (23)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (67)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (22)

Type : Soakaway

Dimensions

Exceedance Level (m)	8.850
Depth (m)	1.000
Base Level (m)	7.850
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	37.187
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	9.297

Inlets

Inlet (1)

Incoming Item(s)	Catchment Area (24)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (68)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (23)

Type : Soakaway

Dimensions

Exceedance Level (m)	8.850
Depth (m)	1.000
Base Level (m)	7.850
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	37.759
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	9.440

Inlets

Inlet

Incoming Item(s)	Catchment Area (25)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (69)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (24)

Type : Soakaway

Dimensions

Exceedance Level (m)	8.850
Depth (m)	1.000
Base Level (m)	7.850
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	37.648
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	9.412

Inlets

Inlet

Incoming Item(s)	Catchment Area (26)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (70)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (25)

Type : Soakaway

Dimensions

Exceedance Level (m)	8.850
Depth (m)	1.000
Base Level (m)	7.850
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	37.130
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	9.282

Inlets

Inlet

Incoming Item(s)	Catchment Area (27)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (71)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (28)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (1)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (1)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (29)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (2)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (2)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (30)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (3)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (3)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (31)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (4)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (4)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (32)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (5)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (5)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (33)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (6)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (6)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (48)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (7)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (7)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (47)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (8)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (8)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (46)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (9)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (9)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (45)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (10)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (10)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (44)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Stormwater Controls Storm Phase: Phase	Company Address:		



Soakaway (11)

Type : Soakaway

Dimensions

Exceedance Level (m)	10.600
Depth (m)	1.000
Base Level (m)	9.600
Freeboard (mm)	0
Soakaway Shape	Rectangular
Diameter / Width (m)	1.000
Length (m)	75.000
Porosity (%)	25
Ineffective Storage Depth (m)	0.000
Number of Soakaways	1
Total Volume (m³)	18.750

Inlets

Inlet

Incoming Item(s)	Catchment Area (11)
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	Pipe (34)
Outlet Type	Free Discharge

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Connections Storm Phase: Phase	Company Address:		



Name	Length (m)	Connection Type	Slope (1:X)	Manning's n	Colebrook-White Roughness (mm)	Diameter / Base Width (mm)	Height (mm)	Side Slope (1:X)
Pipe (9)	89.874	Pipe	185.308		0.3	375		
Pipe (10)	52.500	Pipe	583.333		0.3	1200		
Pipe (11)	52.732	Pipe	585.916		0.3	1200		
Pipe (12)	44.728	Pipe	559.101		0.3	1200		
Pipe (13)	79.991	Pipe	571.368		0.3	1200		
Pipe (14)	63.909	Pipe	580.991		0.3	1200		
Pipe (15)	64.141	Pipe	583.100		0.3	1200		
Pipe (16)	107.604	Pipe	524.898		0.3	1200		
Pipe (35)	38.000	Pipe	237.500		0.3	150		
Pipe (36)	48.154	Pipe	17.511		0.3	150		
Pipe (37)	38.000	Pipe	237.500		0.3	150		
Pipe (38)	48.132	Pipe	16.948		0.3	150		
Pipe (39)	37.879	Pipe	236.745		0.3	150		
Pipe (40)	48.104	Pipe	16.418		0.3	150		
Pipe (41)	34.613	Pipe	532.504		0.3	1200		
Pipe (42)	19.010	Pipe	54.314		0.3	525		
Pipe (43)	29.613	Pipe	65.807		0.3	525		
Pipe (66)	3.426	Pipe	8.355		0.6	250		
Pipe (67)	2.450	Pipe	9.798		0.6	250		
Pipe (68)	2.971	Pipe	7.245		0.6	250		
Pipe (69)	2.768	Pipe	11.073		0.6	250		
Pipe (70)	4.248	Pipe	10.361		0.6	250		
Pipe (71)	3.180	Pipe	12.719		0.6	250		
Pipe (72)	39.828	Pipe	6.843		0.6	900		
Pipe (73)	13.852	Pipe	125.924		0.6	1200		
Pipe (74)	13.257	Pipe	120.517		0.6	1200		
Pipe (75)	50.003	Pipe	-14.073		0.6	1200		
Pipe (76)	27.249	Pipe	349.341		0.6	1200		
Pipe (77)	51.553	Pipe	15.887		0.6	300		
Pipe (78)	104.673	Pipe	126.876		0.6	525		
Trapezoidal Channel	135.922	Trapezoidal Channel	115.188	0.040		750	1000	3.00
Pipe (79)	14.502	Pipe	12.290		0.6	900		
Pipe	50.000	Pipe	277.778		0.6	300		
Pipe (1)	50.000	Pipe	185.185		0.6	300		
Pipe (2)	50.000	Pipe	185.185		0.6	300		
Pipe (3)	50.000	Pipe	178.571		0.6	375		
Pipe (4)	50.000	Pipe	192.308		0.6	375		
Pipe (5)	37.836	Pipe	189.181		0.6	375		
Pipe (7)	100.000	Pipe	90.910		0.6	150		
Pipe (17)	100.000	Pipe	78.125		0.6	150		
Pipe (18)	100.000	Pipe	64.516		0.6	150		
Pipe (19)	100.000	Pipe	54.945		0.6	150		
Pipe (20)	100.000	Pipe	47.619		0.6	150		
Pipe (21)	100.000	Pipe	42.373		0.6	150		
Pipe (22)	100.000	Pipe	90.909		0.6	150		
Pipe (23)	100.000	Pipe	78.125		0.6	150		
Pipe (24)	100.000	Pipe	64.516		0.6	150		
Pipe (25)	100.000	Pipe	54.945		0.6	150		
Pipe (26)	100.000	Pipe	47.619		0.6	150		
Pipe (27)	100.000	Pipe	42.373		0.6	150		
Pipe (28)	4.742	Pipe	11.856		0.6	250		
Pipe (29)	3.252	Pipe	8.129		0.6	250		
Pipe (30)	3.405	Pipe	8.513		0.6	250		
Pipe (31)	4.476	Pipe	11.191		0.6	250		
Pipe (32)	5.195	Pipe	12.987		0.6	250		
Pipe (33)	4.068	Pipe	10.171		0.6	250		

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Connections Storm Phase: Phase	Company Address:		



Pipe (34)	1.496	Pipe	3.739		0.6	250	
Pipe (44)	1.916	Pipe	4.790		0.6	250	
Pipe (45)	1.957	Pipe	4.893		0.6	250	
Pipe (46)	1.680	Pipe	4.199		0.6	250	
Pipe (47)	2.360	Pipe	5.901		0.6	250	
Pipe (48)	4.509	Pipe	11.272		0.6	250	
Pipe (6)	116.185	Pipe	181.540		0.6	375	


Name	Upstream Cover Level (m)	Upstream Invert Level (m)	Downstream Cover Level (m)	Downstream Invert Level (m)	Part Family	Lock	Flow Restriction (L/s)	Culvert Type
Pipe (9)	9.600	6.000	8.740	5.515		Levels		(None)
Pipe (10)	8.740	4.690	8.280	4.600		None		(None)
Pipe (11)	8.280	4.600	7.980	4.510		None		(None)
Pipe (12)	7.980	4.510	7.890	4.430		None		(None)
Pipe (13)	7.890	4.430	7.850	4.290		None		(None)
Pipe (14)	7.850	4.290	7.115	4.180		None		(None)
Pipe (15)	7.115	4.180	7.435	4.070		None		(None)
Pipe (16)	7.435	4.070	6.245	3.865		None		(None)
Pipe (35)	9.000	7.600	9.000	7.440		None		(None)
Pipe (36)	9.000	7.440	8.740	4.690		None		(None)
Pipe (37)	9.000	7.600	9.000	7.440		None		(None)
Pipe (38)	9.000	7.440	8.280	4.600		None		(None)
Pipe (39)	9.000	7.600	9.000	7.440		None		(None)
Pipe (40)	9.000	7.440	7.980	4.510		None		(None)
Pipe (41)	6.245	3.865	6.100	3.800		Levels		(None)
Pipe (42)	6.100	3.800	6.100	3.450		Levels		(None)
Pipe (43)	6.100	3.450	4.000	3.000		None	400.0	(None)
Pipe (66)	8.850	7.850	9.000	7.440		None		(None)
Pipe (67)	8.850	7.850	9.000	7.600		None		(None)
Pipe (68)	8.850	7.850	9.000	7.440		None		(None)
Pipe (69)	8.850	7.850	9.000	7.600		None		(None)
Pipe (70)	8.850	7.850	9.000	7.440		None		(None)
Pipe (71)	8.850	7.850	9.000	7.600		None		(None)
Pipe (72)	3.690	1.820	4.500	-4.000		None		(None)
Pipe (73)	4.500	-4.000	4.500	-4.110		None		(None)
Pipe (74)	4.500	-4.110	4.500	-4.220		None		(None)
Pipe (75)	4.500	-4.220	4.500	-0.667		None		(None)
Pipe (76)	4.500	-0.667	4.300	-0.745		None		(None)
Pipe (77)	4.000	2.500	4.300	-0.745		None		(None)
Pipe (78)	4.000	-3.175	4.500	-4.000		None		(None)
Trapezoidal Channel	4.000	3.000	3.690	1.820		None		
Pipe (79)	4.000	3.000	3.690	1.820		None		(None)
Pipe	10.100	8.100	10.100	7.920		None		(None)
Pipe (1)	10.100	7.920	10.100	7.650		None		(None)
Pipe (2)	10.100	7.650	10.100	7.380		None		(None)
Pipe (3)	10.100	7.380	10.100	7.100		None		(None)
Pipe (4)	10.100	7.100	10.100	6.840		None		(None)
Pipe (5)	10.100	6.840	10.030	6.640		None		(None)
Pipe (7)	10.600	9.200	10.100	8.100		None		(None)
Pipe (17)	10.600	9.200	10.100	7.920		None		(None)
Pipe (18)	10.600	9.200	10.100	7.650		None		(None)
Pipe (19)	10.600	9.200	10.100	7.380		None		(None)
Pipe (20)	10.600	9.200	10.100	7.100		None		(None)
Pipe (21)	10.600	9.200	10.100	6.840		None		(None)
Pipe (22)	10.600	9.200	10.100	8.100		None		(None)
Pipe (23)	10.600	9.200	10.100	7.920		None		(None)
Pipe (24)	10.600	9.200	10.100	7.650		None		(None)
Pipe (25)	10.600	9.200	10.100	7.380		None		(None)
Pipe (26)	10.600	9.200	10.100	7.100		None		(None)
Pipe (27)	10.600	9.200	10.100	6.840		None		(None)

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Connections Storm Phase: Phase	Company Address:		



Pipe (28)	10.600	9.600	10.600	9.200	None	(None)
Pipe (29)	10.600	9.600	10.600	9.200	None	(None)
Pipe (30)	10.600	9.600	10.600	9.200	None	(None)
Pipe (31)	10.600	9.600	10.600	9.200	None	(None)
Pipe (32)	10.600	9.600	10.600	9.200	None	(None)
Pipe (33)	10.600	9.600	10.600	9.200	None	(None)
Pipe (34)	10.600	9.600	10.600	9.200	None	(None)
Pipe (44)	10.600	9.600	10.600	9.200	None	(None)
Pipe (45)	10.600	9.600	10.600	9.200	None	(None)
Pipe (46)	10.600	9.600	10.600	9.200	None	(None)
Pipe (47)	10.600	9.600	10.600	9.200	None	(None)
Pipe (48)	10.600	9.600	10.600	9.200	None	(None)
Pipe (6)	10.030	6.640	9.600	6.000	None	(None)

Name	Culvert Entrance
Pipe (9)	(None)
Pipe (10)	(None)
Pipe (11)	(None)
Pipe (12)	(None)
Pipe (13)	(None)
Pipe (14)	(None)
Pipe (15)	(None)
Pipe (16)	(None)
Pipe (35)	(None)
Pipe (36)	(None)
Pipe (37)	(None)
Pipe (38)	(None)
Pipe (39)	(None)
Pipe (40)	(None)
Pipe (41)	(None)
Pipe (42)	(None)
Pipe (43)	(None)
Pipe (66)	(None)
Pipe (67)	(None)
Pipe (68)	(None)
Pipe (69)	(None)
Pipe (70)	(None)
Pipe (71)	(None)
Pipe (72)	(None)
Pipe (73)	(None)
Pipe (74)	(None)
Pipe (75)	(None)
Pipe (76)	(None)
Pipe (77)	(None)
Pipe (78)	(None)
Trapezoidal Channel	
Pipe (79)	(None)
Pipe	(None)
Pipe (1)	(None)
Pipe (2)	(None)
Pipe (3)	(None)
Pipe (4)	(None)
Pipe (5)	(None)
Pipe (7)	(None)
Pipe (17)	(None)
Pipe (18)	(None)
Pipe (19)	(None)
Pipe (20)	(None)
Pipe (21)	(None)
Pipe (22)	(None)

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025			
	Designed by: BOW	Checked by: DD	Approved By: DD	
	Report Details: Type: Connections Storm Phase: Phase			
Company Address:				


Pipe (23)	(None)
Pipe (24)	(None)
Pipe (25)	(None)
Pipe (26)	(None)
Pipe (27)	(None)
Pipe (28)	(None)
Pipe (29)	(None)
Pipe (30)	(None)
Pipe (31)	(None)
Pipe (32)	(None)
Pipe (33)	(None)
Pipe (34)	(None)
Pipe (44)	(None)
Pipe (45)	(None)
Pipe (46)	(None)
Pipe (47)	(None)
Pipe (48)	(None)
Pipe (6)	(None)

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Summary Storm Phase: Phase	Company Address:		



FSR: 1 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
Manhole (9)	FSR: 1 years: +0 %: 15 mins: Winter	9.600	6.000	6.732	0.732	215.3	0.828	0.000	206.7	176.545	Surcharged
Manhole (10)	FSR: 1 years: +0 %: 15 mins: Winter	8.740	4.690	4.984	0.294	212.9	0.332	0.000	213.5	181.414	OK
Manhole (11)	FSR: 1 years: +0 %: 30 mins: Winter	8.280	4.600	4.905	0.305	231.4	0.345	0.000	228.5	261.124	OK
Manhole (12)	FSR: 1 years: +0 %: 30 mins: Winter	7.980	4.510	4.814	0.304	234.5	0.344	0.000	232.7	267.629	OK
Manhole (13)	FSR: 1 years: +0 %: 30 mins: Winter	7.890	4.430	4.726	0.296	232.7	0.335	0.000	231.2	267.847	OK
Manhole (14)	FSR: 1 years: +0 %: 30 mins: Winter	7.850	4.290	4.588	0.298	231.2	0.337	0.000	228.0	267.745	OK
Manhole (15)	FSR: 1 years: +0 %: 30 mins: Winter	7.115	4.180	4.473	0.293	228.0	0.332	0.000	224.7	267.827	OK
Manhole (16)	FSR: 1 years: +0 %: 30 mins: Winter	7.435	4.070	4.350	0.280	224.7	0.316	0.000	222.2	266.750	OK
Manhole (17)	FSR: 1 years: +0 %: 30 mins: Winter	6.245	3.865	4.172	0.307	263.4	0.348	0.000	262.4	396.180	OK
Manhole (36)	FSR: 1 years: +0 %: 15 mins: Winter	9.000	7.600	7.670	0.070	5.2	0.079	0.000	5.1	2.438	OK
Manhole (37)	FSR: 1 years: +0 %: 15 mins: Winter	9.000	7.440	7.487	0.047	10.2	0.053	0.000	10.4	4.873	OK
Manhole (38)	FSR: 1 years: +0 %: 15 mins: Winter	9.000	7.600	7.920	0.320	22.3	0.362	0.000	18.4	9.795	Surcharged
Manhole (39)	FSR: 1 years: +0 %: 15 mins: Winter	9.000	7.440	7.524	0.084	28.5	0.095	0.000	28.6	14.617	OK
Manhole (40)	FSR: 1 years: +0 %: 15 mins: Winter	9.000	7.600	7.670	0.070	5.1	0.079	0.000	5.1	2.439	OK
Manhole (41)	FSR: 1 years: +0 %: 15 mins: Winter	9.000	7.440	7.487	0.047	10.2	0.053	0.000	10.2	4.862	OK
Pond Outfall	FSR: 1 years: +0 %: 720 mins: Winter	6.100	3.450	3.857	0.407	27.3	2.161	0.000	27.1	939.732	OK
Manhole (43)	FSR: 1 years: +0 %: 180 mins: Winter	4.000	3.000	3.134	0.134	68.5	0.152	0.000	56.2	328.482	OK
38	FSR: 1 years: +0 %: 480 mins: Winter	3.690	1.820	3.146	1.326	365.4	1.500	0.000	365.5	9086.266	Surcharged
ExMH5	FSR: 1 years: +0 %: 600 mins: Winter	4.500	-4.000	3.125	7.125	367.8	8.059	0.000	367.8	10168.705	Surcharged
ExMH4a	FSR: 1 years: +0 %: 600 mins: Winter	4.500	-4.110	3.122	7.232	367.8	8.180	0.000	367.8	10087.577	Surcharged
ExMH4	FSR: 1 years: +0 %: 600 mins: Winter	4.500	-4.220	3.119	7.339	367.8	8.300	0.000	367.8	10023.710	Surcharged
ExMH	FSR: 1 years: +0 %: 600 mins: Winter	4.500	-0.667	3.113	3.780	367.8	4.275	0.000	367.8	9994.229	Surcharged
S	FSR: 1 years: +0 %: 600 mins: Winter	4.300	-0.745	3.108	3.853	368.5	0.000	0.000	368.5	10051.002	OK
Manhole (44)	FSR: 1 years: +0 %: 15 mins: Winter	4.000	2.500	3.159	0.659	33.3	0.746	0.000	33.0	13.699	Surcharged
Manhole (45)	FSR: 1 years: +0 %: 30 mins: Winter	4.000	-3.175	3.117	6.292	90.3	7.116	0.000	90.2	91.324	Surcharged
Manhole	FSR: 1 years: +0 %: 15 mins: Winter	10.030	6.640	7.995	1.355	218.8	1.533	0.000	215.3	175.223	Surcharged
Manhole (1)	FSR: 1 years: +0 %: 15 mins: Winter	10.100	6.840	8.456	1.616	221.9	1.828	0.000	218.8	176.345	Surcharged
Manhole (2)	FSR: 1 years: +0 %: 15 mins: Winter	10.600	9.200	9.520	0.320	25.0	0.362	0.000	24.1	11.736	Surcharged
Manhole (3)	FSR: 1 years: +0 %: 15 mins: Winter	10.600	9.200	9.523	0.323	25.0	0.365	0.000	24.1	11.736	Surcharged
Manhole (4)	FSR: 1 years: +0 %: 15 mins: Winter	10.600	9.200	9.635	0.435	24.1	0.491	0.000	21.4	10.988	Surcharged

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Junctions Summary Storm Phase: Phase		Company Address:			


Manhole (5)	FSR: 1 years: +0 %: 15 mins: Winter	10.10 0	7.100	8.823	1.723	184.7	1.949	0.000	175.4	148.819	Surcharged
Manhole (6)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.634	0.434	24.0	0.490	0.000	21.4	10.987	Surcharged
Manhole (7)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.660	0.460	26.2	0.521	0.000	19.4	10.997	Surcharged
Manhole (18)	FSR: 1 years: +0 %: 15 mins: Winter	10.10 0	7.380	9.030	1.650	148.2	1.867	0.000	135.4	119.836	Surcharged
Manhole (19)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.658	0.458	23.3	0.518	0.000	19.4	10.994	Surcharged
Manhole (20)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.702	0.502	23.3	0.568	0.000	18.8	10.991	Surcharged
Manhole (21)	FSR: 1 years: +0 %: 15 mins: Winter	10.10 0	7.650	9.343	1.693	124.9	1.915	0.000	113.8	90.739	Surcharged
Manhole (22)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.701	0.501	22.7	0.566	0.000	19.0	10.986	Surcharged
Manhole (23)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.731	0.531	26.0	0.601	0.000	18.2	11.010	Surcharged
Manhole (24)	FSR: 1 years: +0 %: 15 mins: Winter	10.10 0	7.920	9.475	1.555	98.7	1.759	0.000	85.1	61.649	Surcharged
Manhole (25)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.728	0.528	31.0	0.598	0.000	18.5	11.000	Surcharged
Manhole (26)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.744	0.544	27.9	0.615	0.000	17.9	11.231	Surcharged
Manhole (27)	FSR: 1 years: +0 %: 15 mins: Winter	10.10 0	8.100	9.515	1.415	55.7	1.601	0.000	48.4	32.613	Surcharged
Manhole (28)	FSR: 1 years: +0 %: 15 mins: Winter	10.60 0	9.200	9.741	0.541	35.4	0.612	0.000	18.0	11.222	Surcharged

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Summary Storm Phase: Phase	Company Address:		



FSR: 10 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
Manhole (9)	FSR: 10 years: +0 %: 15 mins: Winter	9.600	6.000	6.969	0.969	236.4	1.096	0.000	228.5	341.767	Surcharged
Manhole (10)	FSR: 10 years: +0 %: 15 mins: Winter	8.740	4.690	5.013	0.323	246.6	0.365	0.000	244.1	351.212	OK
Manhole (11)	FSR: 10 years: +0 %: 15 mins: Winter	8.280	4.600	4.940	0.340	287.0	0.385	0.000	280.0	379.849	OK
Manhole (12)	FSR: 10 years: +0 %: 30 mins: Winter	7.980	4.510	4.855	0.345	292.0	0.390	0.000	290.6	517.827	OK
Manhole (13)	FSR: 10 years: +0 %: 30 mins: Winter	7.890	4.430	4.766	0.336	290.6	0.380	0.000	289.0	518.090	OK
Manhole (14)	FSR: 10 years: +0 %: 30 mins: Winter	7.850	4.290	4.631	0.341	289.0	0.386	0.000	286.8	517.990	OK
Manhole (15)	FSR: 10 years: +0 %: 30 mins: Winter	7.115	4.180	4.520	0.340	286.8	0.384	0.000	287.7	517.931	OK
Manhole (16)	FSR: 10 years: +0 %: 30 mins: Winter	7.435	4.070	4.399	0.329	287.7	0.372	0.000	289.0	519.121	OK
Manhole (17)	FSR: 10 years: +0 %: 30 mins: Winter	6.245	3.865	4.291	0.426	488.4	0.482	0.000	486.9	768.800	OK
Manhole (36)	FSR: 10 years: +0 %: 15 mins: Winter	9.000	7.600	7.705	0.105	9.9	0.119	0.000	10.0	4.722	OK
Manhole (37)	FSR: 10 years: +0 %: 15 mins: Winter	9.000	7.440	7.508	0.068	19.8	0.077	0.000	19.9	9.413	OK
Manhole (38)	FSR: 10 years: +0 %: 15 mins: Winter	9.000	7.600	8.298	0.698	26.3	0.790	0.000	25.8	18.962	Surcharged
Manhole (39)	FSR: 10 years: +0 %: 15 mins: Winter	9.000	7.440	7.557	0.117	44.1	0.133	0.000	44.0	28.301	OK
Manhole (40)	FSR: 10 years: +0 %: 15 mins: Winter	9.000	7.600	7.705	0.105	9.9	0.119	0.000	10.0	4.722	OK
Manhole (41)	FSR: 10 years: +0 %: 15 mins: Winter	9.000	7.440	7.507	0.067	19.8	0.076	0.000	19.8	9.388	OK
Pond Outfall	FSR: 10 years: +0 %: 720 mins: Winter	6.100	3.450	3.924	0.474	29.7	2.518	0.000	29.7	1680.548	OK
Manhole (43)	FSR: 10 years: +0 %: 120 mins: Winter	4.000	3.000	3.181	0.181	97.5	0.204	0.000	76.4	626.454	OK
38	FSR: 10 years: +0 %: 480 mins: Winter	3.690	1.820	3.214	1.394	614.9	1.577	0.000	615.1	15607.898	Surcharged
ExMH5	FSR: 10 years: +0 %: 480 mins: Winter	4.500	-4.000	3.157	7.157	617.0	8.094	0.000	617.0	15998.195	Surcharged
ExMH4a	FSR: 10 years: +0 %: 480 mins: Winter	4.500	-4.110	3.147	7.257	617.0	8.208	0.000	617.0	15896.698	Surcharged
ExMH4	FSR: 10 years: +0 %: 480 mins: Winter	4.500	-4.220	3.138	7.358	617.0	8.322	0.000	617.0	15832.768	Surcharged
ExMH	FSR: 10 years: +0 %: 480 mins: Winter	4.500	-0.667	3.121	3.788	617.0	4.284	0.000	617.0	15803.199	Surcharged
S	FSR: 10 years: +0 %: 480 mins: Winter	4.300	-0.745	3.108	3.853	617.4	0.000	0.000	617.4	15896.822	OK
Manhole (44)	FSR: 10 years: +0 %: 15 mins: Winter	4.000	2.500	3.280	0.780	64.4	0.882	0.000	63.9	28.070	Surcharged
Manhole (45)	FSR: 10 years: +0 %: 15 mins: Winter	4.000	-3.175	3.119	6.294	165.1	7.118	0.000	162.7	134.569	Surcharged
Manhole	FSR: 10 years: +0 %: 15 mins: Winter	10.030	6.640	8.490	1.850	242.0	2.092	0.000	236.4	340.192	Surcharged
Manhole (1)	FSR: 10 years: +0 %: 15 mins: Winter	10.100	6.840	9.033	2.193	250.6	2.481	0.000	242.0	341.413	Surcharged
Manhole (2)	FSR: 10 years: +0 %: 15 mins: Winter	10.600	9.200	10.011	0.811	33.9	0.918	0.000	24.7	22.854	Surcharged
Manhole (3)	FSR: 10 years: +0 %: 15 mins: Winter	10.600	9.200	10.011	0.811	33.9	0.918	0.000	24.7	22.855	Surcharged
Manhole (4)	FSR: 10 years: +0 %: 15 mins: Winter	10.600	9.200	10.043	0.843	31.5	0.953	0.000	22.0	21.410	Surcharged

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Junctions Summary Storm Phase: Phase		Company Address:			


Manhole (5)	FSR: 10 years: +0 %: 15 mins: Winter	10.10 0	7.100	9.452	2.352	211.3	2.660	0.000	191.9	288.086	Surcharged
Manhole (6)	FSR: 10 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.042	0.842	31.2	0.952	0.000	22.0	21.408	Surcharged
Manhole (7)	FSR: 10 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.101	0.901	31.6	1.019	0.000	20.4	21.412	Surcharged
Manhole (18)	FSR: 10 years: +0 %: 30 mins: Winter	10.10 0	7.380	9.632	2.252	151.3	2.547	0.000	155.6	308.812	Surcharged
Manhole (19)	FSR: 10 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.099	0.899	32.6	1.017	0.000	20.4	21.404	Surcharged
Manhole (20)	FSR: 10 years: +0 %: 30 mins: Winter	10.60 0	9.200	10.260	1.060	26.8	1.198	0.000	20.3	28.673	Surcharged
Manhole (21)	FSR: 10 years: +0 %: 30 mins: Winter	10.10 0	7.650	9.948	2.298	121.2	2.599	0.000	125.1	233.721	Flood Risk
Manhole (22)	FSR: 10 years: +0 %: 30 mins: Winter	10.60 0	9.200	10.259	1.059	29.2	1.197	0.000	20.3	28.671	Surcharged
Manhole (23)	FSR: 10 years: +0 %: 30 mins: Winter	10.60 0	9.200	10.342	1.142	27.8	1.292	0.000	20.0	28.708	Flood Risk
Manhole (24)	FSR: 10 years: +0 %: 60 mins: Winter	10.10 0	7.920	9.945	2.025	84.0	2.290	0.000	89.4	203.228	Flood Risk
Manhole (25)	FSR: 10 years: +0 %: 30 mins: Winter	10.60 0	9.200	10.342	1.142	33.0	1.292	0.000	20.1	28.705	Flood Risk
Manhole (26)	FSR: 10 years: +0 %: 30 mins: Winter	10.60 0	9.200	10.382	1.182	28.7	1.337	0.000	19.9	29.253	Flood Risk
Manhole (27)	FSR: 10 years: +0 %: 120 mins: Winter	10.10 0	8.100	9.583	1.483	40.9	1.678	0.000	47.2	134.177	Surcharged
Manhole (28)	FSR: 10 years: +0 %: 30 mins: Winter	10.60 0	9.200	10.383	1.183	20.0	1.338	0.000	20.0	29.271	Flood Risk

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Summary Storm Phase: Phase	Company Address:		



FSR: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
Manhole (9)	FSR: 100 years: +0 %: 15 mins: Winter	9.600	6.000	7.117	1.117	245.7	1.263	0.000	243.3	553.315	Surcharged
Manhole (10)	FSR: 100 years: +0 %: 15 mins: Winter	8.740	4.690	5.034	0.344	274.4	0.389	0.000	271.9	568.540	OK
Manhole (11)	FSR: 100 years: +0 %: 15 mins: Winter	8.280	4.600	4.969	0.369	321.1	0.418	0.000	316.0	614.543	OK
Manhole (12)	FSR: 100 years: +0 %: 15 mins: Winter	7.980	4.510	4.883	0.373	342.9	0.422	0.000	339.4	629.826	OK
Manhole (13)	FSR: 100 years: +0 %: 30 mins: Winter	7.890	4.430	4.796	0.366	337.0	0.414	0.000	335.7	858.155	OK
Manhole (14)	FSR: 100 years: +0 %: 30 mins: Winter	7.850	4.290	4.666	0.376	335.7	0.425	0.000	333.1	858.040	OK
Manhole (15)	FSR: 100 years: +0 %: 30 mins: Winter	7.115	4.180	4.565	0.385	333.1	0.435	0.000	337.0	857.845	OK
Manhole (16)	FSR: 100 years: +0 %: 30 mins: Winter	7.435	4.070	4.481	0.411	337.0	0.465	0.000	361.5	861.047	OK
Manhole (17)	FSR: 100 years: +0 %: 30 mins: Winter	6.245	3.865	4.404	0.539	760.5	0.610	0.000	754.1	1271.117	OK
Manhole (36)	FSR: 100 years: +0 %: 15 mins: Winter	9.000	7.600	7.834	0.234	18.9	0.265	0.000	15.9	7.613	Surcharged
Manhole (37)	FSR: 100 years: +0 %: 15 mins: Winter	9.000	7.440	7.532	0.092	31.8	0.104	0.000	31.9	15.183	OK
Manhole (38)	FSR: 100 years: +0 %: 30 mins: Winter	9.000	7.600	8.836	1.236	31.2	1.398	0.000	33.1	41.522	Flood Risk
Manhole (39)	FSR: 100 years: +0 %: 15 mins: Winter	9.000	7.440	8.040	0.600	54.0	0.679	0.000	49.3	45.627	Surcharged
Manhole (40)	FSR: 100 years: +0 %: 15 mins: Winter	9.000	7.600	7.825	0.225	18.1	0.255	0.000	15.6	7.614	Surcharged
Manhole (41)	FSR: 100 years: +0 %: 15 mins: Winter	9.000	7.440	7.529	0.089	31.4	0.101	0.000	31.5	15.144	OK
Pond Outfall	FSR: 100 years: +0 %: 720 mins: Winter	6.100	3.450	4.026	0.576	33.2	3.059	0.000	33.2	2245.499	Surcharged
Manhole (43)	FSR: 100 years: +0 %: 240 mins: Winter	4.000	3.000	3.396	0.396	129.4	0.448	0.000	81.9	673.836	OK
38	FSR: 100 years: +0 %: 480 mins: Winter	3.690	1.820	3.442	1.622	1097.9	1.835	0.000	1097.5	27514.611	Flood Risk
ExMH5	FSR: 100 years: +0 %: 480 mins: Winter	4.500	-4.000	3.260	7.260	1097.5	8.211	0.000	1097.5	28216.535	Surcharged
ExMH4a	FSR: 100 years: +0 %: 480 mins: Winter	4.500	-4.110	3.231	7.341	1097.5	8.302	0.000	1097.5	28118.844	Surcharged
ExMH4	FSR: 100 years: +0 %: 480 mins: Winter	4.500	-4.220	3.201	7.421	1097.5	8.394	0.000	1097.5	28054.840	Surcharged
ExMH	FSR: 100 years: +0 %: 480 mins: Winter	4.500	-0.667	3.148	3.815	1097.5	4.315	0.000	1097.5	28025.164	Surcharged
S	FSR: 100 years: +0 %: 480 mins: Winter	4.300	-0.745	3.108	3.853	1097.5	0.000	0.000	1097.5	28181.016	OK
Manhole (44)	FSR: 100 years: +0 %: 15 mins: Winter	4.000	2.500	3.535	1.035	103.7	1.171	0.000	102.7	46.250	Surcharged
Manhole (45)	FSR: 100 years: +0 %: 30 mins: Winter	4.000	-3.175	3.145	6.320	287.7	7.148	0.000	281.7	308.758	Surcharged
Manhole	FSR: 100 years: +0 %: 15 mins: Winter	10.030	6.640	8.806	2.166	254.8	2.450	0.000	245.7	551.660	Surcharged
Manhole (1)	FSR: 100 years: +0 %: 15 mins: Winter	10.100	6.840	9.404	2.564	261.9	2.899	0.000	254.8	552.926	Surcharged
Manhole (2)	FSR: 100 years: +0 %: 15 mins: Winter	10.600	9.200	10.586	1.386	50.1	1.567	0.000	24.9	36.949	Flood Risk
Manhole (3)	FSR: 100 years: +0 %: 15 mins: Winter	10.600	9.200	10.586	1.386	50.8	1.567	0.000	25.0	36.947	Flood Risk
Manhole (4)	FSR: 100 years: +0 %: 15 mins: Winter	10.600	9.200	10.594	1.394	51.8	1.576	0.000	22.1	34.612	Flood Risk

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Junctions Summary Storm Phase: Phase		Company Address:			


Manhole (5)	FSR: 100 years: +0 %: 15 mins: Winter	10.10 0	7.100	9.830	2.730	218.7	3.088	0.000	201.1	466.937	Flood Risk
Manhole (6)	FSR: 100 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.594	1.394	54.0	1.577	0.000	22.2	34.610	Flood Risk
Manhole (7)	FSR: 100 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.595	1.395	39.0	1.578	0.000	21.2	34.606	Flood Risk
Manhole (18)	FSR: 100 years: +0 %: 60 mins: Winter	10.10 0	7.380	9.889	2.509	171.9	2.838	0.000	173.1	661.514	Flood Risk
Manhole (19)	FSR: 100 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.596	1.396	25.6	1.579	0.000	21.5	34.598	Flood Risk
Manhole (20)	FSR: 100 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	25.4	1.587	0.003	20.8	35.321	Flood
Manhole (21)	FSR: 100 years: +0 %: 60 mins: Winter	10.10 0	7.650	10.090	2.440	153.7	2.760	0.000	154.3	500.618	Flood Risk
Manhole (22)	FSR: 100 years: +0 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	25.5	1.585	0.001	21.1	35.053	Flood
Manhole (23)	FSR: 100 years: +0 %: 60 mins: Winter	10.60 0	9.200	10.596	1.396	22.2	1.579	0.000	21.2	61.673	Flood Risk
Manhole (24)	FSR: 100 years: +0 %: 60 mins: Winter	10.10 0	7.920	10.124	2.204	123.5	26.617	24.152	123.8	339.836	Flood
Manhole (25)	FSR: 100 years: +0 %: 60 mins: Winter	10.60 0	9.200	10.597	1.397	20.0	1.581	0.000	21.2	61.682	Flood Risk
Manhole (26)	FSR: 100 years: +0 %: 60 mins: Winter	10.60 0	9.200	10.599	1.399	20.7	1.582	0.000	22.0	62.799	Flood Risk
Manhole (27)	FSR: 100 years: +0 %: 60 mins: Winter	10.10 0	8.100	10.148	2.048	63.0	50.400	48.138	101.3	179.264	Flood
Manhole (28)	FSR: 100 years: +0 %: 60 mins: Winter	10.60 0	9.200	10.599	1.399	20.7	1.582	0.000	22.0	62.812	Flood Risk

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Junctions Summary Storm Phase: Phase	Company Address:		





FSR: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Outflow

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
Manhole (9)	FSR: 100 years: +45 %: 15 mins: Winter	9.600	6.000	7.202	1.202	253.8	1.360	0.000	251.7	807.359	Surcharged
Manhole (10)	FSR: 100 years: +45 %: 15 mins: Winter	8.740	4.690	5.050	0.360	293.7	0.407	0.000	291.2	829.433	OK
Manhole (11)	FSR: 100 years: +45 %: 15 mins: Winter	8.280	4.600	4.986	0.386	342.5	0.437	0.000	338.0	896.008	OK
Manhole (12)	FSR: 100 years: +45 %: 15 mins: Winter	7.980	4.510	4.905	0.395	376.9	0.447	0.000	372.0	918.139	OK
Manhole (13)	FSR: 100 years: +45 %: 30 mins: Winter	7.890	4.430	4.819	0.389	370.1	0.440	0.000	367.0	1242.287	OK
Manhole (14)	FSR: 100 years: +45 %: 15 mins: Winter	7.850	4.290	4.714	0.424	361.6	0.480	0.000	376.7	918.095	OK
Manhole (15)	FSR: 100 years: +45 %: 15 mins: Winter	7.115	4.180	4.642	0.462	376.7	0.523	0.000	393.7	922.414	OK
Manhole (16)	FSR: 100 years: +45 %: 15 mins: Winter	7.435	4.070	4.564	0.494	393.7	0.559	0.000	440.0	957.083	OK
Manhole (17)	FSR: 100 years: +45 %: 30 mins: Winter	6.245	3.865	4.503	0.638	1024.9	0.721	0.000	1013.5	1839.501	OK
Manhole (36)	FSR: 100 years: +45 %: 15 mins: Winter	9.000	7.600	7.967	0.367	19.6	0.416	0.000	19.2	11.050	Surcharged
Manhole (37)	FSR: 100 years: +45 %: 15 mins: Winter	9.000	7.440	7.554	0.114	42.1	0.129	0.000	42.0	22.034	OK
Manhole (38)	FSR: 100 years: +45 %: 60 mins: Winter	9.000	7.600	8.838	1.238	33.2	1.400	0.000	34.2	78.343	Flood Risk
Manhole (39)	FSR: 100 years: +45 %: 15 mins: Winter	9.000	7.440	8.349	0.909	69.1	1.028	0.000	52.3	66.188	Surcharged
Manhole (40)	FSR: 100 years: +45 %: 15 mins: Winter	9.000	7.600	7.966	0.366	19.6	0.414	0.000	19.2	11.051	Surcharged
Manhole (41)	FSR: 100 years: +45 %: 15 mins: Winter	9.000	7.440	7.551	0.111	42.0	0.126	0.000	42.0	21.981	OK
Pond Outfall	FSR: 100 years: +45 %: 960 mins: Winter	6.100	3.450	4.157	0.707	37.2	3.753	0.000	37.2	3319.693	Surcharged
Manhole (43)	FSR: 100 years: +45 %: 60 mins: Winter	4.000	3.000	3.395	0.395	220.3	0.446	0.000	99.3	802.291	OK
38	FSR: 100 years: +45 %: 480 mins: Winter	3.690	1.820	3.853	2.033	1662.5	284.441	282.326	1646.5	42203.512	Flood
ExMH5	FSR: 100 years: +45 %: 480 mins: Winter	4.500	-4.000	3.449	7.449	1646.5	8.424	0.000	1646.5	43261.422	Surcharged
ExMH4a	FSR: 100 years: +45 %: 480 mins: Winter	4.500	-4.110	3.382	7.492	1646.5	8.474	0.000	1646.5	43164.895	Surcharged

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Junctions Summary Storm Phase: Phase		Company Address:			


ExMH4	FSR: 100 years: +45 %: 480 mins: Winter	4.500	-4.220	3.317	7.537	1646.5	8.524	0.000	1646.5	43100.762	Surcharged
ExMH	FSR: 100 years: +45 %: 480 mins: Winter	4.500	-0.667	3.199	3.866	1646.5	4.372	0.000	1646.5	43070.898	Surcharged
S	FSR: 100 years: +45 %: 600 mins: Winter	4.300	-0.745	3.108	3.853	1647.4	0.000	0.000	1647.4	46912.879	OK
Manhole (44)	FSR: 100 years: +45 %: 15 mins: Winter	4.000	2.500	3.976	1.476	150.4	1.669	0.000	148.5	67.797	Flood Risk
Manhole (45)	FSR: 100 years: +45 %: 30 mins: Winter	4.000	-3.175	3.452	6.627	417.2	7.495	0.000	415.6	455.514	Surcharged
Manhole	FSR: 100 years: +45 %: 15 mins: Winter	10.03 0	6.640	8.994	2.354	262.5	2.663	0.000	253.8	805.759	Surcharged
Manhole (1)	FSR: 100 years: +45 %: 15 mins: Winter	10.10 0	6.840	9.624	2.784	277.2	3.148	0.000	262.5	806.960	Surcharged
Manhole (2)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.599	1.399	40.7	1.582	0.000	26.0	53.674	Flood Risk
Manhole (3)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.599	1.399	41.0	1.582	0.000	26.0	53.673	Flood Risk
Manhole (4)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	39.4	1.587	0.003	23.4	50.376	Flood
Manhole (5)	FSR: 100 years: +45 %: 15 mins: Winter	10.10 0	7.100	10.011	2.911	233.4	3.293	0.000	209.7	682.186	Flood Risk
Manhole (6)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	40.6	1.584	0.000	23.5	50.554	Flood
Manhole (7)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	51.4	1.585	0.002	22.4	50.547	Flood
Manhole (18)	FSR: 100 years: +45 %: 120 mins: Winter	10.10 0	7.380	9.932	2.552	179.7	2.887	0.000	180.3	1210.207	Flood Risk
Manhole (19)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.597	1.397	55.3	1.580	0.000	22.6	50.336	Flood Risk
Manhole (20)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	26.9	1.588	0.004	19.7	51.367	Flood
Manhole (21)	FSR: 100 years: +45 %: 120 mins: Winter	10.10 0	7.650	10.104	2.454	162.5	6.583	3.812	162.9	915.470	Flood
Manhole (22)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	24.6	1.586	0.003	19.8	51.520	Flood
Manhole (23)	FSR: 100 years: +45 %: 30 mins: Winter	10.60 0	9.200	10.600	1.400	20.5	1.588	0.004	21.7	71.725	Flood
Manhole (24)	FSR: 100 years: +45 %: 120 mins: Winter	10.10 0	7.920	10.159	2.239	141.6	61.577	59.112	141.9	620.833	Flood
Manhole (25)	FSR: 100 years: +45 %: 15 mins: Winter	10.60 0	9.200	10.600	1.400	24.6	1.589	0.006	21.5	53.414	Flood
Manhole (26)	FSR: 100 years: +45 %: 180 mins: Winter	10.60 0	9.200	10.597	1.397	21.9	1.580	0.000	23.3	130.265	Flood Risk
Manhole (27)	FSR: 100 years: +45 %: 120 mins: Winter	10.10 0	8.100	10.188	2.088	61.3	90.239	87.977	116.8	328.238	Flood

Project Wind: Phase 1 Enabling Works			Date: 16/04/2025								
			Designed by:	Checked by:	Approved By:						
			BOW	DD	DD						
Report Details: Type: Junctions Summary Storm Phase: Phase			Company Address:								
Manhole (28)	FSR: 100 years: +45 %: 60 mins: Winter	10.60 0	9.200	10.600	1.400	22.3	1.585	0.002	23.7	96.464	Flood


Project Wind: Phase 1 Enabling Works	Date: 16/04/2025			
	Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase	Company Address:			



**FSR: 1 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max.
Avg. Depth**

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Company Address:			


Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Residual Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
Pond	FSR: 1 years: +0 %: 720 mins: Winter	3.871	3.871	1.071	1.071	70.0	8220.134	0.000	0.000	27.3	940.222	78.082	OK
Soakaway (20)	FSR: 1 years: +0 %: 15 mins: Winter	7.875	7.875	0.025	0.025	5.3	0.221	0.000	0.000	5.2	2.455	97.469	OK
Soakaway (21)	FSR: 1 years: +0 %: 15 mins: Winter	7.876	7.876	0.026	0.026	5.3	0.244	0.000	0.000	5.2	2.440	97.375	OK
Soakaway (22)	FSR: 1 years: +0 %: 15 mins: Winter	7.884	7.884	0.034	0.034	10.6	0.318	0.000	0.000	10.5	4.904	96.580	OK
Soakaway (23)	FSR: 1 years: +0 %: 15 mins: Winter	7.923	7.923	0.073	0.073	21.2	0.687	0.000	0.000	22.3	9.788	92.724	OK
Soakaway (24)	FSR: 1 years: +0 %: 15 mins: Winter	7.877	7.877	0.027	0.027	5.3	0.250	0.000	0.000	5.2	2.446	97.345	OK
Soakaway (25)	FSR: 1 years: +0 %: 15 mins: Winter	7.878	7.878	0.028	0.028	5.3	0.259	0.000	0.000	5.1	2.440	97.208	OK
Cow Gut Diversion	FSR: 1 years: +0 %: 480 mins: Winter	3.386	3.174	0.386	0.174	339.6	57.916	0.000	0.000	339.6	8636.320	86.635	OK
Soakaway	FSR: 1 years: +0 %: 15 mins: Winter	9.664	9.664	0.064	0.064	25.9	1.202	0.000	0.000	25.0	11.940	93.588	OK
Soakaway (1)	FSR: 1 years: +0 %: 15 mins: Winter	9.658	9.658	0.058	0.058	24.3	1.085	0.000	0.000	24.1	11.191	94.214	OK
Soakaway (2)	FSR: 1 years: +0 %: 15 mins: Winter	9.666	9.666	0.066	0.066	24.3	1.233	0.000	0.000	26.2	11.191	93.421	OK
Soakaway (3)	FSR: 1 years: +0 %: 15 mins: Winter	9.706	9.706	0.106	0.106	24.3	1.994	0.000	0.000	23.3	11.193	89.366	OK
Soakaway (4)	FSR: 1 years: +0 %: 15 mins: Winter	9.734	9.734	0.134	0.134	24.3	2.517	0.000	0.000	26.0	11.192	86.575	OK
Soakaway (5)	FSR: 1 years: +0 %: 15 mins: Winter	9.746	9.746	0.146	0.146	24.6	2.740	0.000	0.000	27.9	11.363	85.384	OK
Soakaway (6)	FSR: 1 years: +0 %: 15 mins: Winter	9.664	9.664	0.064	0.064	25.9	1.192	0.000	0.000	25.0	11.940	93.644	OK
Soakaway (7)	FSR: 1 years: +0 %: 15 mins: Winter	9.656	9.656	0.056	0.056	24.3	1.045	0.000	0.000	24.0	11.193	94.426	OK
Soakaway (8)	FSR: 1 years: +0 %: 15 mins: Winter	9.663	9.663	0.063	0.063	24.3	1.180	0.000	0.000	23.3	11.190	93.705	OK
Soakaway (9)	FSR: 1 years: +0 %: 15 mins: Winter	9.703	9.703	0.103	0.103	24.3	1.928	0.000	0.000	22.7	11.193	89.718	OK
Soakaway (10)	FSR: 1 years: +0 %: 15 mins: Winter	9.730	9.730	0.130	0.130	24.3	2.444	0.000	0.000	31.0	11.195	86.963	OK
Soakaway (11)	FSR: 1 years: +0 %: 15 mins: Winter	9.743	9.743	0.143	0.143	24.6	2.680	0.000	0.000	35.4	11.365	85.708	OK

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD		Approved By: DD
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Company Address:			




FSR: 10 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Residual Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
Pond	FSR: 10 years: +0 %: 720 mins: Winter	3.930	3.930	1.130	1.130	120.7	8850.976	0.000	0.000	29.7	1681.466	76.400	OK
Soakaway (20)	FSR: 10 years: +0 %: 15 mins: Winter	7.885	7.885	0.035	0.035	10.3	0.308	0.000	0.000	10.1	4.751	96.479	OK
Soakaway (21)	FSR: 10 years: +0 %: 15 mins: Winter	7.889	7.889	0.039	0.039	10.2	0.360	0.000	0.000	9.9	4.723	96.123	OK
Soakaway (22)	FSR: 10 years: +0 %: 15 mins: Winter	7.901	7.901	0.051	0.051	20.5	0.478	0.000	0.000	20.2	9.484	94.859	OK
Soakaway (23)	FSR: 10 years: +0 %: 15 mins: Winter	8.309	8.309	0.459	0.459	41.0	4.333	0.000	0.000	26.3	18.938	54.100	OK
Soakaway (24)	FSR: 10 years: +0 %: 15 mins: Winter	7.887	7.887	0.037	0.037	10.2	0.346	0.000	0.000	10.1	4.735	96.328	OK
Soakaway (25)	FSR: 10 years: +0 %: 15 mins: Winter	7.890	7.890	0.040	0.040	10.2	0.374	0.000	0.000	9.9	4.723	95.974	OK
Cow Gut Diversion	FSR: 10 years: +0 %: 480 mins: Winter	3.476	3.248	0.476	0.248	585.2	82.172	0.000	0.000	585.2	14609.578	81.037	OK
Soakaway	FSR: 10 years: +0 %: 15 mins: Winter	10.019	10.019	0.419	0.419	50.0	7.866	0.000	0.000	33.9	23.094	58.049	OK
Soakaway (1)	FSR: 10 years: +0 %: 30 mins: Winter	10.050	10.050	0.450	0.450	36.9	8.444	0.000	0.000	24.4	28.825	54.963	OK
Soakaway (2)	FSR: 10 years: +0 %: 30 mins: Winter	10.125	10.125	0.525	0.525	36.9	9.845	0.000	0.000	24.3	28.828	47.492	OK
Soakaway (3)	FSR: 10 years: +0 %: 30 mins: Winter	10.263	10.263	0.663	0.663	36.9	12.426	0.000	0.000	26.8	28.831	33.730	OK
Soakaway (4)	FSR: 10 years: +0 %: 30 mins: Winter	10.345	10.345	0.745	0.745	36.8	13.968	0.000	0.000	27.8	28.829	25.505	OK
Soakaway (5)	FSR: 10 years: +0 %: 30 mins: Winter	10.384	10.384	0.784	0.784	37.4	14.711	0.000	0.000	28.7	29.266	21.543	OK

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Company Address:			


Soakaway (6)	FSR: 10 years: +0 %: 15 mins: Winter	10.019	10.019	0.419	0.419	50.0	7.861	0.000	0.000	33.9	23.094	58.077	OK
Soakaway (7)	FSR: 10 years: +0 %: 30 mins: Winter	10.049	10.049	0.449	0.449	36.9	8.423	0.000	0.000	24.4	28.828	55.076	OK
Soakaway (8)	FSR: 10 years: +0 %: 30 mins: Winter	10.123	10.123	0.523	0.523	36.8	9.805	0.000	0.000	24.1	28.825	47.708	OK
Soakaway (9)	FSR: 10 years: +0 %: 30 mins: Winter	10.261	10.261	0.661	0.661	36.9	12.391	0.000	0.000	29.2	28.830	33.915	OK
Soakaway (10)	FSR: 10 years: +0 %: 30 mins: Winter	10.344	10.344	0.744	0.744	36.9	13.944	0.000	0.000	33.0	28.835	25.634	OK
Soakaway (11)	FSR: 10 years: +0 %: 30 mins: Winter	10.384	10.384	0.784	0.784	37.4	14.710	0.000	0.000	20.0	29.270	21.545	OK

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025			
	Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase	Company Address:			




FSR: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Residual Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
Pond	FSR: 100 years: +0 %: 720 mins: Winter	4.029	4.029	1.229	1.229	197.1	9924.854	0.000	0.000	33.2	2249.715	73.537	OK
Soakaway (20)	FSR: 100 years: +0 %: 15 mins: Winter	7.896	7.896	0.046	0.046	16.6	0.406	0.000	0.000	16.3	7.652	95.363	OK
Soakaway (21)	FSR: 100 years: +0 %: 15 mins: Winter	7.900	7.900	0.050	0.050	16.5	0.464	0.000	0.000	18.9	7.608	94.998	OK
Soakaway (22)	FSR: 100 years: +0 %: 15 mins: Winter	8.045	8.045	0.195	0.195	33.1	1.812	0.000	0.000	29.1	15.278	80.510	OK
Soakaway (23)	FSR: 100 years: +0 %: 15 mins: Winter	8.898	8.898	1.048	1.048	66.0	11.268	1.827	0.000	31.5	30.497	-19.364	Flood
Soakaway (24)	FSR: 100 years: +0 %: 15 mins: Winter	7.898	7.898	0.048	0.048	16.5	0.453	0.000	0.000	16.3	7.628	95.185	OK
Soakaway (25)	FSR: 100 years: +0 %: 15 mins: Winter	7.902	7.902	0.052	0.052	16.5	0.479	0.000	0.000	18.1	7.609	94.836	OK
Cow Gut Diversion	FSR: 100 years: +0 %: 480 mins: Winter	3.618	3.487	0.618	0.487	1065.4	143.818	0.000	0.000	1065.1	26287.422	66.811	OK
Soakaway	FSR: 100 years: +0 %: 30 mins: Winter	10.625	10.625	1.025	1.025	64.7	20.633	1.881	0.000	27.8	50.626	-10.044	Flood
Soakaway (1)	FSR: 100 years: +0 %: 30 mins: Winter	10.638	10.638	1.038	1.038	60.7	21.605	2.853	0.000	25.7	47.465	-15.229	Flood
Soakaway (2)	FSR: 100 years: +0 %: 30 mins: Winter	10.665	10.665	1.065	1.065	60.7	23.598	4.846	0.000	32.5	47.468	-25.856	Flood
Soakaway (3)	FSR: 100 years: +0 %: 30 mins: Winter	10.704	10.704	1.104	1.104	60.7	26.568	7.816	0.000	26.3	47.467	-41.695	Flood
Soakaway (4)	FSR: 100 years: +0 %: 30 mins: Winter	10.726	10.726	1.126	1.126	60.7	28.220	9.468	0.000	20.5	47.467	-50.506	Flood
Soakaway (5)	FSR: 100 years: +0 %: 60 mins: Winter	10.738	10.738	1.138	1.138	42.7	29.085	10.333	0.000	20.7	62.718	-55.120	Flood

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Company Address:			


Soakaway (6)	FSR: 100 years: +0 %: 30 mins: Winter	10.625	10.625	1.025	1.025	64.7	20.630	1.878	0.000	27.8	50.630	-10.026	Flood
Soakaway (7)	FSR: 100 years: +0 %: 30 mins: Winter	10.638	10.638	1.038	1.038	60.7	21.578	2.826	0.000	25.5	47.463	-15.085	Flood
Soakaway (8)	FSR: 100 years: +0 %: 30 mins: Winter	10.664	10.664	1.064	1.064	60.7	23.551	4.799	0.000	35.5	47.464	-25.605	Flood
Soakaway (9)	FSR: 100 years: +0 %: 30 mins: Winter	10.710	10.710	1.110	1.110	60.7	27.007	8.255	0.000	20.6	47.468	-44.038	Flood
Soakaway (10)	FSR: 100 years: +0 %: 30 mins: Winter	10.728	10.728	1.128	1.128	60.7	28.379	9.627	0.000	20.5	47.471	-51.356	Flood
Soakaway (11)	FSR: 100 years: +0 %: 60 mins: Winter	10.737	10.737	1.137	1.137	42.7	29.056	10.304	0.000	20.7	62.725	-54.965	Flood

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD		Approved By: DD
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Company Address:			



FSR: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Residual Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
Pond	FSR: 100 years: +45 %: 960 mins: Winter	4.159	4.159	1.359	1.359	230.7	11370.967	0.000	0.000	37.2	3324.609	69.681	OK
Soakaway (20)	FSR: 100 years: +45 %: 15 mins: Winter	7.908	7.908	0.058	0.058	24.0	0.509	0.000	0.000	23.7	11.092	94.183	OK
Soakaway (21)	FSR: 100 years: +45 %: 15 mins: Winter	7.970	7.970	0.120	0.120	23.9	1.114	0.000	0.000	19.6	11.027	88.005	OK
Soakaway (22)	FSR: 100 years: +45 %: 15 mins: Winter	8.363	8.363	0.513	0.513	47.9	4.769	0.000	0.000	45.2	22.141	48.701	OK
Soakaway (23)	FSR: 100 years: +45 %: 30 mins: Winter	9.258	9.258	1.408	1.408	76.9	24.857	15.416	0.000	32.4	60.173	-163.324	Flood
Soakaway (24)	FSR: 100 years: +45 %: 15 mins: Winter	7.910	7.910	0.060	0.060	23.9	0.566	0.000	0.000	23.6	11.055	93.989	OK
Soakaway (25)	FSR: 100 years: +45 %: 15 mins: Winter	7.970	7.970	0.120	0.120	23.9	1.111	0.000	0.000	19.6	11.030	88.026	OK
Cow Gut Diversion	FSR: 100 years: +45 %: 480 mins: Winter	4.151	4.108	1.151	1.108	1666.1	550.265	116.932	0.000	1645.8	40896.762	-26.984	Flood
Soakaway	FSR: 100 years: +45 %: 30 mins: Winter	10.874	10.874	1.274	1.274	93.9	39.321	20.569	0.000	26.0	73.405	-109.713	Flood
Soakaway (1)	FSR: 100 years: +45 %: 30 mins: Winter	10.885	10.885	1.285	1.285	88.0	40.145	21.393	0.000	24.2	68.815	-114.108	Flood
Soakaway (2)	FSR: 100 years: +45 %: 60 mins: Winter	10.948	10.948	1.348	1.348	61.0	44.873	26.121	0.000	24.0	89.583	-139.321	Flood
Soakaway (3)	FSR: 100 years: +45 %: 60 mins: Winter	11.012	11.012	1.412	1.412	61.0	49.692	30.940	0.000	19.3	89.587	-165.023	Flood
Soakaway (4)	FSR: 100 years: +45 %: 60 mins: Winter	11.035	11.035	1.435	1.435	61.0	51.394	32.642	0.000	20.3	89.572	-174.100	Flood
Soakaway (5)	FSR: 100 years: +45 %: 60 mins: Winter	11.044	11.044	1.444	1.444	62.0	52.025	33.273	0.000	21.2	90.927	-177.469	Flood

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Company Address:			


Soakaway (6)	FSR: 100 years: +45 %: 30 mins: Winter	10.874	10.874	1.274	1.274	93.8	39.314	20.56 1	0.000	26.0	73.401	-109.672	Flood
Soakaway (7)	FSR: 100 years: +45 %: 30 mins: Winter	10.888	10.888	1.288	1.288	88.0	40.377	21.62 5	0.000	24.0	68.817	-115.345	Flood
Soakaway (8)	FSR: 100 years: +45 %: 60 mins: Winter	10.933	10.933	1.333	1.333	61.0	43.729	24.97 7	0.000	28.5	89.569	-133.219	Flood
Soakaway (9)	FSR: 100 years: +45 %: 60 mins: Winter	11.017	11.017	1.417	1.417	61.0	50.026	31.27 4	0.000	18.9	89.589	-166.807	Flood
Soakaway (10)	FSR: 100 years: +45 %: 60 mins: Winter	11.036	11.036	1.436	1.436	61.0	51.465	32.71 3	0.000	21.3	89.589	-174.481	Flood
Soakaway (11)	FSR: 100 years: +45 %: 60 mins: Winter	11.066	11.066	1.466	1.466	62.0	53.741	34.98 9	0.000	22.3	90.939	-186.617	Flood

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Connections Summary Storm Phase: Phase	Company Address:		




FSR: 1 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow

Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
Pipe (9)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (9)	Manhole (10)	9.600	6.732	0.375	176.545	1.9	1.3	206.7	Surcharged
Pipe (10)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (10)	Manhole (11)	8.740	4.984	0.297	181.414	1.0	0.11	213.5	OK
Pipe (11)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (11)	Manhole (12)	8.280	4.905	0.304	261.124	1.0	0.12	228.5	OK
Pipe (12)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (12)	Manhole (13)	7.980	4.814	0.300	267.629	1.1	0.12	232.7	OK
Pipe (13)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (13)	Manhole (14)	7.890	4.726	0.296	267.847	1.1	0.12	231.2	OK
Pipe (14)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (14)	Manhole (15)	7.850	4.588	0.295	267.745	1.1	0.12	228.0	OK
Pipe (15)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (15)	Manhole (16)	7.115	4.473	0.286	267.827	1.1	0.12	224.7	OK
Pipe (16)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (16)	Manhole (17)	7.435	4.350	0.293	266.314	1.0	0.11	222.2	OK
Pipe (35)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (36)	Manhole (37)	9.000	7.670	0.059	2.438	0.8	0.41	5.1	OK
Pipe (36)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (37)	Manhole (10)	9.000	7.487	0.150	4.873	1.8	0.22	10.4	OK
Pipe (37)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (38)	Manhole (39)	9.000	7.920	0.150	9.795	1.0	1.48	18.4	Surcharged
Pipe (38)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (39)	Manhole (11)	9.000	7.524	0.150	14.617	2.4	0.6	28.6	OK
Pipe (39)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (40)	Manhole (41)	9.000	7.670	0.059	2.439	0.8	0.41	5.1	OK
Pipe (40)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (41)	Manhole (12)	9.000	7.487	0.150	4.862	1.4	0.21	10.2	OK
Pipe (41)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (17)	Pond	6.245	4.172	0.289	395.744	1.3	0.13	262.4	OK
Pipe (42)	FSR: 1 years: +0 %: 600 mins: Winter	Pipe	Pond	Pond Outfall	6.100	3.871	0.239	839.300	0.5	0.04	27.3	OK
Pipe (43)	FSR: 1 years: +0 %: 720 mins: Winter	Pipe	Pond Outfall	Manhole (43)	6.100	3.857	0.108	939.601	0.9	0.04	27.1	OK
Pipe (66)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (20)	Manhole (37)	8.850	7.875	0.036	2.455	1.2	0.02	5.2	OK
Pipe (67)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (21)	Manhole (36)	8.850	7.876	0.048	2.440	0.8	0.02	5.2	OK

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Connections Summary Storm Phase: Phase		Company Address:			

Pipe (68)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (22)	Manhole (39)	8.850	7.884	0.059	4.904	1.2	0.04	10.5	OK
Pipe (69)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (23)	Manhole (38)	8.850	7.923	0.196	9.788	1.0	0.11	22.3	OK
Pipe (70)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (24)	Manhole (41)	8.850	7.877	0.037	2.446	1.2	0.02	5.2	OK
Pipe (71)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (25)	Manhole (40)	8.850	7.878	0.049	2.440	0.8	0.03	5.1	OK
Pipe (72)	FSR: 1 years: +0 %: 480 mins: Winter	Pipe	38	ExMH5	3.690	3.146	0.900	8998.982	1.3	0.05	365.5	Surcharged
Pipe (73)	FSR: 1 years: +0 %: 600 mins: Winter	Pipe	ExMH5	ExMH4a	4.500	3.125	1.200	10112.114	0.8	0.1	367.8	Surcharged
Pipe (74)	FSR: 1 years: +0 %: 600 mins: Winter	Pipe	ExMH4a	ExMH4	4.500	3.122	1.200	10086.643	0.5	0.1	367.8	Surcharged
Pipe (75)	FSR: 1 years: +0 %: 600 mins: Winter	Pipe	ExMH4	ExMH	4.500	3.119	1.200	0.000	0.3	0.43	367.8	Surcharged
Pipe (76)	FSR: 1 years: +0 %: 600 mins: Winter	Pipe	ExMH	S	4.500	3.113	1.200	9993.991	0.3	0.16	367.8	Surcharged
Pipe (77)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (44)	S	4.000	3.159	0.300	13.699	0.5	0.12	33.0	Surcharged
Pipe (78)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Manhole (45)	ExMH5	4.000	3.117	0.525	89.687	1.1	0.21	90.2	Surcharged
Trapezoidal Channel	FSR: 1 years: +0 %: 180 mins: Winter	Trapezoidal Channel	Manhole (43)	38	4.000	3.134	0.724	319.412	0.0	0.01	56.2	OK
Pipe (79)	FSR: 1 years: +0 %: 480 mins: Winter	Pipe	Cow Gut Diversion	38	4.000	3.317	0.750	8636.320	2.7	0.06	339.6	OK
Pipe	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (27)	Manhole (24)	10.100	9.515	0.300	32.613	0.9	0.73	48.4	Surcharged
Pipe (1)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (24)	Manhole (21)	10.100	9.475	0.300	61.649	1.2	1.05	85.1	Surcharged
Pipe (2)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (21)	Manhole (18)	10.100	9.343	0.300	90.739	1.6	1.4	113.8	Surcharged
Pipe (3)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (18)	Manhole (5)	10.100	9.030	0.375	119.836	1.3	0.91	135.4	Surcharged
Pipe (4)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (5)	Manhole (1)	10.100	8.823	0.375	148.819	1.6	1.22	175.4	Surcharged
Pipe (5)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (1)	Manhole	10.100	8.456	0.375	176.345	2.0	1.51	218.8	Surcharged
Pipe (7)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (26)	Manhole (27)	10.600	9.744	0.150	11.231	1.0	0.96	17.9	Surcharged
Pipe (17)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (23)	Manhole (24)	10.600	9.731	0.150	11.010	1.0	0.91	18.2	Surcharged
Pipe (18)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (20)	Manhole (21)	10.600	9.702	0.150	10.991	1.1	0.85	18.8	Surcharged
Pipe (19)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (7)	Manhole (18)	10.600	9.660	0.150	10.997	1.1	0.81	19.4	Surcharged

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025					
		Designed by: BOW	Checked by: DD	Approved By: DD			
Report Details: Type: Connections Summary Storm Phase: Phase		Company Address:					


Pipe (20)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (4)	Manhole (5)	10.600	9.635	0.150	10.988	1.2	0.83	21.4	Surcharged
Pipe (21)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (2)	Manhole (1)	10.600	9.520	0.150	11.736	1.4	0.88	24.1	Surcharged
Pipe (22)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (28)	Manhole (27)	10.600	9.741	0.150	11.222	1.0	0.97	18.0	Surcharged
Pipe (23)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (25)	Manhole (24)	10.600	9.728	0.150	11.000	1.0	0.92	18.5	Surcharged
Pipe (24)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (22)	Manhole (21)	10.600	9.701	0.150	10.986	1.1	0.86	19.0	Surcharged
Pipe (25)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (19)	Manhole (18)	10.600	9.658	0.150	10.994	1.1	0.81	19.4	Surcharged
Pipe (26)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (6)	Manhole (5)	10.600	9.634	0.150	10.987	1.2	0.83	21.4	Surcharged
Pipe (27)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole (3)	Manhole (1)	10.600	9.523	0.150	11.736	1.4	0.88	24.1	Surcharged
Pipe (28)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway	Manhole (2)	10.600	9.664	0.183	11.940	1.7	0.12	25.0	OK
Pipe (29)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (1)	Manhole (4)	10.600	9.658	0.242	11.191	1.7	0.1	24.1	OK
Pipe (30)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (2)	Manhole (7)	10.600	9.666	0.250	11.191	1.6	0.11	26.2	OK
Pipe (31)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (3)	Manhole (20)	10.600	9.706	0.250	11.193	1.5	0.11	23.3	OK
Pipe (32)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (4)	Manhole (23)	10.600	9.734	0.250	11.192	1.5	0.14	26.0	OK
Pipe (33)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (5)	Manhole (26)	10.600	9.746	0.250	11.363	1.4	0.13	27.9	OK
Pipe (34)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (11)	Manhole (28)	10.600	9.743	0.250	11.365	1.8	0.1	35.4	OK
Pipe (44)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (10)	Manhole (25)	10.600	9.730	0.250	11.195	1.6	0.1	31.0	OK
Pipe (45)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Soakaway (9)	Manhole (22)	10.600	9.678	0.250	14.902	1.5	0.07	22.8	OK
Pipe (46)	FSR: 1 years: +0 %: 30 mins: Winter	Pipe	Soakaway (8)	Manhole (19)	10.600	9.646	0.230	14.897	1.6	0.07	24.3	OK
Pipe (47)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (7)	Manhole (6)	10.600	9.656	0.241	11.193	1.7	0.08	24.0	OK
Pipe (48)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Soakaway (6)	Manhole (3)	10.600	9.664	0.184	11.940	1.7	0.12	25.0	OK
Pipe (6)	FSR: 1 years: +0 %: 15 mins: Winter	Pipe	Manhole	Manhole (9)	10.030	7.995	0.375	175.223	1.9	1.45	215.3	Surcharged

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Connections Summary Storm Phase: Phase	Company Address:		




FSR: 10 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow


Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
Pipe (9)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (9)	Manhole (10)	9.600	6.969	0.375	341.767	2.1	1.44	228.5	Surcharged
Pipe (10)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (10)	Manhole (11)	8.740	5.013	0.331	351.212	1.0	0.13	244.1	OK
Pipe (11)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (11)	Manhole (12)	8.280	4.940	0.341	379.849	1.1	0.15	280.0	OK
Pipe (12)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (12)	Manhole (13)	7.980	4.855	0.340	517.827	1.1	0.15	290.6	OK
Pipe (13)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (13)	Manhole (14)	7.890	4.766	0.338	518.090	1.1	0.15	289.0	OK
Pipe (14)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (14)	Manhole (15)	7.850	4.631	0.340	517.990	1.1	0.15	286.8	OK
Pipe (15)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (15)	Manhole (16)	7.115	4.520	0.334	517.931	1.1	0.15	287.7	OK
Pipe (16)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (16)	Manhole (17)	7.435	4.399	0.378	516.078	1.1	0.15	289.0	OK
Pipe (35)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (36)	Manhole (37)	9.000	7.705	0.087	4.722	0.9	0.8	10.0	OK
Pipe (36)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (37)	Manhole (10)	9.000	7.508	0.150	9.413	1.9	0.42	19.9	OK
Pipe (37)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (38)	Manhole (39)	9.000	8.298	0.150	18.962	1.5	2.07	25.8	Surcharged
Pipe (38)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (39)	Manhole (11)	9.000	7.557	0.150	28.301	2.6	0.92	44.0	OK
Pipe (39)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (40)	Manhole (41)	9.000	7.705	0.086	4.722	0.9	0.8	10.0	OK
Pipe (40)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (41)	Manhole (12)	9.000	7.507	0.150	9.388	1.6	0.41	19.8	OK

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025					
	Designed by:	Checked by:	Approved By:			
	BOW	DD	DD			
Report Details: Type: Connections Summary Storm Phase: Phase			Company Address:			

Pipe (41)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (17)	Pond	6.245	4.291	0.399	765.758	1.5	0.25	486.9	OK
Pipe (42)	FSR: 10 years: +0 %: 180 mins: Winter	Pipe	Pond	Pond Outfall	6.100	3.912	0.284	637.915	0.5	0.04	31.1	OK
Pipe (43)	FSR: 10 years: +0 %: 720 mins: Winter	Pipe	Pond Outfall	Manhole (43)	6.100	3.924	0.141	1680.299	1.1	0.05	29.7	OK
Pipe (66)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (20)	Manhole (37)	8.850	7.885	0.052	4.751	1.4	0.04	10.1	OK
Pipe (67)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (21)	Manhole (36)	8.850	7.889	0.072	4.723	1.0	0.05	9.9	OK
Pipe (68)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (22)	Manhole (39)	8.850	7.901	0.084	9.484	1.5	0.08	20.2	OK
Pipe (69)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (23)	Manhole (38)	8.850	8.309	0.250	18.938	1.2	0.13	26.3	Surch arged
Pipe (70)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (24)	Manhole (41)	8.850	7.887	0.052	4.735	1.4	0.05	10.1	OK
Pipe (71)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (25)	Manhole (40)	8.850	7.890	0.073	4.723	0.9	0.05	9.9	OK
Pipe (72)	FSR: 10 years: +0 %: 480 mins: Winter	Pipe	38	ExMH5	3.690	3.214	0.900	15515.80 6	1.2	0.08	615.1	Surch arged
Pipe (73)	FSR: 10 years: +0 %: 480 mins: Winter	Pipe	ExMH5	ExMH4a	4.500	3.157	1.200	15921.03 4	0.8	0.16	617.0	Surch arged
Pipe (74)	FSR: 10 years: +0 %: 480 mins: Winter	Pipe	ExMH4a	ExMH4	4.500	3.147	1.200	15895.56 0	0.5	0.16	617.0	Surch arged
Pipe (75)	FSR: 10 years: +0 %: 480 mins: Winter	Pipe	ExMH4	ExMH	4.500	3.138	1.200	0.000	0.5	0.73	617.0	Surch arged
Pipe (76)	FSR: 10 years: +0 %: 480 mins: Winter	Pipe	ExMH	S	4.500	3.121	1.200	15802.91 3	0.5	0.27	617.0	Surch arged
Pipe (77)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (44)	S	4.000	3.280	0.300	28.070	0.9	0.23	63.9	Surch arged
Pipe (78)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (45)	ExMH5	4.000	3.119	0.525	133.219	1.7	0.38	162.7	Surch arged
Trapezoida l Channel	FSR: 10 years: +0 %: 120 mins: Winter	Trapezoidal Channel	Manhole (43)	38	4.000	3.181	0.770	619.071	0.1	0.01	76.4	OK

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Connections Summary Storm Phase: Phase		Company Address:			

Pipe (79)	FSR: 10 years: +0 %: 480 mins: Winter	Pipe	Cow Gut Diversion	38	4.000	3.398	0.821	14609.578	2.8	0.1	585.2	OK
Pipe	FSR: 10 years: +0 %: 120 mins: Winter	Pipe	Manhole (27)	Manhole (24)	10.100	9.583	0.300	134.177	0.8	0.71	47.2	Surcharged
Pipe (1)	FSR: 10 years: +0 %: 60 mins: Winter	Pipe	Manhole (24)	Manhole (21)	10.100	9.945	0.300	203.228	1.3	1.1	89.4	Flood Risk
Pipe (2)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (21)	Manhole (18)	10.100	9.948	0.300	233.721	1.8	1.54	125.1	Flood Risk
Pipe (3)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (18)	Manhole (5)	10.100	9.632	0.375	308.812	1.4	1.04	155.6	Surcharged
Pipe (4)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (5)	Manhole (1)	10.100	9.452	0.375	288.086	1.7	1.33	191.9	Surcharged
Pipe (5)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (1)	Manhole	10.100	9.033	0.375	341.413	2.2	1.67	242.0	Surcharged
Pipe (7)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (26)	Manhole (27)	10.600	10.382	0.150	29.253	1.1	1.07	19.9	Flood Risk
Pipe (17)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (23)	Manhole (24)	10.600	10.342	0.150	28.708	1.1	1	20.0	Flood Risk
Pipe (18)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (20)	Manhole (21)	10.600	10.260	0.150	28.673	1.1	0.92	20.3	Surcharged
Pipe (19)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (7)	Manhole (18)	10.600	10.101	0.150	21.412	1.2	0.85	20.4	Surcharged
Pipe (20)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (4)	Manhole (5)	10.600	10.043	0.150	21.410	1.2	0.85	22.0	Surcharged
Pipe (21)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (2)	Manhole (1)	10.600	10.011	0.150	22.854	1.4	0.9	24.7	Surcharged
Pipe (22)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (28)	Manhole (27)	10.600	10.383	0.150	29.264	1.1	1.07	20.0	Flood Risk
Pipe (23)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (25)	Manhole (24)	10.600	10.342	0.150	28.705	1.1	1	20.1	Flood Risk
Pipe (24)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Manhole (22)	Manhole (21)	10.600	10.259	0.150	28.671	1.1	0.92	20.3	Surcharged
Pipe (25)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (19)	Manhole (18)	10.600	10.099	0.150	21.404	1.2	0.85	20.4	Surcharged

Project Wind: Phase 1 Enabling Works				Date: 16/04/2025											
				Designed by: BOW		Checked by: DD							Approved By: DD		
Report Details: Type: Connections Summary Storm Phase: Phase				Company Address:											


Pipe (26)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (6)	Manhole (5)	10.600	10.042	0.150	21.408	1.2	0.85	22.0	Surcharged
Pipe (27)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole (3)	Manhole (1)	10.600	10.011	0.150	22.855	1.4	0.9	24.7	Surcharged
Pipe (28)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Soakaway	Manhole (2)	10.600	10.000	0.250	30.746	1.6	0.18	35.7	Surcharged
Pipe (29)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaway (1)	Manhole (4)	10.600	10.047	0.250	21.656	1.7	0.13	31.5	Surcharged
Pipe (30)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaway (2)	Manhole (7)	10.600	10.105	0.250	21.665	1.7	0.13	31.6	Surcharged
Pipe (31)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaway (3)	Manhole (20)	10.600	10.214	0.250	21.661	1.6	0.19	38.9	Surcharged
Pipe (32)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaway (4)	Manhole (23)	10.600	10.289	0.250	21.660	1.5	0.19	35.8	Surcharged
Pipe (33)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Soakaway (5)	Manhole (26)	10.600	10.384	0.250	29.266	1.5	0.13	28.7	Surcharged
Pipe (34)	FSR: 10 years: +0 %: 60 mins: Winter	Pipe	Soakaway (11)	Manhole (28)	10.600	10.270	0.250	37.489	1.5	0.07	25.6	Surcharged
Pipe (44)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Soakaway (10)	Manhole (25)	10.600	10.344	0.250	28.835	1.6	0.1	33.0	Surcharged
Pipe (45)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Soakaway (9)	Manhole (22)	10.600	10.261	0.250	28.830	1.6	0.09	29.2	Surcharged
Pipe (46)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaway (8)	Manhole (19)	10.600	10.102	0.250	21.654	1.9	0.1	32.6	Surcharged
Pipe (47)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Soakaway (7)	Manhole (6)	10.600	10.046	0.250	21.659	1.8	0.11	31.2	Surcharged
Pipe (48)	FSR: 10 years: +0 %: 30 mins: Winter	Pipe	Soakaway (6)	Manhole (3)	10.600	10.000	0.250	30.746	1.6	0.17	35.7	Surcharged
Pipe (6)	FSR: 10 years: +0 %: 15 mins: Winter	Pipe	Manhole	Manhole (9)	10.030	8.490	0.375	340.192	2.1	1.6	236.4	Surcharged

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Connections Summary Storm Phase: Phase	Company Address:		




FSR: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow


Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
Pipe (9)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (9)	Manhole (10)	9.600	7.117	0.375	553.315	2.2	1.53	243.3	Surcharged
Pipe (10)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (10)	Manhole (11)	8.740	5.034	0.357	568.540	1.0	0.15	271.9	OK
Pipe (11)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (11)	Manhole (12)	8.280	4.969	0.371	614.543	1.1	0.17	316.0	OK
Pipe (12)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (12)	Manhole (13)	7.980	4.883	0.368	629.826	1.2	0.18	339.4	OK
Pipe (13)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Manhole (13)	Manhole (14)	7.890	4.796	0.371	858.155	1.2	0.18	335.7	OK
Pipe (14)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Manhole (14)	Manhole (15)	7.850	4.666	0.380	858.040	1.1	0.18	333.1	OK
Pipe (15)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Manhole (15)	Manhole (16)	7.115	4.565	0.397	857.845	1.1	0.18	337.0	OK
Pipe (16)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Manhole (16)	Manhole (17)	7.435	4.481	0.475	855.927	1.1	0.18	361.5	OK
Pipe (35)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (36)	Manhole (37)	9.000	7.834	0.150	7.613	1.0	1.28	15.9	Surcharged
Pipe (36)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (37)	Manhole (10)	9.000	7.532	0.150	15.183	2.1	0.68	31.9	OK
Pipe (37)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Manhole (38)	Manhole (39)	9.000	8.836	0.150	41.522	1.9	2.66	33.1	Flood Risk
Pipe (38)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (39)	Manhole (11)	9.000	8.040	0.150	45.627	2.8	1.03	49.3	Surcharged
Pipe (39)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (40)	Manhole (41)	9.000	7.825	0.150	7.614	1.0	1.25	15.6	Surcharged
Pipe (40)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (41)	Manhole (12)	9.000	7.529	0.150	15.144	1.8	0.65	31.5	OK

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025			
	Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Connections Summary Storm Phase: Phase	Company Address:			

Pipe (41)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Manhole (17)	Pond	6.245	4.404	0.503	1265.997	1.7	0.39	754.1	OK
Pipe (42)	FSR: 100 years: +0 %: 720 mins: Winter	Pipe	Pond	Pond Outfall	6.100	4.029	0.403	2249.715	0.5	0.05	33.2	OK
Pipe (43)	FSR: 100 years: +0 %: 720 mins: Winter	Pipe	Pond Outfall	Manhole (43)	6.100	4.026	0.250	2245.046	1.2	0.05	33.2	Surch arged
Pipe (66)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (20)	Manhole (37)	8.850	7.896	0.069	7.652	1.5	0.07	16.3	OK
Pipe (67)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (21)	Manhole (36)	8.850	7.900	0.138	7.608	1.0	0.09	18.9	OK
Pipe (68)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (22)	Manhole (39)	8.850	8.045	0.250	15.278	1.6	0.11	29.1	OK
Pipe (69)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (23)	Manhole (38)	8.850	8.898	0.250	30.497	1.3	0.15	31.5	Flood
Pipe (70)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (24)	Manhole (41)	8.850	7.898	0.068	7.628	1.5	0.08	16.3	OK
Pipe (71)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaw ay (25)	Manhole (40)	8.850	7.902	0.135	7.609	1.0	0.09	18.1	OK
Pipe (72)	FSR: 100 years: +0 %: 480 mins: Winter	Pipe	38	ExMH5	3.690	3.442	0.900	27426.35 5	1.7	0.14	1097. 5	Flood Risk
Pipe (73)	FSR: 100 years: +0 %: 480 mins: Winter	Pipe	ExMH5	ExMH4a	4.500	3.260	1.200	28142.93 4	1.0	0.29	1097. 5	Surch arged
Pipe (74)	FSR: 100 years: +0 %: 480 mins: Winter	Pipe	ExMH4a	ExMH4	4.500	3.231	1.200	28117.45 7	1.0	0.28	1097. 5	Surch arged
Pipe (75)	FSR: 100 years: +0 %: 480 mins: Winter	Pipe	ExMH4	ExMH	4.500	3.201	1.200	0.000	1.0	1.29	1097. 5	Surch arged
Pipe (76)	FSR: 100 years: +0 %: 480 mins: Winter	Pipe	ExMH	S	4.500	3.148	1.200	28024.81 3	1.0	0.49	1097. 5	Surch arged
Pipe (77)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (44)	S	4.000	3.535	0.300	46.250	1.5	0.37	102.7	Surch arged
Pipe (78)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Manhole (45)	ExMH5	4.000	3.145	0.525	308.629	1.3	0.65	281.7	Surch arged
Trapezoidal Channel	FSR: 100 years: +0 %: 240 mins: Winter	Trapezoidal Channel	Manhole (43)	38	4.000	3.396	0.986	661.420	0.1	0.01	81.9	OK

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Connections Summary Storm Phase: Phase		Company Address:			

Pipe (79)	FSR: 100 years: +0 %: 480 mins: Winter	Pipe	Cow Gut Diversio n	38	4.000	3.562	0.900	26287.42 2	3.0	0.19	1065. 1	OK
Pipe	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (27)	Manhole (24)	10.100	10.148	0.300	179.264	1.4	1.53	101.3	Flood
Pipe (1)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (24)	Manhole (21)	10.100	10.124	0.300	339.836	1.8	1.52	123.8	Flood
Pipe (2)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (21)	Manhole (18)	10.100	10.090	0.300	500.618	2.2	1.89	154.3	Flood Risk
Pipe (3)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (18)	Manhole (5)	10.100	9.889	0.375	661.514	1.6	1.16	173.1	Flood Risk
Pipe (4)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (5)	Manhole (1)	10.100	9.830	0.375	466.937	1.8	1.4	201.1	Flood Risk
Pipe (5)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (1)	Manhole	10.100	9.404	0.375	552.926	2.3	1.76	254.8	Surch arged
Pipe (7)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (26)	Manhole (27)	10.600	10.599	0.150	62.799	1.2	1.18	22.0	Flood Risk
Pipe (17)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (23)	Manhole (24)	10.600	10.596	0.150	61.673	1.2	1.06	21.2	Flood Risk
Pipe (18)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (20)	Manhole (21)	10.600	10.600	0.150	35.223	1.2	0.94	20.8	Flood
Pipe (19)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (7)	Manhole (18)	10.600	10.595	0.150	34.606	1.2	0.88	21.2	Flood Risk
Pipe (20)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (4)	Manhole (5)	10.600	10.594	0.150	34.612	1.2	0.85	22.1	Flood Risk
Pipe (21)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (2)	Manhole (1)	10.600	10.586	0.150	36.949	1.4	0.91	24.9	Flood Risk
Pipe (22)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (28)	Manhole (27)	10.600	10.599	0.150	62.812	1.2	1.18	22.0	Flood Risk
Pipe (23)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Manhole (25)	Manhole (24)	10.600	10.597	0.150	61.682	1.2	1.06	21.2	Flood Risk
Pipe (24)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (22)	Manhole (21)	10.600	10.600	0.150	34.939	1.2	0.95	21.1	Flood
Pipe (25)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (19)	Manhole (18)	10.600	10.596	0.150	34.598	1.2	0.89	21.5	Flood Risk

Project Wind: Phase 1 Enabling Works				Date: 16/04/2025											
				Designed by: BOW		Checked by: DD							Approved By: DD		
Report Details: Type: Connections Summary Storm Phase: Phase				Company Address:											


Pipe (26)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (6)	Manhole (5)	10.600	10.594	0.150	34.610	1.3	0.86	22.2	Flood Risk
Pipe (27)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole (3)	Manhole (1)	10.600	10.586	0.150	36.947	1.4	0.91	25.0	Flood Risk
Pipe (28)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway	Manhole (2)	10.600	10.596	0.250	37.207	1.8	0.25	50.1	Surcharged
Pipe (29)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (1)	Manhole (4)	10.600	10.604	0.250	34.879	1.8	0.21	51.8	Flood
Pipe (30)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (2)	Manhole (7)	10.600	10.622	0.250	34.891	1.8	0.16	39.0	Flood
Pipe (31)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Soakaway (3)	Manhole (20)	10.600	10.704	0.250	47.467	1.5	0.13	26.3	Flood
Pipe (32)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (4)	Manhole (23)	10.600	10.665	0.250	34.882	1.7	0.13	25.3	Flood
Pipe (33)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (5)	Manhole (26)	10.600	10.670	0.250	35.412	1.7	0.12	25.7	Flood
Pipe (34)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (11)	Manhole (28)	10.600	10.674	0.250	35.416	2.2	0.07	25.6	Flood
Pipe (44)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (10)	Manhole (25)	10.600	10.665	0.250	34.889	2.0	0.08	25.4	Flood
Pipe (45)	FSR: 100 years: +0 %: 60 mins: Winter	Pipe	Soakaway (9)	Manhole (22)	10.600	10.699	0.250	61.789	1.6	0.09	27.2	Flood
Pipe (46)	FSR: 100 years: +0 %: 30 mins: Winter	Pipe	Soakaway (8)	Manhole (19)	10.600	10.664	0.250	47.464	1.9	0.11	35.5	Flood
Pipe (47)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (7)	Manhole (6)	10.600	10.604	0.250	34.881	1.9	0.19	54.0	Flood
Pipe (48)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Soakaway (6)	Manhole (3)	10.600	10.596	0.250	37.207	1.8	0.25	50.8	Surcharged
Pipe (6)	FSR: 100 years: +0 %: 15 mins: Winter	Pipe	Manhole	Manhole (9)	10.030	8.806	0.375	551.660	2.2	1.66	245.7	Surcharged

Project Wind: Phase 1 Enabling Works	Date: 16/04/2025		
	Designed by: BOW	Checked by: DD	Approved By: DD
Report Details: Type: Connections Summary Storm Phase: Phase	Company Address:		




FSR: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Flow


Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
Pipe (9)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (9)	Manhole (10)	9.600	7.202	0.375	807.359	2.3	1.59	251.7	Surcharged
Pipe (10)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (10)	Manhole (11)	8.740	5.050	0.373	829.433	1.1	0.16	291.2	OK
Pipe (11)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (11)	Manhole (12)	8.280	4.986	0.390	896.008	1.1	0.18	338.0	OK
Pipe (12)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (12)	Manhole (13)	7.980	4.905	0.392	918.139	1.3	0.2	372.0	OK
Pipe (13)	FSR: 100 years: +45 %: 30 mins: Winter	Pipe	Manhole (13)	Manhole (14)	7.890	4.819	0.401	1242.287	1.2	0.19	367.0	OK
Pipe (14)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (14)	Manhole (15)	7.850	4.714	0.438	918.095	1.1	0.2	376.7	OK
Pipe (15)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (15)	Manhole (16)	7.115	4.642	0.476	916.910	1.1	0.21	393.7	OK
Pipe (16)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (16)	Manhole (17)	7.435	4.564	0.546	915.436	1.2	0.22	440.0	OK
Pipe (35)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (36)	Manhole (37)	9.000	7.967	0.150	11.050	1.1	1.54	19.2	Surcharged
Pipe (36)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (37)	Manhole (10)	9.000	7.554	0.150	22.034	2.4	0.9	42.0	OK
Pipe (37)	FSR: 100 years: +45 %: 60 mins: Winter	Pipe	Manhole (38)	Manhole (39)	9.000	8.838	0.150	78.343	1.9	2.75	34.2	Flood Risk
Pipe (38)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (39)	Manhole (11)	9.000	8.349	0.150	66.188	3.0	1.1	52.3	Surcharged
Pipe (39)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (40)	Manhole (41)	9.000	7.966	0.150	11.051	1.1	1.54	19.2	Surcharged
Pipe (40)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (41)	Manhole (12)	9.000	7.551	0.150	21.981	2.4	0.87	42.0	OK

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Connections Summary Storm Phase: Phase		Company Address:			

Pipe (41)	FSR: 100 years: +45 %: 30 mins: Winter	Pipe	Manhole (17)	Pond	6.245	4.503	0.591	1832.958	1.8	0.52	1013.5	OK
Pipe (42)	FSR: 100 years: +45 %: 960 mins: Winter	Pipe	Pond	Pond Outfall	6.100	4.159	0.525	3324.609	0.5	0.05	37.2	OK
Pipe (43)	FSR: 100 years: +45 %: 960 mins: Winter	Pipe	Pond Outfall	Manhole (43)	6.100	4.157	0.525	3319.215	1.3	0.06	37.3	Surcharged
Pipe (66)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaway (20)	Manhole (37)	8.850	7.908	0.086	11.092	1.6	0.1	23.7	OK
Pipe (67)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaway (21)	Manhole (36)	8.850	7.970	0.244	11.027	1.1	0.09	19.6	OK
Pipe (68)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaway (22)	Manhole (39)	8.850	8.363	0.250	22.141	1.6	0.18	45.2	Surcharged
Pipe (69)	FSR: 100 years: +45 %: 60 mins: Winter	Pipe	Soakaway (23)	Manhole (38)	8.850	9.093	0.250	78.322	1.1	0.16	33.2	Flood
Pipe (70)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaway (24)	Manhole (41)	8.850	7.910	0.085	11.055	1.6	0.11	23.6	OK
Pipe (71)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaway (25)	Manhole (40)	8.850	7.970	0.243	11.030	1.0	0.1	19.6	OK
Pipe (72)	FSR: 100 years: +45 %: 480 mins: Winter	Pipe	38	ExMH5	3.690	3.853	0.900	42116.879	2.6	0.22	1646.5	Flood
Pipe (73)	FSR: 100 years: +45 %: 480 mins: Winter	Pipe	ExMH5	ExMH4a	4.500	3.449	1.200	43188.559	1.5	0.44	1646.5	Surcharged
Pipe (74)	FSR: 100 years: +45 %: 480 mins: Winter	Pipe	ExMH4a	ExMH4	4.500	3.382	1.200	43163.082	1.5	0.43	1646.5	Surcharged
Pipe (75)	FSR: 100 years: +45 %: 480 mins: Winter	Pipe	ExMH4	ExMH	4.500	3.317	1.200	0.000	1.5	1.94	1646.5	Surcharged
Pipe (76)	FSR: 100 years: +45 %: 480 mins: Winter	Pipe	ExMH	S	4.500	3.199	1.200	43070.438	1.5	0.73	1646.5	Surcharged
Pipe (77)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (44)	S	4.000	3.976	0.300	67.797	2.1	0.53	148.5	Flood Risk
Pipe (78)	FSR: 100 years: +45 %: 30 mins: Winter	Pipe	Manhole (45)	ExMH5	4.000	3.452	0.525	455.342	1.9	0.97	415.6	Surcharged
Trapezoidal Channel	FSR: 100 years: +45 %: 60 mins: Winter	Trapezoidal Channel	Manhole (43)	38	4.000	3.395	0.985	779.980	0.0	0.02	99.3	OK

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025			
		Designed by: BOW	Checked by: DD	Approved By: DD	
Report Details: Type: Connections Summary Storm Phase: Phase		Company Address:			

Pipe (79)	FSR: 100 years: +45 %: 480 mins: Winter	Pipe	Cow Gut Diversion	38	4.000	4.130	0.900	40896.762	3.1	0.29	1645.8	Flood
Pipe	FSR: 100 years: +45 %: 120 mins: Winter	Pipe	Manhole (27)	Manhole (24)	10.100	10.188	0.300	328.238	1.7	1.76	116.8	Flood
Pipe (1)	FSR: 100 years: +45 %: 120 mins: Winter	Pipe	Manhole (24)	Manhole (21)	10.100	10.159	0.300	620.833	2.0	1.74	141.9	Flood
Pipe (2)	FSR: 100 years: +45 %: 120 mins: Winter	Pipe	Manhole (21)	Manhole (18)	10.100	10.104	0.300	915.470	2.3	2	162.9	Flood
Pipe (3)	FSR: 100 years: +45 %: 120 mins: Winter	Pipe	Manhole (18)	Manhole (5)	10.100	9.932	0.375	1210.207	1.6	1.21	180.3	Flood Risk
Pipe (4)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (5)	Manhole (1)	10.100	10.011	0.375	682.186	1.9	1.46	209.7	Flood Risk
Pipe (5)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (1)	Manhole	10.100	9.624	0.375	806.960	2.4	1.81	262.5	Surcharged
Pipe (7)	FSR: 100 years: +45 %: 180 mins: Winter	Pipe	Manhole (26)	Manhole (27)	10.600	10.597	0.150	130.265	1.3	1.25	23.3	Flood Risk
Pipe (17)	FSR: 100 years: +45 %: 30 mins: Winter	Pipe	Manhole (23)	Manhole (24)	10.600	10.600	0.150	71.456	1.2	1.08	21.7	Flood
Pipe (18)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (20)	Manhole (21)	10.600	10.600	0.150	51.198	1.1	0.89	19.7	Flood
Pipe (19)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (7)	Manhole (18)	10.600	10.600	0.150	50.547	1.3	0.93	22.4	Flood
Pipe (20)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (4)	Manhole (5)	10.600	10.600	0.150	50.376	1.3	0.91	23.4	Flood
Pipe (21)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (2)	Manhole (1)	10.600	10.599	0.150	53.674	1.5	0.95	26.0	Flood Risk
Pipe (22)	FSR: 100 years: +45 %: 60 mins: Winter	Pipe	Manhole (28)	Manhole (27)	10.600	10.600	0.150	96.464	1.3	1.27	23.7	Flood
Pipe (23)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (25)	Manhole (24)	10.600	10.600	0.150	52.979	1.2	1.07	21.5	Flood
Pipe (24)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (22)	Manhole (21)	10.600	10.600	0.150	51.338	1.1	0.89	19.8	Flood
Pipe (25)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (19)	Manhole (18)	10.600	10.597	0.150	50.336	1.3	0.94	22.6	Flood Risk

Project Wind: Phase 1 Enabling Works		Date: 16/04/2025					
		Designed by: BOW	Checked by: DD	Approved By: DD			
Report Details: Type: Connections Summary Storm Phase: Phase		Company Address:					

Pipe (26)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (6)	Manhole (5)	10.600	10.600	0.150	50.554	1.3	0.91	23.5	Flood
Pipe (27)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole (3)	Manhole (1)	10.600	10.599	0.150	53.673	1.5	0.95	26.0	Flood Risk
Pipe (28)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay	Manhole (2)	10.600	10.800	0.250	53.928	1.8	0.2	40.7	Flood
Pipe (29)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (1)	Manhole (4)	10.600	10.799	0.250	50.549	1.9	0.16	39.4	Flood
Pipe (30)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (2)	Manhole (7)	10.600	10.822	0.250	50.568	1.9	0.22	51.4	Flood
Pipe (31)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (3)	Manhole (20)	10.600	10.849	0.250	50.564	1.8	0.13	26.9	Flood
Pipe (32)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (4)	Manhole (23)	10.600	10.857	0.250	50.560	1.7	0.13	24.4	Flood
Pipe (33)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (5)	Manhole (26)	10.600	10.869	0.250	51.314	1.8	0.11	24.9	Flood
Pipe (34)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (11)	Manhole (28)	10.600	10.872	0.250	51.328	2.3	0.07	24.9	Flood
Pipe (44)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (10)	Manhole (25)	10.600	10.858	0.250	50.556	2.2	0.08	24.6	Flood
Pipe (45)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (9)	Manhole (22)	10.600	10.850	0.250	50.570	2.2	0.08	24.6	Flood
Pipe (46)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (8)	Manhole (19)	10.600	10.818	0.250	50.560	2.2	0.16	55.3	Flood
Pipe (47)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (7)	Manhole (6)	10.600	10.801	0.250	50.553	2.1	0.14	40.6	Flood
Pipe (48)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Soakaw ay (6)	Manhole (3)	10.600	10.800	0.250	53.926	1.8	0.2	41.0	Flood
Pipe (6)	FSR: 100 years: +45 %: 15 mins: Winter	Pipe	Manhole	Manhole (9)	10.030	8.994	0.375	805.759	2.3	1.71	253.8	Surch arged

Cundall Johnston & Partners LLP

One Carter Lane London EC4V 5ER
Tel: +44 (0)20 7438 1600

Asia Australia Europe MENA UK and Ireland
www.cundall.com

