

A large teal graphic element on the left side of the page, consisting of a triangle pointing upwards at the top, a vertical rectangle below it, and a diagonal line connecting the top-left corner of the rectangle to the top-right corner of the triangle above it.

Fullerton Sludge Treatment Centre Accident Management Plan

February 2024

This page left intentionally blank for pagination.

Mott MacDonald
4th Floor
Mountbatten House
Grosvenor Square
Southampton SO15 2JU
United Kingdom

T +44 (0)23 8062 8800
mottmac.com

Fullerton Sludge Treatment Centre Accident Management Plan

February 2024

Issue and Revision Record

Revision	Date	Originator	Checker	Approver	Description
P01	February 2024	Amelia Luk	David Dray	Anita Manns	Draft (February 2024 Resubmission)
P02	February 2024	Amelia Luk	David Dray	Anita Manns	For EA Submission

Document reference: 790101_MSD_AMP_FUL_February 2024

Information class: Standard

This document is issued for the party which commissioned it and for specific purposes connected with the above-captioned project only. It should not be relied upon by any other party or used for any other purpose.

We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.

This document contains confidential information and proprietary intellectual property. It should not be shown to other parties without consent from us and from the party which commissioned it.

Contents

1	Introduction	1
1.1	Scope	1
1.2	Roles and Responsibility	2
1.3	Roles and Responsibility	2
2	Site information	4
2.1	Site location	4
2.2	Summary of Site and sensitive receptors	4
3	Accident Management Techniques	5
3.1	Loss of Containment	8
3.1.1	Gas Escape	8
3.1.2	Liquid Escape	9
3.1.3	Material Storage	9
3.1.4	Odour	10
3.1.5	Vandalism and unauthorised access	10
3.1.6	Physical Protection Measures	11
3.1.7	Overfilling of tanks	11
3.1.8	Fire	12
3.1.9	Arson risks	12
3.1.10	Contingency for Sludge Treatment Issues	12
4	Risk Assessment Methodology	14
5	Reporting and Recording	37
5.1	Reporting	37
5.2	Recording	37
5.3	Post-incident Review	38
5.4	Competence and Training	38
6	Emergency Response Procedures (ERP)	40
6.1	Fire	40
6.2	Explosion	40
6.3	Pollution	41
6.4	Flooding	41
6.5	Road traffic accident impact or collision	41
6.6	Collapse of a structure or building	41
6.7	Spill transferring wastes	42
6.8	Chemical spillage/leak onsite	42

6.9	Sludge spillage on site	42
6.10	Diesel spillage/leak on site	43
6.11	Overfilling vessels	44
6.12	Plant and equipment failures	44
6.13	Containment failure	44
6.14	Failure to contain firewater	45
6.15	Incorrect connection leading to releases to drains and other systems	45
6.16	Incompatible substances coming into contact	45
6.17	Emission of effluent or Biogas before composition checked	45
6.18	Theft & Vandalism	46

A. Grab Pack 47

Tables

Table 1.1: Key contacts and communication in the case of an emergency	2
Table 3.1: Supporting Emergency Procedures – IMP	5
Table 3.2: Raw Material and Process Chemical Storage	11
Table 3.3: Mitigation measures with sludge treatment incidents	13
Table 4.1: Severity Index	14
Table 4.2: Probability Index	14
Table 4.3: Magnitude of risk	14
Table 4.4: Accident risk assessment table	15

1 Introduction

This Accident Management Plan (AMP) describes the requirements, procedures and actions to be taken in the event of an environmental accident or incident at Fullerton Sludge Treatment Centre (STC), also referred to as the “Site”. This plan will support the Fullerton STC Environmental Management System.

1.1 Scope

Environmental accidents and incidents shall cover emissions to air, land or water that can cause harm to the environment.

This plan is written in accordance with the IED Environmental Permit application requirements for Fullerton; BAT, specifically BAT1; and associated written management systems and procedures. Southern Water is required to review this plan annually, unless there are incidents, operational or managerial changes at the Site, which would require an earlier review.

The Site is manned during opening hours (7am – 5pm on weekdays, 7am – 1pm on Saturdays and 7am – 11am on Sundays), and staff are on call from Millbrook and Slowhill.

The Site also operates under an Incident Management Plan (IMP), to be read in conjunction with this Accident Management Plan, which is incorporated into Southern Water’s Environmental Management System to prevent and manage environmental related accidents. The IMP includes an inventory of substances stored at the Site, details on storage facilities, inventory of pollution prevention equipment (spill kits and fire extinguishers), inventory of waste and storage capacities, contact details of internal contacts (Site manager, Environmental Governance Manager and key HSE staff), national and regional (where appropriate) contact details of emergency services and environmental regulators. The IMP is distributed to key staff, to supervise the implementation of the Plan, and shared with external contacts (emergency services and the Environment Agency). The IMP is accompanied by a Site Plan that identifies the locations of designated storage areas (and their maximum storage capacity), location of spill kits and fire extinguisher and storage locations and hazards posed by chemical substances.

The IMP references procedures to comply with environmental legislation and protect the environment and human health in regard to potential accidents:

- Spill prevention and management, and operation of safety valves
- Procedures for recovering spilled product
- Procedures for the prevention of overflowing vessels, and the management of plant and equipment failures
- Fire prevention and responses to fires, including fire water containment procedures
- Security measures to prevent unauthorised access, arson and vandalism
- Competence, training and awareness requirements
- Monitoring and measurement requirements
- Record keeping procedures for the recording of incidents, accidents and near misses
- Emergency procedures to notify relevant authorities, emergency services and neighbours

There are several different document types referenced in the IMP. These have been listed below:

- EMS – Environmental Management System
- FEC – Field Event Co-ordinator's Manual

- IMP – Incident Management Plan
- BCP – Business Continuity Plan
- CCM – Control Centre Manual
- SIB – Safety Instruction Book
- CAT – Catastrophe Plans

Southern Water is committed to continual environmental improvements, including minimising the risk of accidents both on the Site and its operations and in the wider environmental setting. This commitment is delivered through efficient control of processes, capital investments, and environmental training.

1.2 Roles and Responsibility

The Site Manager has overall responsibility for reviewing the processes on the Site to minimise the risk of accidents and reduce the impact of any accidents should they occur. This document is reviewed annually, but the review process is ongoing as part of the regular performance monitoring for the Site.

1.3 Roles and Responsibility

The Site Manager has overall responsibility for reviewing the processes on the Site to minimise the risk of accidents and reduce the impact of any accidents should they occur. This document is reviewed annually, but the review process is ongoing as part of the regular performance monitoring for the Site. In the case of an emergency, key contacts and communication details are listed in Table 1.1.

Table 1.1: Key contacts and communication in the case of an emergency

Contact	Office Hours	Out of Hours
Southern Water	Duty Manager, Control Centre 01903 272095	Duty Manager, Control Centre 01903 272095
Environment Agency	0800 807060 (Emergency Hotline) 0370 8506506 (Routine enquiries)	0800 807060 (Emergency Hotline) 0370 8506506 (Routine enquiries)
Emergency Services	999	999
Local Police	999	999
Local Hospital	Royal Hampshire County Hospital. Romsey Road Winchester S022 5DG	999
EA Incident Hotline	0800 80 70 60	0800 80 70 60
EA Local Contact	0800 80 70 60	0800 80 70 60
Local Authority Emergency Planning Department	Emergency Planning department Hants county council 01962 846 846	
Borough Council	Test Valley Borough Council 01264 368000(24 hr)	01264 368000(24 hr)
Water Company	Duty Manager, Control Centre 01903 272095	Duty Manager, Control Centre 01903 272095
Gas Company	0800 111 999	0800 111 999
Electricity Company	UK Power Networks 08433 102243	UK Power Networks 08433 102243
Framework Waste Contractor	MTS	MTS

Contact	Office Hours	Out of Hours
	01634 250326	01634 250326
Specialist Spill Clean Up Contractor	MTS 01634 250326 Cappagh Browne 0330 3031279	MTS 01634 250326 Cappagh Browne 0330 3031279

2 Site information

2.1 Site location

Fullerton Wastewater Works (WTW) and Sludge Treatment Centre (STC) is located 500m southeast of the village of Goodworth Clatford, approximately 4km south of the town of Andover, Hampshire. The WTW was built in 1969 and the STC was built in 1995. The Fullerton catchment serves the town of Andover and surrounding villages over a large area, with a combined population of approximately 66,137.

Site address: Romsey Road, Andover, Hampshire, SP11 7HR.

National grid reference: SU 36857 41560.

2.2 Summary of Site and sensitive receptors

The Site is situated 500m to the southeast of the village of Goodworth Clatford, approximately 4km south of the town of Andover, Hampshire. The Site is bordered by agricultural and rural land use to the east, south and west. To the north of the Site is the Fullerton Solar Energy Farm.

There are a number of sensitive receptors within 500m of the potential emission sources at Fullerton WTW and STC. As demonstrated in Figure 2 the receptor closest to potential emission sources at Fullerton STC is a cluster of residential properties, located approximately 15m east of the Site.

3 Accident Management Techniques

The IED Regulations require the identification of potential accidents associated with the operation of an Installation and implementation of measures to avoid or minimise the effects of an accident, should they occur. This section sets out the measures to be adopted at the Installation to minimise potential risks to the environment. See Section 6 for Emergency Response Procedures.

The Site has an IMP designed to give first response instruction and procedures to control any Incidents/Emergencies at the Site.

Table 3.1 below provides a list, along with a brief description of each, of the procedures which form part of the IMP.

Table 3.1: Supporting Emergency Procedures – IMP

Procedure Reference	Brief Summary
EMS 234 Chemical and Oil Storage	Specifies the standard for storage of chemicals and oils. Outlines the amounts of substances that can be stored on site without consent from the Local Authority, and details how these substances should be safely stored. Also includes Information on the auditing, training requirements and any associated documents.
EMS 260 Pollution Prevention (standard)	Specifies the standard for managing and reducing the risk of land contamination. Outlines the tasks a manager should complete i.e., ensuring spill kits are available, and who to contact in the event of an incident. The document also lists the measures that Southern Water should take to prevent pollution incidents. Also includes Information on the auditing, training requirements and any associated documents.
EMS 265 Discharges (Standard)	Sets the minimum standard of operation in managing effluent and potable water process discharges. Details definitions which relate to the procedure and outlines the standard. Also includes Information on the auditing, training requirements and any associated documents.
EMS 360 Pollution Prevention Procedure	Outlines the responsibilities of staff in relation to the procedure. The Procedure includes details on items such as site drainage, working on or near watercourses and excavations. As well as addressing different spill types; chemical, oil and sludge/sewage. Information on the auditing, training requirements, reporting forms and any associated documents.
EMS 361 Chemical Risk Assessment (Procedure)	Defines the procedure for assessing the environmental risk from bulk chemicals. Outlines the procedure for undertaking a risk assessment, and where required which EMS procedures need to be followed. Also addresses risk mitigation and employee awareness as well as the auditing, training requirements, reporting forms and any associated documents.
EMS 362 Environmental Fire Risk Assessment Procedure	Specifies the procedure for minimising the environmental consequence of a fire. Outlines the responsibilities of staff in relation to the procedure and provides a procedure for an Environmental Fire Risk Assessment. Information on the auditing, training requirements, reporting forms and any associated documents
EMS 363 Procedure for Managing oil spills on sites	Outlines the responsibilities of staff in relation to the procedure. The procedure details how to determine the severity of the spill for different scenarios; land, inland waters and coastal waters/beaches, and how to prevent, control and remediate the environmental damage caused by spillages from the site. Information on the auditing, training requirements, reporting forms and any associated documents.
EMS 364 Lime Spill Management Procedure	Outlines the procedure for managing lime chemical spills at STCs. Defines the responsibilities of staff, and the procedure for managing the spill including the spill assessment and notification and escalation. Information on the auditing, training requirements, reporting forms and any associated documents.

Procedure Reference	Brief Summary
EMS 365 Discharges Procedure	Defines the procedure that must be adopted when managing intermittent discharges. Outlines the responsibilities of staff in relation to the procedure and outlines the procedure where an emergency discharge is foreseeable for both emergency and stormwater and potable water. Information on the auditing, training requirements, reporting forms and any associated documents.
EMS 381 Operational Waste Procedures	Specifies the procedure for managing wastes. The procedure addresses the definitions of different waste types and outlines a general procedure for managing waste. Identifies where further procedures should also be followed for specific waste types e.g., asbestos, WEEE and waste oils. Information on the auditing, training requirements, reporting forms and any associated documents.
EMS 382 Hazardous Waste Procedures	Specifies the procedure for moving hazardous waste between different sites. The procedure addresses identifying hazardous waste, storage of hazardous waste, consignment notes and record keeping. Information on the auditing, training requirements, reporting forms and any associated documents.
EMS 461 Chemical Risk Assessment (Form)	A template for a chemical risk assessment including the following: <ul style="list-style-type: none"> ● Site details ● Chemical details ● Chemical classification ● Risk activity ● Risks for health, fire/DSEAR¹ and environment ● Handling, usage and storage requirements ● Management of spills ● Disposal And the safety data sheet.
EMS 480 Waste Descriptions	Provides written descriptions of different waste types covering the following: <ul style="list-style-type: none"> ● Process giving rise to the waste ● Waste characteristics ● Handling advice ● Containment ● Disposal ● Name of waste ● Waste classification ● Producer and registered office details ● EWC ● Controlled Waste Regulations 2012 description ● Waste type ● Form ● Temperature ● SIC code <p>Information on the auditing, training requirements, reporting forms and any associated documents.</p>
FEC 307 Reporting of Unauthorised Access, Including Loss, Theft and Vandalism	Outlines the responsibilities of staff in relations to the reporting these incidents, and the procedure to be followed. Also includes Information on the auditing, training requirements and any associated documents.
FEC 320 Process Related Incidents	Specifies the procedures to follow in responding to process-related pollution incidents. Responsibilities of staff are outlined in the procedure, as well as contacting the FEC, FEC actions and reporting procedures. Information on the auditing, training requirements, reporting forms and any associated documents

¹ Dangerous Substances and Explosive Atmosphere Regulations

Procedure Reference	Brief Summary
FEC 322 – Spillage Procedure	<p>Outlines the responsibilities of staff in relation to the procedure. The procedure outlines the process for handling spillages on site including:</p> <ul style="list-style-type: none"> • Spillage assessment • Notifications and escalation • Containment • Awareness and training <p>Information on the auditing, training requirements, reporting forms and any associated documents.</p>
IMPO_101 – Overview of the Incident Management Plan	This document sets out the overall structure of the Incident Management Plans and provides a short overview of each of the main plans
IMP 217 and IMP 218 Team Roles – Objectives and Responsibilities	Sets out the Objectives and Responsibilities for roles within the Incident Management Team and provides guidance for the ELT Representative. IMP 217 identifies when Southern Water should contact the Environment Agency, and IMP 218 identifies the process for contacting other authorities.
BCP 415 Guidance on Reporting Potential Media Interest	Sets out the types of incidents to be reported back by Field Operations Staff & Contract staff working on behalf of Southern Water that will potentially attract media interest, including contact numbers.
CCM 302 Procedure Following the Receipt of a Fire Alarm	Provides a consistent regional approach to dealing with any formal notification of a fire alarm within the Company. Outlines the responsibilities of staff, the procedure for when a fire alarm notification is received, inspections/audits, training and any associated documents.
SIB 603 Risk Assessment and Safety Instructions for Fire Awareness	<p>Covers the following:</p> <ul style="list-style-type: none"> • Training needs of staff and fire wardens • What Managers must provide (i.e. fire safety meetings, plans) • Inspections • Safety instructions for occupied sites, unoccupied sites, and company vehicles • Firefighting procedure • Records to be completed
CAT 303 Actions Following Severe Weather or Flood Warnings	<p>Outlines the plan of actions that should be undertaken following severe weather or flood warnings and the responsibilities of the staff under these circumstances. The procedure details checklists for the following scenarios:</p> <ul style="list-style-type: none"> • impending severe weather, • flood watch, • flood warning, • severe flood warning, and • an all clear checklist. <p>Also includes Information on the auditing, training requirements and any associated documents.</p>
Environmental Emergencies Poster (EMS)	A poster which should be displayed on all sites. The poster lists the type of emergency (fires, spills etc) and both the action which should be undertaken the contact phone number which should be called. The poster also highlights a list of things which should be checked prior to work starting such as the H&S notice boards, environmental notice boards and continuity plans.
Pollution 30 Minute Plan	Outlines a five-step plan for responding to a pollution incident in 30 minutes and outlines what should be done at each of the five stages.
Site Chemical Risk Register	Southern Water electronic database containing an inventory of hazardous substances used and stored by Southern Water and those relevant to individual sites, helping Southern Water to control substance use and comply with the COSHH regulations
Alternative Response Coordinators Booklet	These documents provide flowcharts and a step-by-step guide for completing the Alternative Response tasks. Section 5: Resilience Guidance identifies criteria on when to contact local authorities and other first responders

A site-specific Fire Prevention Plan is available for Fullerton to reduce the risk of fire and explosion. Please see the site-specific Fire Prevention Plan for full details of corrective measures.

3.1 Loss of Containment

3.1.1 Gas Escape

Loss of containment of gaseous materials at the Site could result in the escape of biogas or other gases to the atmosphere around the site. In order to minimise the potential for accidental releases of gas from the Installation the following measures have been adopted:

- The gas holders are double-membrane inflatable bag type holders, constructed of a Type IV fabric², which is resistant to UV and microbial degradation. The stored gas is contained within the inner membrane. The exterior dimension of the gasholder remains constant
- All pipework at the Site used for the transfer of gaseous products has been manufactured to the appropriate British Standard using appropriate grade materials and all pipe joints and seals are also designed to meet the required British Standard
- Regular monitoring of storage vessels, pipework and gas levels is undertaken to minimise release of fugitive emissions
- Storage vessels and pipework are subject to regular inspection, by the site operators to ensure the structural integrity of the system remains uncompromised
- All staff with responsibility for the handling or transfer of gaseous materials receive training for their role
- All staff on site will receive training in site emergency procedures and the actions to take in the event of discovering a gas leak as part of their mandatory site induction training
- The gas system has safety pressure release valves, which are designed to prevent over-pressurisation of the system. Gas emissions from this point are monitored on telemetry with immediate call-out of staff to remedy
- A waste gas burner is incorporated to deal with excess biogas and is the first point of relief for excess gas or pressure as an emergency measure

The Site is designed to meet the Dangerous Substances and Explosive Atmosphere Regulations (DSEAR). Consideration of the requirements of DSEAR is included in the Designers Risk Assessment including information on the operation and maintenance of the Installation to ensure DSEAR requirements are met.

An IMP is in place for the Fullerton site. The IMP includes actions to be followed in the event of a loss of containment of gaseous materials at the Installation.

Preventative measures incorporated into normal operations include a DSEAR operational risk assessment that will be periodically reviewed and updated against the latest DSEAR regulations and guidance to ensure best practice is adopted.

A Leak Detection and Repair (LDAR) plan is in place at the Fullerton STC.

² Type IV fabric is a biogas storage system that is constructed using a polyester fabric that has a PVC coating on both sides which makes it resistant to corrosive gas and heat.

3.1.2 Liquid Escape

Failure of the liquid containment systems at the STC could potentially lead to oil bearing fluids, reagents and process effluents discharging to surface waters and ground waters in proximity to the Installation. Potential risks associated with this have been reduced through the implementation of the following measures:

- The storage vessels for all boiler feed water treatment chemicals and fuel storage liquid materials located within the installation are double-skinned or banded to 110% capacity and have been manufactured to the required British Standard using appropriate grade materials
- Where applicable, on-site storage tanks are banded to 110% of their storage capacity in line with environmental good practice and bands are regularly inspected for liquid content and emptied, if required
- Regular monitoring of storage vessels, pipework and fluid levels is undertaken to ensure no fugitive emissions are being released
- Storage vessels, bands and pipework are subject to regular inspection by the Site Manager or the nominated deputy to ensure the structural integrity of the system remains uncompromised
- All pipework at the site used for the transfer of liquids has been manufactured to the appropriate British Standard using appropriate grade materials and all pipe joints and seals are also designed to meet the required British Standard
- Spill kits comprising suitable materials for the containment of liquid spills have been placed throughout the site for the use of all staff
- Site surfaces surrounding liquid storage areas and transfer pipes are constructed of impermeable material and run off is diverted to appropriate drainage structures to prevent escape of fluids to surface waters or ground waters
- All staff with responsibility for the handling or transfer of liquid materials receive appropriate training for their role
- All staff on site must receive training in site emergency procedures and the actions to take in the event of discovering a liquid spillage and the use of spill containment measures as part of their mandatory site induction training

3.1.3 Material Storage

All chemical tanks and stores must be clearly labelled and marked with appropriate warning signs and all delivery points must be kept locked except when in the presence of an Operations team member.

The levels of raw materials are checked and recorded.

During deliveries of material to site, special care is taken to ensure that all storage tank levels and contents are checked in order to prevent the accidental overfilling of tanks or the inadvertent mixing of substances. Specific measures are in place for the discharging of sludge from delivery tankers to reduce the risk of overfilling of the tank and spillages during discharge.

The following are requirements for deliveries on site:

- Each direct delivery must be checked for the correct quality and strength and to ensure that no damage etc. has occurred in transit
- Supplier's Advice Notes must be checked, to ensure that the goods match the documentation, and then signed
- Retain copies of Supplier's Advice Notes
- All chemical deliveries must be supervised by nominated personnel as detailed on the current list

- Chemical deliveries must be recorded and must include a declaration that they conform to the required standard, either on the delivery note, or as a separate certificate of conformance
- Appropriate training is provided to personnel involved in receipt and handling of deliveries and specific procedures for the filling of tanks have been developed within the management systems

3.1.4 Odour

Biogas is a naturally odorous material; however, the high alkaline conditions present within the STC digesters, scrub most of the hydrogen sulphide (H₂S) (an odorous constituent) from the biogas, resulting in relatively low concentrations. In addition, there will be no other odour emissions at the site from normal operations at the Installation.

Sewage, sewage sludges and returned liquors can all contribute to odour on a STC. A number of odour release points/areas have been identified in Fullerton STC, and a combination of good baseline site management and odour control measures have been implemented to manage these sources. Three odour control units are installed on the Site.

Regular inspection of site storage facilities and pipework will be undertaken to ensure that the structural integrity of the system remains intact in line with the Fullerton STC LDAR plan and Odour Management Plan (OMP). Regular site inspections and sniff checks are undertaken by the site team to ensure that no significant fugitive emissions of odour likely to cause pollution of the environment, adversely impact human health or significantly reduce the amenity of the local area are present. In the event of an accidental emission of odorous material from site storage facilities or pipework, the source of the emission will be isolated, investigated and, if required, operation suspended until the source of the emission has been sealed.

3.1.5 Vandalism and unauthorised access

Vandalism and unauthorised access to plant infrastructure and work areas has the potential to result in:

- Damage to plant infrastructure and equipment
- Increased risk of injury to personnel
- Uncontrolled release of fugitive emissions of gaseous, liquid or solid materials to the environment

Operations and Maintenance (O&M) activities at the STC occur on a continuous basis and high levels of site security are maintained to prevent unauthorised access to plant infrastructure and work areas in accordance with Field Event Coordinator's Manual (FEC) in relation to Reporting of Unauthorised Access, Including Loss, Theft and Vandalism (FEC 307). In light of this the potential for vandalism is considered to be effectively minimised.

The following measures have also been adopted as security measures:

- For visitors and unauthorised personnel, an intercom system at the Site entrance is used before entry is allowed
- On arrival at site, visitors must sign the visitor's book and also announce their arrival to staff in the control room
- The Site is manned during opening hours (7am – 5pm on weekdays, 7am – 1pm on Saturdays and 7am – 11am on Sundays), and staff are on call from Millbrook and Slowhill
- CCTV cameras are positioned in the cess plant around the Site
- Access to Site and waste is restricted by three quarters 10ft chain link fencing with barbed wire and one quarter 3 wired barked wire fencing with trees.

- Regular inspections of the boundary fencing and buildings are undertaken to ensure that these have not been compromised and continue to prevent easy access to the Site
- Out-of-hour intruder alarms are set for buildings
- CCTV cameras onsite as a deterrent to any unauthorised visitors

3.1.6 Physical Protection Measures

The Site has been designed to include protection of structures to minimise accident / incident issues. Potential risks associated with this have been reduced through the implementation of the following physical protection measures:

- All pipework at the site used for the transfer of gaseous products has been manufactured to the required British Standards using appropriate grade materials and all pipe joints and seals are also designed to meet the required British Standard
- Storage vessels and pipework are subject to regular inspection, by the site team to ensure the structural integrity of the system remains uncompromised.

3.1.7 Overfilling of tanks

Details of the raw materials and process chemicals held on site and their storage arrangements are provided in Table 3.2 below. During deliveries of material to site special care is taken to ensure that all storage tank levels and contents are checked in order to prevent the accidental overfilling of tanks or the inadvertent mixing of substances. Appropriate training is provided to personnel involved in receipt and handling of deliveries and specific procedures for the filling of tanks will be developed within the quality and environmental management system (QEMS) for the Site.

The volume of material in the receiving tanks will be measured and recorded manually prior to filling.

In the event of a spillage of polluting substances, absorbent material will be used to clear the spillage. The used materials will be removed and stored in suitable containers prior to authorised disposal. The Installation will incorporate impermeable paving with self-contained drainage.

Table 3.2: Raw Material and Process Chemical Storage

Raw Material / Process Chemical	Maximum storage amount (tonnes or m ³)	Storage
Biogas	<3,000 m ³ max	Gas bag Digesters Pipelines
Diesel Oil	25m ³	Tank
Sludge	2,000m ³	Tank
Sludge Cake	<6,000m ³	Bays
Polymer	1 x 1m ³ /750kg bags	Bags
Polymer	10 x 1m ³ /750kg bags	Bags
Polymer	12m ³	Storage tank.
Lime (Dust).	Variable this is an unusual activity	In bags
Gas Cylinders	Welding / burning Equip.	Gas Bottles stored in a locked building overnight.
Ferric Sulphate	35,000 ltrs	Storage tank
Aerosol Leaks of Biogas	Not known as would be formed by leaks	Gas bag Digesters Pipelines

Raw Material / Process Chemical	Maximum storage amount (tonnes or m ³)	Storage
		Flare Stack CHP Engine
JCB Loader / MTS Tankers & Chemical Delivery tankers.	25m ³	Vehicle stored outside control room overnight.
Antifoam	1m ³	Intermediate Bulk Container (IBC)
Polymer	12m ³ as liquid in storage tank	Storage tank.
Sludge	<3,000m ³	Tanks
Sludge	90m ³	Tank

3.1.8 Fire

Operational activities at the STC are such that the potential for fire and explosion exists. However, the local Fire Service has not carried out any risk assessment investigations on site. Potential hazards arising from fire and explosion at the Site include:

- Uncontrolled release of pollutants from equipment, plant and infrastructure
- Uncontrolled release of pollutants from material stores
- Loss of containment of contaminated firewater

Fire detectors and fire alarms are fitted in all buildings. Fire extinguishers are located at strategic points throughout the STC. All fire extinguishers are clearly marked and tested to confirm their functionality. All personnel will be made aware of their location and trained in their use for escape purposes only, in order to minimise the risk to life posed by fire and explosion.

However, the emergency policy is to evacuate the building in the event of a fire. Staff are informed during induction of the emergency procedures at the Site to be followed in the event of fire incidents at the Site.

To reduce the risk of fires from the Anaerobic Digestion process, it is managed by controlling KPI's on process control on a SCADA control system, DSEAR risk assessments are in place, with 12 monthly service agreements in place around the Biogas system. Six monthly inspections on the Boilers and CHP systems are also conducted.

Controls to reduce the risk of fires are good signage and EX zoned areas with fencing and locked gate policy around DSEAR areas. Lightning protection is also in place on Biogas storage bags. Operational and maintenance staff have received training in both Biogas awareness and DSEAR.

The Digestion process risks are managed by DSEAR risk assessments, Zonal areas & Biogas training for site operators and Maintenance staff along with Gas safe contractors carrying out programmed maintenance activities.

3.1.9 Arson risks

With flammable or combustible materials there is always a risk of arson on a site. This risk is controlled by secure perimeter fencing and an electric gate at the main entrance of the Fullerton site, plus adherence to a locked gate policy

3.1.10 Contingency for Sludge Treatment Issues

In the case of incidents with sludge treatment, the mitigation measures related to sludge treatment processes are listed in Table 3.3. A full list of mitigation measures covering different processes of the entire site can refer to the operational continuity plan of Fullerton.

Table 3.3: Mitigation measures with sludge treatment incidents

Incident	Mitigation measures
Strain presses (and screened sludge holding tanks)	<ul style="list-style-type: none"> • D/S units; can be bypassed in an emergency through grit and screening plant to ensure sludge does not back up through site. Pumping station from strain presses feeding thickened sludge storage tank (TSST) can be left failed overnight. Check Mono-muncher operation (D/S 1.6 kW 4A) if high rag pass forward, and primary desludge not running on if feed-well high as can overtop and spill onto biofilters. External Vaughn mixers on tank 10 kW 25A.
Drum thickeners (and thickened sludge storage tank)	<ul style="list-style-type: none"> • If feed sludge particularly watery, check humus desludge valves are not stuck/excessively cracked open as top water well weirs into sludge well. Drum thickeners can be bypassed in an emergency but recommended action is to leave failed overnight if cannot be restarted. 100-150 m³/d throughput; polymer (Superfloc C-496) dosing circa 0.1 l/s. Drum feed pumps VSD 3.2 kW 8A. Polymer flocculation tank mixer and dosing pumps circa 2 – 5A (kW rating unknown). External Vaughn chopper pump (10 kW 25A) must run permanently. Thickened sludge liquor pumps D/S 1.6 kW 4A.
Digesters (and digester storage tank)	<ul style="list-style-type: none"> • If digester found foaming turn feed pumps and mixers off; dose anti-foam. Sludge throughput automated through STC stream; if control failed would require manual intervention to keep digesters fed. 'Secondary' digester is storage tank for centrifuge feed. D/S digester feed pumps 1.6 kW 4A (critical asset). Digester No.s 1 and 2 mixers (external pumps) VSD 12.4 kW 31A. Digester No.3 4 kW 10A Vaughn HF4P65, 225 m³/h flow rate. Heat exchanger D/S pumps 2.4 kW 6A – check if temperature issues (may need further investigation to identify hot spots).
Centrifuges	<ul style="list-style-type: none"> • Standby units could be procured if downtime projected for an extended period to ensure sludge inventory does not increase excessively (i.e. resulting in accumulation in PSTs and diversion of cess). D/A centrifuge feed pumps 0.8 kW 2A. Bowl drive VSD 14 kW 35A, scroll drive VSD 2kW 5A.
Combined heat and power unit (CHP)	<ul style="list-style-type: none"> • Uses methane gas from gas holder (400 m³ volume) to generate heat and power. NB: monitored/responded 24/7 by Veolia. STC only required to provide correct quantity/quality of biogas. Gas bag volumes and pressure on SCADA/Prism. • NB: cess diversion reduces load to process stream by approximately 10% (i.e. sludge make and load for biological treatment). Max cess throughput 35 l/s.
Power Failure	<ul style="list-style-type: none"> • No manual restarting required after switching back from generator power to main incomer. If permanent generator were to fail under load would require similarly sized asset hard-wired (no plug socket in any MCC).
Contaminated Trade	<ul style="list-style-type: none"> • Date/time-stamped photos and samples for laboratory submission. Ensure Process Scientist and Trade Effluent Inspector aware for further investigation.
Reduced Sludge Disposal	<ul style="list-style-type: none"> • (Site receives imports and is an STC)
Odour Control	<ul style="list-style-type: none"> • Scaled to treat 6,320 m³/hour foul air; D/D 1.6 kW 4A extractor fans. For mobile unit small generator could potentially be used for power supply.

4 Risk Assessment Methodology

The risk assessment has been undertaken by identifying hazards and source-pathway-receptors and assigning a probability of exposure and a severity of consequence. These are assigned as described in Table 4.1 and Table 4.2 and are based on the generic risk assessments used for standard rules “SR2012 No11 and No12”, “SR2009 No 4” and “SR2008 No 19”, applicable to anaerobic digestion operations including use of the resultant biogas.

The probability and severity scores are then combined within a matrix to give an overall magnitude of the risk. This matrix is shown in Table 4.3 and is intended to illustrate the general approach to scoring.

Risks are categorised as either low, medium or high; this ranges from being a nuisance in some instances to potential health risks in others.

Table 4.1: Severity Index

Severity of harm	Severity index
Impact to people or designated receptor	High
Impact to non-designated receptor	Medium
All other impacts	Low

Table 4.2: Probability Index

Severity of harm	Severity index
Impact to people or designated receptor	High
Impact to non-designated receptor	Medium
All other impacts	Low

Table 4.3: Magnitude of risk

Severity index	Probability index		
	Low	Medium	High
Low	Low	Low	Medium
Medium	Low	Medium	High
High	Medium	High	High

Table 4.4: Accident risk assessment table

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
All surface waters close to and downstream of the Site.	Tank failure, spillages of digestate and/or liquids including oil. Damage to drainage system. Spillage of raw materials of sludge/liquor during delivery/storage. Contaminated run off from cake storage e.g. containing suspended solids.	Aquatic or chronic effects to aquatic life, contamination, and water deterioration of water quality.	Direct run-off from the Site across ground surface, via surface water drains, ditches etc. Indirect run-off via the soil layer. Transport through soil/groundwater then extraction/ abstraction at borehole or intake.	Medium	High	High	Potential for leaks from digestions tanks, storage vessels/bays and drainage system which may cause contamination or deterioration of surface water quality. The hardstanding and pavement across the site is in reasonable condition, with a few cracks and potholes noted along the site road. The whole site is not bunded, but most tanks are. Where hardstanding is in place, all water flows to the drainage network which diverts all water to the head of works. Quantities of liquids stored are generally low. The nearest river to the Site is the River Test and is located approximately 40m west. There has been no substantiated pollution incident to water, air,	The Site drainage plan is documented and all staff are trained in the event of emergencies or accidents. Impermeable surface and secondary containment, in the form of constructed bunds or portable bunds, is in place around storage areas of all wastes and raw materials surrounding the STC and WTW. Bunding will also be implemented for all raw material storage. All skips and bins are stored on a hardstanding area. As part of the BAT requirements, and in accordance with the recommendations of the Construction Industry Research and Information Association (CIRIA) standard 736 risk assessment, damaged bunding and hardstanding are to be repaired throughout the Site. All transfer of digestate and material takes place under supervision and with flow rate control.	Medium

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
							or land has been recorded within 250m of the Site.	All tanks undergo a delegated inspection regime and the process parameters are monitored and understood by site operatives.	
Abstraction from watercourse downstream of facility (for agricultural or potable use).	Spillage of liquids, contaminated rainwater run-off from waste e.g. containing suspended solids.	Acute effects, closure of abstraction intakes.	Direct run-off from site across ground surface, via surface water drains etc. then abstraction.	Low	Medium	Low	Watercourse must have medium / high flow for abstraction to be permitted, which will dilute contaminated run-off. No groundwater abstractions are present on-site. There has been no substantiated pollution incident to water, air or land has been recorded within 250m of the Site.	Digestion tanks are built to appropriate standard and require appropriate bunding. There are 14 cake bays on site, which are located within the main building, Cake is moved the site by telehandlers and conveyors. Activities are managed and operated in accordance with the EMS.	Low
Groundwater, land and surface water	Spillages of liquids, contaminated rainwater run-off from wate e.g. containing suspended solids. Sludge/liquid spillages as a result of loss of tank/pipe integrity carelessness during transfer or overfilling	Chronic effects: contamination of groundwater, requiring treatment of water or closure of borehole or abstraction intakes. Acute or chronic effects to aquatic life, contamination and deterioration of land and water quality. Pollution of water or land.	Transport through soil/groundwater then extraction at borehole or intake.	Low	Medium	Low	Potential for leaks from digestion tanks and storage vessels. Site infrastructure and hardstanding is generally in good condition. The hardstanding and pavement across the key areas of the site is in decent condition, but the site road has a number of cracks and potholes. Quantities of liquids stored are generally low.	Spill procedures are in place under EMS363 and 364 as well as a pollution prevention procedure EMS360 All spillages are recorded in the site diary including actions taken. Site Manager ensures the programme of Planned Preventative Maintenance (PPM) is implemented effectively to minimise the probability of equipment malfunction. Control of substances hazardous to health (COSHH) assessment	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>undertaken for all raw materials.</p> <p>Both clean and contaminated surface water is directed to a pumping station which recirculates it back into the system.</p> <p>The surface drainage of potentially contaminated areas from within the Site boundary is routed into the head of the works with no discharge outside of the Site boundary.</p> <p>Regular inspections of the Site drainage systems and other equipment are undertaken, with any repairs and maintenance carried out if necessary. All complaints and other incidents are recorded in the site diary including actions taken.</p> <p>The condensate is clean, uncontaminated water and is small in quantity.</p>	
Groundwater, land and surface water	Spillages of sludge/liquids during transfer of imported and indigenous/ unknown sludge and liquids from tankers.	Acute or chronic effects: contamination of groundwater, requiring treatment of water or closure of borehole or closure of abstraction intakes.	Transport through soil/groundwater then extraction/ abstraction at borehole or intake.	Low	Medium	Low	<p>Potential for spillage during transfer of liquid/sludge from tankers.</p> <p>Sludge currently imported into site from over 30 sites on average.</p>	<p>Impermeable surface required for storage of all waste.</p> <p>Activities to be managed and operated in accordance with the EMS and management plans and procedures implemented to reduce</p>	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
		Acute or chronic effects to aquatic life, contamination and deterioration of land and water quality. Pollution of water or land.					Sludge cake is delivered in sealed RoRo containers and is unloaded inside main building. Cake is transported around the site via telehandlers (20 tonnes per day on average) and conveyors.	spills when transferring liquids/sludges from tankers. Established procedures in place for the acceptance of tankered trade waste (EMS387), waste duty of care (EMS380), operational waste procedures (EMS381) and waste rejection (EMS488). Compliance with the waste duty of care requirements to ensure waste accepted meets the permit conditions and relevant legislation. All liquid run off will be captured in the drainage network and returned to head of works.	
Groundwater, land and surface water	Flooding of site	If waste is washed off site it may contaminate natural habitats downstream.	Flood waters	Low	Medium	Low	Permitted waste types are sludges/bio-solids, which may contain pathogens, so any waste washed off site will add to the volume of the local post-flood clean up and may be hazardous to human health. Area is not known to flood, and there have been no previous floods recorded on the Site.	The drainage network sends water to the head of the works for treatment. There are no direct potentially contaminated discharges to controlled surface waters. Activities to be managed and operated in accordance with a management system and management plans and procedures implemented, including the removal of	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								spilled waste and other pollutants (such as use of spill kits and mobile bunds) before these could enter any flood waters if an event was to occur.	
Local human population, domestic properties, site offices.	Spillages of odorous materials including oils, fuels, chemicals. Failure to clean up spillages. Contaminated spill equipment not disposed of appropriately.	Nuisance, loss of amenity.	Air transport, then inhalation.	Low	Medium	Low	Local residents and staff often sensitive to odour. The nearest sensitive human receptors are two residential properties, located directly adjacent to the east of the Site entrance. There is also a solar PV plant (place of work) is located approximately 50m from the boundary of the Site. Other sensitive receptors include a farmhouse approximately 400m southwest of the site, a residential property 500m northwest of the site and a petrol station approximately 700m northwest of the Site.	Procedures for dealing with spillages are covered in the EMS under EMS363 and 364 for the Site. There is also a Field Event Co-ordinator's (FEC) Manual which provides spillage procedures for EP sites (FEC322). The Site Manager shall ensure all relevant staff are appropriately trained to use the spill kits and that all spillages are cleaned up immediately. All areas of the Site are to be cleaned regularly; Site Manager to oversee regular cleaning schedule, all staff trained on importance of good housekeeping and site cleanliness. All spills are recorded in the site diary including actions taken.	Low
Local human population and local environment.	Flooding of the site.	If waste is washed off-site, it may contaminate buildings/	Flood waters	Low	Medium	Low	Permitted waste types are sludges/bio-solids, which may contain pathogens, so any	The drainage network sends water to the head of the works for treatment. There are no	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
		gardens/ natural habitats downstream.					waste washed off-site will add to the volume of the local post-flood clean up and may be hazardous to human health. The site is located within a Flood Zone 1 (less than 1 in 1,000 annual probability), and also there have not been any reported flooding issues from the Site previously.	direct potentially contaminated discharges to controlled surface waters. Activities to be managed and operated in accordance with a management system and management plans and procedures implemented, including the removal of spilled waste and other pollutants (such as use of spill kits and mobile bunds) before these could enter any flood waters if an event was to occur.	
Local human population and / or livestock after gaining unauthorised access to the installation.	All on-site hazards: machinery, wastes and vehicles.	Bodily injury, death.	Direct physical contact.	Low	Medium	Low	Potential injury to on-site personnel as a result of vehicle movements or equipment malfunction or misuse. Direct physical contact is minimised by activity being carried out within enclosed digesters so a low magnitude risk is estimated. Contact with waste is minimal with exception of leaks or spills from unloading of tanker and transfer of filter cake.	Overall management of the site is overseen by an experienced member of staff holding an appropriate Certificate of Technical Competence (CoTC) awarded by the Waste Management Industry Training and Advisory Board. This competent person delegates responsibilities to appropriately experienced and trained site operatives throughout the operating hours. All operational staff are fully trained in the site operating procedures and SWS' safety and environmental	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>management procedures and are kept up to date on changes.</p> <p>Training includes awareness raising of the potential on-site hazards and health and safety measures to adhere to.</p> <p>Preventative measures will be under continuous review as part of the EMS procedures.</p> <p>Activities are managed and operated in accordance with the EMS – this includes site security measures to prevent unauthorised access. No maintenance work or contractor is permitted on-site without a suitable permission to work and qualification.</p> <p>The main site entrance is secured by a manually operated gate which is locked out of operating hours.</p> <p>Three quarters of the perimeter fencing is a 10ft tall chainlink fence with barbed wire. The remaining quarter is a 3 wired barbed wire fence with trees. The Site has a CCTV system observing the cess plant.</p>	

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>The Site is staffed during shift times (Monday-Friday: 7am-5pm, Saturday: 7am- 1pm and Sunday 7am-11 am).</p> <p>Regular inspections of the boundary fencing and buildings are undertaken to ensure that these have not been compromised and continue to prevent easy access to site. Repairs are undertaken in accordance with the EMS requirements.</p> <p>Key sludge treatment and wastewater treatment activities undertaken within enclosed systems.</p> <p>Under current conditions, five or six 29m³ tankers per day deliver sludge to the Site and sludge can enter the site 24/7.</p> <p>Vehicle movements around the Site vary depending on what activities are being undertaken. Cake is moved to cake bays once a trailer is full. Waste is removed as required. Therefore, frequent vehicle movements are typically undertaken only by site</p>	

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								staff and maintenance contractors. Operator has produced a hazard review and risk assessment documents relating to this and other types of potential incidents, within the EMS, H&S and O&M manuals.	
Local human population and local environment.	Flooding of the site.	If waste is washed off-site, it may contaminate buildings / gardens / natural habitats downstream.	Flood waters	Low	Medium	Low	Permitted waste types are sludges/bio-solids, which may contain pathogens, so any waste washed off-site will add to the volume of the local post-flood clean up and may be hazardous to human health. The site is located within a Flood Zone 1 (less than 1 in 1,000) annual probability, and also there have not been any reported flooding issues from the Site previously.	The drainage network sends water to the head of the works for treatment. There are no direct potentially contaminated discharges to controlled surface waters. Activities to be managed and operated in accordance with a management system and management plans and procedures implemented, including the removal of spilled waste and other pollutants (such as use of spill kits and mobile bunds) before these could enter any flood waters if an event was to occur.	Low
Local human population and / or livestock after gaining unauthorised access to the installation.	All on-site hazards: machinery, wastes and vehicles.	Bodily injury, death.	Direct physical contact.	Low	Medium	Low	Potential injury to on-site personnel as a result of vehicle movements or equipment malfunction or misuse.	Overall management of the site is overseen by an experienced member of staff holding an appropriate Certificate of Technical Competence (CoTC) awarded by the	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
							<p>Direct physical contact is minimised by activity being carried out within enclosed digesters so a low magnitude risk is estimated.</p> <p>Contact with waste is minimal with exception of leaks or spills from unloading of tanker and transfer of filter cake.</p>	<p>Waste Management Industry Training and Advisory Board. This competent person delegates responsibilities to appropriately experienced and trained site operatives throughout the operating hours.</p> <p>All operational staff are fully trained in the site operating procedures and SWS' safety and environmental management procedures and are kept up to date on changes.</p> <p>Training includes awareness raising of the potential on-site hazards and health and safety measures to adhere to.</p> <p>Preventative measures will be under continuous review as part of the EMS procedures.</p> <p>Activities are managed and operated in accordance with the EMS – this includes site security measures to prevent unauthorised access. No maintenance work or contractor is permitted on-site without a suitable permission to work and qualification.</p>	

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>The main site entrance is secured by a manually operated gate which is locked out of operating hours.</p> <p>Three quarters of the perimeter fencing is a 10ft tall chain-link fence with barbed wire. The remaining quarter is a 3 wired barbed wire fence with trees. The Site has a CCTV system observing the cess plant.</p> <p>The Site is staffed during shift times (Monday-Friday: 7am-5pm, Saturday: 7am- 1pm and Sunday 7am-11am).</p> <p>Regular inspections of the boundary fencing and buildings are undertaken to ensure that these have not been compromised and continue to prevent easy access to site.</p> <p>Repairs are undertaken in accordance with the EMS requirements.</p> <p>Key sludge treatment and wastewater treatment activities undertaken within enclosed systems.</p> <p>Under current conditions, five or six 29m³ tankers per day deliver sludge to the Site and</p>	

Data and information				Judgement				Action (by permitting)	
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								sludge can enter the site 24/7. Vehicle movements around the Site vary depending on what activities are being undertaken. Cake is moved to cake bays once a trailer is full. Waste is removed as required. Therefore, frequent vehicle movements are typically undertaken only by site staff and maintenance contractors. Operator has produced a hazard review and risk assessment documents relating to this and other types of potential incidents, within the EMS, H&S and O&M manuals.	
Local human population and local environment.	Explosion of biogas causing release of polluting materials to air (smoke or fumes), water or land	Respiratory irritation, illness and nuisance to local population. Injury to staff, fire fighters or arsonists/vandals. Potential for uncontrolled release of fugitive emissions of gaseous, liquid or solid materials to air, water or land. Acute or chronic effects to aquatic life, contamination	Air transport. Direct run-off from site across ground surface, via surface water drains, ditches etc. Indirect run-off via the soil layer Transport through soil/ groundwater then abstraction.	Low	High	Medium	Emissions to air, land or water may cause harm to and deterioration of air, land or water. Smoke and fumes may cause irritation, illness or nuisance to local residents and site staff. An explosion could cause injury to local residents and site staff from flying debris.	The key sludge treatment and WTW processes are undertaken within enclosed systems such as the AD and biogas systems. Sludge storage tanks are covered and enclosed. Activities are managed and operated in accordance with the EMS, H&S and O&M manuals – this includes site security measures to	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
		and deterioration of land and water quality.					Although biogas is flammable, risk of direct physical contact is minimised by activity being carried out within the sludge treatment works and in containerised units or locked buildings. Permitted waste types limited to sludges and liquids.	prevent unauthorised access. No maintenance work or contractor is permitted on-site without a suitable permission to work and qualification. Fire detection equipment is installed in the CHP containers and the boiler building which activate an alarm on detection of a fire. Slam shut valves on biogas lines will automatically close on detection of a fire to prevent any fuel being supplied to the CHP engines or boilers. Training and regular toolbox talks are given to operatives on-site and all operators and staff understand their role in an emergency. The EMS includes procedures relating to maintenance and inspection of bunding of tanks. Site Manager shall ensure the programme PPM is implemented effectively to minimise the probability of fire through faulty plant and equipment. All equipment is checked and calibrated as per the	
Local human population and local environment.	Explosion of pressurised tanks due to equipment and/or process failure.	Respiratory irritation, illness and nuisance to local population. Fatality / injury to staff, firefighters. Potential for uncontrolled release of fugitive emissions of gaseous, liquid or solid materials to air, water or land. Acute or chronic effects to aquatic life, contamination and deterioration of land and water quality.		Low	Medium	Low	Emissions to air, land or water may cause harm to and deterioration of air, land or water. Smoke, fumes and material released from tanks may cause irritation, illness or nuisance to local residents and site staff. Impact from the tank explosion may cause external damage to other equipment, buildings located close to the epicentre of the explosion.	prevent unauthorised access. No maintenance work or contractor is permitted on-site without a suitable permission to work and qualification. Fire detection equipment is installed in the CHP containers and the boiler building which activate an alarm on detection of a fire. Slam shut valves on biogas lines will automatically close on detection of a fire to prevent any fuel being supplied to the CHP engines or boilers. Training and regular toolbox talks are given to operatives on-site and all operators and staff understand their role in an emergency. The EMS includes procedures relating to maintenance and inspection of bunding of tanks. Site Manager shall ensure the programme PPM is implemented effectively to minimise the probability of fire through faulty plant and equipment. All equipment is checked and calibrated as per the	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								manufacturer's instructions. Emergency operating procedures are in place. Adequate firefighting measures are implemented on-site. The main site entrance is secured by a manually operated gate which is locked out of operating hours. Three quarters of the perimeter fencing is a 10ft tall chain-link fence with barbed wire. The remaining quarter is a 3 wired barbed wire fence with trees. The Site has a CCTV system observing the cess plant. The site is manned during operating hours, with several operatives available on call.	
Local human population and local environment	Accidental fire causing the release of polluting materials to air (smoke or fumes), water or land. Equipment failure.	Respiratory irritation, illness and nuisance to local population. Injury to staff or fire fighters. Potential for uncontrolled release of fugitive emissions of	Air transport. Direct run-off from site across ground surface, via surface water drains, ditches etc. Indirect run-off via the soil layer	Low	Medium	Low	Emissions to air, land or water may cause harm to and deterioration of air, land or water. Smoke and fumes may cause irritation, illness or nuisance to local residents and site staff.	The key sludge treatment and WTW processes are undertaken within enclosed systems. Storage tanks are enclosed and covered, except cake bays, PST and PE tanks. Activities are managed and operated in	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
		<p>gaseous, liquid or solid materials to air, water or land.</p> <p>Acute or chronic effects to aquatic life, contamination and deterioration of land and water quality.</p>	Transport through soil/ groundwater then abstraction				<p>Although biogas is flammable, risk of direct physical contact is minimised by activity being carried out within the sludge treatment works and in containerised units or locked buildings. Risk of accidental combustion of waste is minimal. Permitted waste types limited to sludges and liquids.</p>	<p>accordance with the EMS, H&S and O&M manuals including, fire and spill management. Fire detection equipment is installed in the CHP containers and the boiler building which activate an alarm on detection of a fire. Slam shut valves on biogas lines will automatically close on detection of a fire to prevent any fuel being supplied to the CHP engines or boilers. A Fire Prevention Plan is not required to be submitted for the permit application as the biowaste process on site is wet anaerobic digestion. However, fire prevention and environmental fire risk assessment procedures are provided in the EMS, H&S manual and Safety Instruction Book (SIB) (EMS362, H&S204, H&S440, and SIB603). There is also Safety zoning of areas under DSEAR/PEXA on site and Smoking is only permitted in designated areas.</p>	

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>Firewater is diverted through the drainage system to the head of the works allowing for contaminated fire water to be contained on site and treated through the wastewater treatment system.</p> <p>Training and regular toolbox talks are given to operatives on-site and all operators and staff understand their role in an emergency. The EMS and Safety Instruction Book (SIB) includes procedures relating to maintenance and inspection of bunding of tanks, spills and environmental incidents.</p> <p>Site Manager shall ensure the programme of PPM is implemented effectively to minimise the probability of fire through faulty plant and equipment. All equipment is checked and calibrated as per the manufacturer's instructions.</p> <p>Emergency operating procedures are in place.</p>	

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
Local human population and local environment.	Arson and/or vandalism causing the release of pollution materials to air (smoke and fumes), water or land.	Respiratory irritation, illness and nuisance to local population. Injury to staff, fire fighters or vandals/arsonists. Potential for uncontrolled release of fugitive emissions of gaseous, liquid or solid materials to air, water or land. Acute or chronic effects to aquatic life, contamination of land and water quality.	Air transport. Spillages and contaminated firewater by direct run-off from site across ground surface, via surface water drains, ditches etc. Indirect run-off via the soil layer. Transport through soil/ groundwater then abstraction.	Low	Medium	Low	Emissions to air, land or water may cause harm to and deterioration of air, land or water. Smoke and fumes may cause irritation, illness or nuisance to local residents and site staff. Although biogas is flammable, risk of direct physical contact is minimised by activity being carried out within the sludge treatment works and in containerised units or locked buildings. Risk of accidental combustion of waste is minimal. Permitted waste types limited to sludges and liquids	Adequate firefighting measures are implemented on-site. The key sludge treatment and WTW processes are undertaken within enclosed systems such as AD and biogas systems. Storage tanks are enclosed and covered, except cake bays, PST and PE tanks. Activities are managed and operated in accordance with the EMS, H&S and O&M manuals – this includes site security measures to prevent unauthorised access, fire explosions and spill management. No maintenance work or contractor is permitted on-site without a suitable permission to work and qualification. Fire detection equipment is installed in the CHP containers and the boiler building which activate an alarm on detection of a fire. Slam shut valves on biogas lines will automatically close on detection of a fire to prevent any fuel being	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>supplied to the CHP engines or boilers.</p> <p>A Fire Prevention Plan is not required to be submitted for the permit application as the biowaste process on site is wet anaerobic digestion. However, fire prevention and environmental fire risk assessment procedures are provided in the EMS and H&S manual (EMS362, H&S204 and H&S440). There is also Safety zoning of areas under DSEAR/PEXA on site and Smoking is only permitted in designated areas.</p> <p>Training and regular toolbox talks are given to operatives on-site and all operators and staff understand their role in an emergency. The EMS includes procedures relating to maintenance and inspection of bunding of tanks, spills and environmental incidents.</p> <p>Site Manager shall ensure the programme of PPM is implemented effectively to minimise the probability of fire</p>	

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>through faulty plant and equipment. All equipment is checked and calibrated as per the manufacturer's instructions.</p> <p>Emergency operating procedures are in place.</p> <p>Adequate firefighting measures are implemented on-site.</p> <p>The main site entrance is secured by a manually operated gate which is locked out of operating hours.</p> <p>Three quarters of the perimeter fencing is a 10ft tall chain-link fence with barbed wire. The remaining quarter is a 3 wired barbed wire fence with trees. The Site has a CCTV system observing the cess plant.</p> <p>The site is manned during operating hours, with several operatives available on call.</p> <p>Regular inspections of the boundary fencing and buildings are undertaken to ensure that these have not been compromised and</p>	

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								continue to prevent easy access to the Site. Repairs are undertaken in accordance with the EMS requirements. Firewater is diverted through the drainage system to the head of the works or to storm overflow allowing for contaminated fire water to be contained on-site and treated through the wastewater treatment system.	
Local human population and local environment.	Operator Error.	Pollution to air, land, surface water and groundwater and human health	Air transport, direct run-off from site across ground surface, via surface water drains, ditches etc. Indirect run-off via the soil layer. Transport through soil/ groundwater then abstraction.	Low	Medium	Low	Possible contamination to air, land, groundwater and surface water. Given the level of operator controls which are in place and management plans, it is considered the probability and magnitude will be low.	Activities to be managed and operated in accordance with the EMS and management plans and procedures implemented. All equipment is checked under preventative maintenance plans and is checked and calibrated as per the manufacturer's instructions. Overall management of the Site is overseen by an experienced member of staff holding an appropriate Certificate of Technical Competence (CoTC) awarded by the Waste Management	Low

Data and information				Judgement			Action (by permitting)		
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								<p>Industry Training and Advisory Board. This competent person delegates responsibilities to appropriately experienced and trained site operatives throughout the operating hours.</p> <p>All operational staff are fully trained in the Site operating procedures and SWS' safety and environmental management procedures and are kept up-to-date on changes. Training includes awareness raising of the potential implications of failure to control operations and the potential impact on the environment.</p> <p>Preventative measures will be under continuous review as part of the EMS procedures.</p> <p>Emergency operating procedures are in place and detailed in the Site's Operational Contingency Plan.</p> <p>Senior site-based management have direct responsibility for</p>	

Data and information				Judgement				Action (by permitting)	
Receptor	Source	Hazard	Pathway	Probability of exposure	Consequence	Magnitude of risk	Justification for magnitude	Risk management	Residual risk
								implementing risk management measures.	

5 Reporting and Recording

5.1 Reporting

The procedure employed by Southern Water for reporting, recording, investigating and responding to incidents or breaches of the permit is the EPR notification procedure. Notifications must be made to the Environment Agency without delay and within 24 hours of the detection of an accident that has caused, is causing or may cause significant pollution or a breach of a limit specified in the Site's Environmental Permit.

If an incident with potentially significant environmental consequences occurs, Southern Water will notify the Environment Agency without delay. Southern Water will also inform the Environment Agency should any complaints be received directly to the Site due to the incident and will advise what remedial measures or actions have been taken to address the issue. Copies of complaints received will be made available to the Environment Agency for review on request.

Routine operation of the installation is subject to the conditions of the Site permit which details various requirements for actions and reporting for both routine and non-compliance.

The permit sections typically include:

- **Section 1 - Management of Installation** - General management of the Site, including handling and disposal of wastes
- **Section 2 Operation of Installation** - General operation of permitted activities and improvements
- **Section 3 Emissions and Monitoring** - Routine monitoring of all emissions (e.g. odour), including annual reporting of specified point emissions (e.g. various specified exhaust gases from CHPs)
- **Section 4 Records and Reporting** - An important section that includes the reporting of non-compliance with any permitted element. The major elements of concern would be:
 - Loss of containment of gaseous substance
 - Loss of containment of liquid substance
 - Equipment / plant failure causing loss of gas or liquid – inclusive of routine emissions monitoring.

Any losses or failures to comply with these areas require immediate notification to the Environment Agency, followed by "Schedule 6, Part A Notification" by email or paper means. The Part A must be submitted within 24hrs of detection of failure. "Part B" notification would then follow giving supporting information as soon as practicable.

Handling of the incidents on Site will be in line with relevant internal incident and accident procedures. These are all subject to audit via internal and external audit protocols.

5.2 Recording

In the event of an accident, a Schedule 6 notification is completed following an incident with potentially significant environmental consequences. Relevant information that must be recorded includes:

- Date, time and location of the event
- Substances involved, including estimated quantities

- Immediate measures taken to minimise environmental impacts

Part A must be completed within 24 hours of detection of the incident and Part B is completed as soon as practicable. Records will be made of all incidents with potentially significant environmental consequences that occur at the Site. The associated actions arising will be held in Corporate Documents.

All records of events with potentially significant environmental consequences and the associated actions arising will be retained as required by the Environmental Permit. Where an incident with potentially significant environmental effects occurs, and the nature of the incident supports further investigation, a post incident review may be required.

5.3 Post-incident Review

Following an incident where potentially significant environmental effects occur, and the nature of the incident warrants it, the incident will be logged and an investigation will take place to determine both the root cause of the incident and how to prevent the incident re-occurring.

This review will assess:

- The cause of the incident
- The effectiveness of the response measures
- The effectiveness of the emergency response management team
- Lessons learned
- Recommendations for improvement

The findings of the investigation will be reported to Southern Water's management and shared with all relevant employees to enable the incorporation of good practice into future works.

Any changes to processes or procedures required as a result of the formal review will be communicated to Southern Water management and employees. If, as a result of the incident, this Accident Management Plan is subject to revision, it should be updated as part of this post-incident review and communicated to relevant Southern Water management and employees.

All safety equipment used to respond to an incident should be checked and replenished as required.

5.4 Competence and Training

Staff at the Site have the competency to manage and operate activities without causing pollution. Competency is ensured through the appropriate training of all staff, covering:

- Awareness of the regulatory implications of the Environmental Permit and AMP for the activity and their work activities
- Awareness of all potential environmental effects from operation under normal and abnormal circumstances
- Awareness of the need to report any deviation from the Environmental Permit
- Prevention of accidental emissions and action to be taken if accidental emissions occur

All staff are aware of the implications of activities undertaken including the operation of the Site. Staff have clearly defined roles and responsibilities. Skills and competencies necessary for key posts are documented and records of training needs and training received for these posts maintained.

Training in the actions to be taken in the event of an accident or emergency is provided to all.

Operator and Contractor staff working on-site as part of their mandatory site induction procedure. All staff are required to demonstrate their understanding of the AMP, and the actions and procedures contained therein, prior to undertaking any activities on-site. It is the responsibility of the Works manager to ensure that all staff members have received this training.

Regular installation drills are undertaken to ensure that all staff are aware of the actions to be taken in the event of an accident or emergency and those staff with specific responsibilities are fully versed in their duties.

Copies of the AMP are available for the review of all staff.

6 Emergency Response Procedures (ERP)

The following Hazards are addressed in specific Emergency Response Procedures (ERP) which will be located at each Emergency Control Centre.

- Fire
- Explosion
- Pollution
- Flooding
- Road traffic accident impact or collision
- Collapse of a structure or building
- Spill transferring wastes
- Chemical spillage/leak onsite
- Sludge spillage on site
- Diesel spillage/leak on site
- Overfilling vessels
- Plant and equipment failures
- Containment failure
- Failure to contain firewater
- Incorrect connection leading to releases to drains and other systems
- Incompatible substances coming into contact

In the event of one or combination of the following incidents occurring, the actions listed in the relevant ERP must be followed.

6.1 Fire

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	Action
		Use the Model Fire Emergency plan on the H&S notice Board and in the Grab Pack container. This Model Emergency plan outlines responsibilities for site staff and call out staff during events.
		Raise the Site Alarm - call 999 and raise the alarm with the DM / RCC.
		SW rules are that we only fight fire to evacuate area or building.
		Attend the muster point and check register for any missing persons.
		If it is safe to do so, isolate any fuel sources.
		Make sure the fire brigade first response team are handed the Site Grab Pack on arrival.
		Liaise with the fire brigade on the area, mention if anyone is missing and confirm what is stored on site (e.g. chemicals, combustible materials, BIOGAS systems etc)
		Refer to plan of Fire Hydrants / Final effluent / Potable water points for use if required.

6.2 Explosion

N/A	Done	The Incident controller will: -
		Raise the Site Alarm - call 999 and raise the Alarm with the DM / RCC.
		Attend the muster point and check register for any missing persons.
		Make sure the fire brigade first response team are handed the Grab pack on arrival.

N/A	Done	The Incident controller will: -
		Liaise with the fire brigade on the area, mention if anyone is missing and confirm what is stored on site (e.g. chemicals, combustible materials, biogas systems etc – as per Sections above)
		Refer to plan of Fire Hydrants / Final effluent / Potable water points for use if required.

6.3 Pollution

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	Action
		Use the Pollution 30 Minute Plan.
		Consider whether the pollution event can be mitigated or stopped - use the 10-minute checks. If it is safe to do so, isolate the equipment to stop the pollution, the consequence of isolating any equipment needs to be considered.
		If not raise the Alarm with the FEC / Process scientist in hours and DM / RCC/ FEC out of hours.
		Liaise with the FPM/ Process scientist in hours & DM / RCC/ FEC out of hours to reduce the impact.

6.4 Flooding

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Use the Pollution 30 Minute Plan.
		Raise the site alarm – call 999 as soon as the site starts to flood and notify the DM / RCC.
		Attend the muster point and check register for any missing persons.
		If it is safe to do so, try to understand why the site is flooding. This may be obvious like the river is overflowing – the river levels are controlled by the Environment Agency so it may be possible to be managed quickly.
		Make sure the Fire brigade/first response team are handed the KFB Grab pack on arrival.
		Liaise with the fire brigade on the area, mention if anyone is missing and confirm what is stored on site (e.g. chemicals, combustible materials, biogas systems etc)

6.5 Road traffic accident impact or collision

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Raise the Site alarm - call 999 and raise the alarm with the DM / RCC.
		Keep the area isolated, do not move vehicles other than for freeing people.
		Cordon off area if the impact or accident is serious.
		Await instruction from the fire brigade or police depending on the nature of the event.
		Please see plan of Fire Hydrants / Final effluent / Potable water points for use if required.
		For leaking tankers after the event (Fuel or Chemicals) put out spill containment if safe to do so.

6.6 Collapse of a structure or building

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Raise the alarm - call 999 and raise the alarm with the DM / RCC.
		Attend the muster point and check register for any missing persons.
		Keep the area isolated, do not move debris other than for freeing people.
		Cordon off area if the collapse is serious.
		Await instruction from the fire brigade or police depending on the nature of the event.
		Please see plan of Fire Hydrants / Final effluent / Potable water for use if required.

6.7 Spill transferring wastes

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Use the Pollution 30 Minute Plan.
		Stop the transfer if safe to do so and isolate if possible - complete Personnel Risk Assessment first.
		Contain the spill if safe to do so, using spill kits if small amounts, cover drains if possible
		Determine what has been spilt and where it has gone (i.e. to ground, to the site drains etc.)
		Report the incident to the FPM/DM/RCC.
		Discuss the impact of the spill with the FPM /Process Scientist/DM.

6.8 Chemical spillage/leak onsite

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Identify source and look to isolate the affected tank/pipework to prevent further leaks.
		Escalate & report to the pollutions team or [REDACTED]
		Instigate mitigation or remedial work <ul style="list-style-type: none"> Contain the affected area – utilise spillage kits/pads to absorb the chemical If chemical has made its way to the site drains please confirm if they return to the works return or the environment. If they go to works return consider isolating and tankering this as contaminated waste rather than returning through the process. If this drains to the environment consider bunging the outfall and tankering the contaminated waste from site.
		Check the notice board to see if the site is located within a SPZ (source protection zone) or SSSI. If you are unsure ask the Pollution Team who can check. Out of hours please ask RCC/Duty Manager. This will guide you on remedial actions needed to be taken.
		Collect evidence (photographs, samples & keep any parts of failed assets that will be needed as evidence)
		Assess the condition of the downstream processes to determine the level of contamination present and whether they will be adversely affected.

6.9 Sludge spillage on site

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Investigate where the spillage is coming from and work backwards to see where the issue starts.
		Spill from tank <ul style="list-style-type: none"> Isolate the sludge tank so no more sludge is feeding into it.

N/A	Done	The Incident controller will: -
		<ul style="list-style-type: none"> • If the tank has overflowed isolating will stop the spill, if it is from a hole in the tank it may need to be drained to stop the spill. Due to size of sludge tanks, it would be preferable to explore setting up over-pumping and hosing to drain tank and send further down sludge process stream/use mobile thickener. • Contain the spilled sludge with sandbags/barriers to prevent spread to the environment. • If the area has drains please check the site drainage plan to ensure these drain to the works return. If they do not or there is no plan assume they drain to the environment. In this case seal the drains to prevent sludge draining into it. • Depending upon the size of the spillage organise a Supersucker and a 4k tanker to assist with the clean-up. For smaller spills (with drains which lead to works return) it may be suitable for the operator to clean up themselves. • If this is the only sludge tank onsite consider other options for removal of sludge from the process whilst the tank is offline. • The indigenous sludge make from the site is 143 m³/d (at assumed 3%DS); cess input calculated as additional 21 m³/d. • Depending on where repair required if likely to take >1 day instigate overpumping to bypass tank/sludge processing node until the repair can be made.
		<p>Spill from pipe</p> <ul style="list-style-type: none"> • Isolate the sludge pipeline and either end. • Contain the spilled sludge with sandbags/barriers to prevent spread to the environment. • If the area has drains, please check the site drainage plan to ensure these drain to the works return. If they do not or there is no plan assume they drain to the environment. In this case seal the drains to prevent sludge draining into it. • Depending upon the size of the spillage, organise a Supersucker and a 4k tanker to assist with the clean-up. For smaller spills (with drains which lead to works return) it may be suitable for the operator to clean up themselves. • Organise a framework contractor to repair the pipe (if above ground) or a dig down and repair if underground. • If this is the only desludge route and cannot be bypassed, ensure other options for controlling the sludge are put in place if the repair is likely to take >1 day. • The indigenous sludge make from the site is 143 m³/d (at assumed 3%DS); cess input calculated as additional 21 m³/d. h. Depending on where repair required if likely to take >1 day instigate over-pumping to bypass tank/sludge processing node until the repair can be made.

6.10 Diesel spillage/leak on site

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Identify source and look to isolate the affected tank/pipework to prevent further leaks
		Escalate & report to the pollutions team on [REDACTED]
		<p>Instigate mitigation or remedial work</p> <ul style="list-style-type: none"> • Contain the affected area – utilise spillage kits/pads to absorb the diesel. • If diesel has made its way to the site drains, please confirm if they return to the works return or the environment. If they go to works return, consider isolating and tankering this as contaminated waste rather than returning through the process. If this drains to the environment, consider bunging the outfall and tankering the contaminated waste from site. • If diesel has escaped from site, instigate remedial works, which could include booming watercourses.
		Check the notice board to see if the site is located within a SPZ (source protection zone) or SSSI? If you are unsure, ask the Pollution Team who can check. Out of hours please ask RCC/Duty Manager. This will guide you on remedial actions needed to be taken.

N/A	Done	The Incident controller will: -
		Collect evidence (photographs, samples & keep any parts of failed assets that will be needed as evidence)
		Assess the condition of the downstream processes to determine the level of contamination present. Instigate remedial action, if necessary, which could include skimming of tanks, draining of tanks or re-seeding if the biological process has been severely affected.
		If diesel has worked its way through the entire process, then deploy a boom for the outfall to capture any further diesel and remove accordingly.
		If the isolation process has removed the availability of any onsite generators and the repair is likely to be >1 day then contact framework Partners to install a temporary fuel tank whilst the repairs are carried out.

6.11 Overfilling vessels

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Stop the transfer if safe to do so and isolate if possible - complete Personnel Risk Assessment first.
		Use the Pollution 30 Minute Plan.
		Contain the spill, if safe to do so, using spill kits if small amounts, cover drains if possible
		Determine what has been spilt and where it has gone (i.e. to ground to the site drains etc.)
		Report the incident to the FPM/DM/RCC.
		Discuss the impact of the spill with the FPM /Process Scientist/DM.

6.12 Plant and equipment failures

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Stop the transfer or process if safe to do so and isolate if possible - complete Personnel Risk Assessment first.
		Use the Pollution 30 Minute Plan.
		Contain the spill, if safe to do so, using spill kits if small amounts, cover drains if possible
		Determine what has been spilt and where it has gone, including Biogas releases (i.e. release to ground, to the site drains or the atmosphere etc.)
		Report the incident to the FPM/DM/RCC.
		Discuss the impact of the spill with the FPM /Process Scientist/DM.

6.13 Containment failure

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Stop the transfer or process if safe to do so by isolation - complete a personal Risk Assessment first.
		Use the Pollution 30 Minute Plan.
		Contain the spill, if safe to do so, using spill kits if small amounts, cover drains if possible
		Determine what has been spilt and where it has gone, including Biogas releases (i.e. release to ground, to the site drains or the atmosphere etc.)
		Report the incident to the FPM/DM/RCC.
		Discuss the impact of the spill with the FPM /Process Scientist/DM.

6.14 Failure to contain firewater

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Use the Pollution 30 Minute Plan.
		Contain the firewater if it is possible to do so, use spill kits if small amounts, cover drains if possible
		Determine what amount has been spilt and where it has gone (e.g. site return WPS, to ground, to the site drains). Consider whether it can be contained and disposed of offsite.
		Report the incident to the FPM/DM/RCC.
		Discuss the impact of the spill with the FPM /Process Scientist/DM. – Process Scientist to risk assess impact.

6.15 Incorrect connection leading to releases to drains and other systems

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Use the Pollution 30 Minute Plan.
		Contain the spill, if safe to do so, using spill kits if small amounts, cover drains if possible
		Determine what amount has been spilt and where it has gone, is it in the site return WPS, has the release been to ground to the site drains. Consider whether it can be contained and disposed of offsite.
		Report the incident to the FPM/DM/RCC.
		Discuss the impact of the spill with the FPM /Process Scientist/DM. – PS to Risk Assessment & impact.

6.16 Incompatible substances coming into contact

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Use the Pollution 30 Minute Plan.
		Keep upwind of any potential fumes.
		Raise the Site alarm - call 999 if any fire or fumes are being generated, raise the Alarm with the DM / RCC.
		Discuss the impact of the spill with the FPM /Process Scientist/DM.
		Contain the liquid solution, if safe to do so, using spill kits if small amounts, cover drains if possible
		Determine what amount has been spilt and where it has gone (e.g. released to site return WPS, to ground, to the site drains). Consider whether it can be contained and disposed of offsite.
		Check the site COSHH register for both or all the components for likely reactions.

6.17 Emission of effluent or Biogas before composition checked

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Use the Pollution 30 Minute Plan.
		Remember this emission may be a release of biogas to atmosphere. (We are not able to sample biogas).
		Sample the effluent if it is safe to do so and notify the FPM/ Process scientist of results.

N/A	Done	The Incident controller will: -
		Discuss the impact of the spill with the FPM /Process Scientist/DM for next steps.
		Report the incident to the DM/RCC/ SW Pollution team for Info.
		Stop the transfer if safe to do so and isolate if possible - complete Personnel Risk Assessment first.
		Contain the release if safe to do so, if there are spare containment tanks utilise these via discussion with Incident team.
		Stop the process, use site spill kits if small amounts have been spilt, cover drains if possible.
		Determine what has been released and where it has gone (e.g. to ground, to the site drains etc.)

6.18 Theft & Vandalism

The Duty Operator on receiving either an automatic or a personnel-raised alarm will:

N/A	Done	The Incident controller will: -
		Use the Pollution 30 Minute Plan if the vandalism has affected the process.
		Remember pollution emission may be a release of biogas to atmosphere or poor effluent quality or a release from a process or fuel storage vessel to land or a water course.
		Discuss the impact of the theft or vandalism with the FPM /Process Scientist/DM.
		Report the incident to the DM/RCC/ SW Pollution team for inclusion in the morning 24-hour report.
		Make a thorough inspection of the SCADA and a walk of the Site if we have had intruders or vandalism on the Site as changes may have been made to the process.
		Report any thefts or vandalism to the police and ask for a crime reference number.

A. Grab Pack



Southern Water

Fullerton WTW/STC

Emergency Grab pack.

Nov 2023.

Final Draft

Author: [REDACTED]

Sponsor: [REDACTED]

Approved and signed off by: [REDACTED]

Version 2.0 Nov 2023

Contents

1. EMERGENCY CONTACT NUMBERS	3
2. SITE PLANS.....	4
3. MATERIALS & CHEMICALS STORAGE ON SITE.....	8
4. LOCATION OF FIRE EXTINGUISHERS ON SITE	11
5. WASHATER MAINS & FIRE HYDRANTS	13
6. DSEAR DRAWINGS	14
7. FIRE RISK ASSESSMENT	34
8. COSHH DATA SHEET	35

1. EMERGENCY CONTACT NUMBERS

Management

RCC – 0330 3030261

[REDACTED]

[REDACTED]

SITE OPS

[REDACTED]

[REDACTED]

[REDACTED]


[REDACTED]

2. SITE PLANS


Map of Processes




Map of flammable substances and fire hydrants .(H)



Map of biogas systems



Emissions Ref	Emissions Points	Assets Ref	Assets	X	Y
A01	CHP exhaust stack	1	CHP	436850	141350
A02	Boiler exhaust stack	2	Boiler house	436915	141409
A03	Flare stack	3	Flare	436820	141327
A04	Whessoe valve 1	4	Gas holder	436840	141340
A05	Whessoe valve 2	5	Digester 1	436854	141401
A06	Whessoe valve 3	6	Digester 2	436872	141412
A07	Whessoe valve 4	7	Digester 3	436881	141394
A08	Generator exhaust	8	Generator	436880	141440
A09	OCU exhaust 1	9	Odour control unit 1	436992	141562
A10	OCU exhaust 2	10	Odour control unit 2	436859	141503
A11	OCU exhaust 3	11	Odour control unit 3	436878	141381
W1	Inlet	12	Inlet and cess reception	437006	141562
		13	Cake Bays x6	436738	141300
		14	Cake Bays x8	436923	141665
		15	Centrifuge building	436755	141353
		16	Ferric dosing	436955	141587
		17	Liquor store	436822	141387
		18	Poly store and make up	436762	141362
		19	Post-digestion storage tank	436802	141370
		20	Post-digestion storage tank	436814	141354
		21	Rag and grit screening	436868	141637
		22	Receiving bay and conveyor	436732	141343
		23	Site drainage return	436701	141385
		24	Third party import sludge	436883	141499
		25	TTW imports	436753	141428
		26	Vector waste	436855	141625
		27	Condensate pot 1	436832	141332
		28	Condensate pot 2	436847	141341
		29	Condensate pot 3	436885	141415



3. MATERIALS & CHEMICALS STORAGE ON SITE

List of combustible materials stored on site.

WASTE INVENTORY (See EMS 480)					
Trade Name/ Substance	Solid/liquid/ gas/powder	UN Number	Max Stored on Site	Location Marked on Site Plan	Type of Containment
Biogas	Biogas	UN1971	<3000 m3 max	Biogas Holder Digester Headspace Flare Stack CHP Engine	Gas bag Digesters Pipelines
Diesel Oil	Liquid	UN1202	25m3	Positions 2 & 3 on site Map.	Tank
Sludge	Liquid	Non - Hazardous	2000m3	Screened Sludge Reception Tanks x2	Tank
Sludge Cake	Dried Cake	Non - Hazardous	<6000m3	Cake Bays	Bays
Polymer	Powder	UN2923	1 X 1m3/750kg bags	Inside building 4 – Thickener building V on map.	Bags
Polymer	Powder	UN2923	10 X 1m3/750kg bags	Inside building 5 – Centrifuge building R on map.	Bags
Polymer	Liquid	UN2923	12m3	Stored in tank in Centrifuge building R on map.	Storage tank.
Lime (Dust).	Solid (granules)	UN1956	Variable this is an unusual activity	Cake Bays	In bags
Gas Cylinders	Gas	N/A	Welding / burning Equip.	Workshop marked as building Y on site plan.	Gas Bottles stored in a locked building overnight.
Ferric Sulphate	Liquid	UN1760	35,000 ltrs	Number 1 on site plan.	Storage tank.
Aerosol Leaks of Biogas	Gas	UN1971	Not Known as would be formed by leaks	Biogas Holder area Digester headspace	Gas bag Digesters Pipelines Flare Stack CHP Engine
JCB Loader / MTS Tankers & Chemical Delivery tankers.	Diesel Powered	N/A	< 100 ltrs Diesel Fuel tank on machine	Out of hours stored in front of the control room but may be anywhere on site during normal hours.	Vehicle stored outside control room overnight.

Likely combustible waste management.

- Paper or cardboard – this is controlled by using sealed bins.
- Plastics – We do not store plastic waste other than in recycle Bins.
- Rags and textiles – rag is managed in skips by MTS for composting.
- Scrap metals contaminated or mixed with other waste such as oils or plastics – managed by Southern Water Scrap metal skips and Fly tipping requests to empty skips.
- De-polluted and un-depolluted ELVs – We do not break ELV's
- Refuse derived fuel (RDF) and solid recovered fuel (SRF) – N/A.
- Compost and plant material – Managed by MTS on SW behalf.
- Biomass – Managed In process control and via sludge cake.
- Mixed waste containing any combustible wastes – Via Sealed bins.
- Sludge cake Storage in cake bays.
- Lime used to treat Sludge cake could be stored on Cake Bays if in use.
- WEEE – Managed via Locked Wee containers.
- Wood – Pallets are stored on site.

Non-Combustible.


CHEMICAL PRODUCT INVENTORY (See relevant COSHH sheets)					
Trade Name/ Substance	Solid/liquid/ gas/powder	UN Number	Max Stored on Site	Location Marked on Site Plan	Type of Containment
Antifoam	Liquid	N/A	1m3	Inside centrifuge building R on site MAP.	Intermediate Bulk Container (IBC)
Polymer	Liquid	N/A	12m3 as liquid in storage tank	Inside Centrifuge building R on site Map	Storage tank.
Wastewater	Liquid	N/A	5200m3	4 Storm Tank	Tank
Wastewater	Liquid	N/A	6400m3	4 X Primary Settlement Tanks	Tanks
Wastewater	Liquid	N/A	4200m3	4 x Mineral media	Filter beds
Wastewater	Liquid	N/A	7800m3	2 x Plastic media filters	Tanks
Wastewater	Liquid	N/A	2600m3	4 x Intermediate Settlement tanks	Tanks
Wastewater	Liquid	N/A	3840 m3	6 X Final Settlement Tanks	Tanks
Sludge	Liquid	N/A	<3000m3	3 X Digesters	Tanks
Sludge	Liquid	N/A	90m3	Thickened Sludge Storage Tank	Tank

4. LOCATION OF FIRE EXTINGUISHERS ON SITE.

POLLUTION PREVENTION EQUIPMENT INVENTORY (ON AND OFF-SITE RESOURCES) ILLUSTRATED ON FULLERTON IMP MAP			
Type	Location	Amount	Staff Contact
Fire Extinguishers	Reception Area	2	[REDACTED]
Fire Extinguishers	Corridor to mess room	2	[REDACTED]
Fire Blanket	Mess Room Kitchen area	1	[REDACTED]
Fire Extinguishers	Mess Room Kitchen area	1	[REDACTED]
Fire Extinguishers	Boiler House	1	[REDACTED]
Fire Extinguishers	Drum Thickener building	1	[REDACTED]
Fire Extinguishers	Centrifuge building downstairs	1	[REDACTED]
Fire Extinguishers	Centrifuge building upstairs	2	[REDACTED]
Fire Extinguishers	Works return/humus tank building	1	[REDACTED]
Fire Extinguishers	Sandfilter kiosk	2	[REDACTED]
Fire Extinguishers	Strainpress building	1	[REDACTED]
Fire Extinguishers	Ferric kiosk	1	[REDACTED]


Fire Extinguishers	Plastic media filter kiosk	1	[REDACTED]
Fire Extinguishers	Primary tank underground gallery	1	[REDACTED]

WASHATER MAINS & FIRE HYDRANTS (H).



5. DSEAR DRAWINGS

AREA REF	SHEET No.	SITE AREA DESCRIPTION
1	2	INLET
2	3+4	PRIMARY DIGESTERS
3	3+4	POST DIGESTION STORAGE TANKS (x2)
4	5+6	POLYELECTROLYTE STATION
5	7	BOILER HOUSE
6	8+9	GAS HOLDER
7	8+9	GAS HOLDER AIR BLOWERS
-	10	DIESEL TANK-DOUBLE SKINNED



ZONE LEGEND			
ZONE 0		ZONE 20	
ZONE 1		ZONE 21	
ZONE 2		ZONE 22	

ENG-FM-210-01-00

DRAWING NO. KH. 639382.030.222957.A		REVISION A																																																								
<p>1. DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.</p> <p>2. ALL DIMENSIONS DENOTED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL.</p> <p>3. ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAINS SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.</p>																																																										
<p>CURRENT VERSION INFORMATION THIS IS MORRISON DRAWING (NOT AS BUILT) DRAWING NO: 73863.0118 REVISION 00 DATE: 13/12/05 ALSO APPROVED BY: STEVEN MANCHESTER (BRE COMPANY) DATE: 23/05/2019.</p>																																																										
<table border="1"> <thead> <tr> <th>DATE</th> <th>BY</th> <th>REV</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>			DATE	BY	REV	DESCRIPTION																																																				
DATE	BY	REV	DESCRIPTION																																																							
<p>Copyright and other intellectual property rights in this document and all related documents, drawings, etc. including calculations, is invested in BTU, and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.</p>																																																										
<p>CLIENT: </p>																																																										
<p> BTU Southmoor Lane Havant Hampshire PO9 1JW</p>																																																										
<p>PROJECT TITLE: FULLERTON WTW ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER, HAMPSHIRE, SP117HR.</p>																																																										
<p>DRAWING TITLE: DSEAR SITE PLAN</p>																																																										
<p>SHEET 1 OF 10</p>																																																										
DATE UPD: FULLERTO	SCALE: NTS	DATE: 101246																																																								
BY: 639382	SCALE: NTS	DATE: AG																																																								
DRAWING NO. KH. 639382.030.222957.A		REVISION A																																																								

5 Risk assessment

For each hazardous area a risk assessment table has been compiled, giving a risk rating for the identified ignition hazards. The likelihood rating given to sparks generated by equipment is based on the number of non-ATEX equipment present. Equipment in each zoned area was catalogued. Where applicable any hazardous areas allocated are illustrated in hazardous zoning drawings of the site and relevant equipment.

5.1 Preliminary treatment

5.1.1 Inlet works

The inlet works at Fullerton STC are open to atmosphere both prior to and after screening.



Figure 1: Inlet works, prior to screens.

According to Southern Water's MED 4004 2015^[3], the inlet works have been allocated a zone 2 classification internally. This is due to the potential for flammable liquids such as petrol possibly being present in the accepted waste.

The zone will exist above the liquid surface as high as the coping and up to the inlet screens.




Figure 2: Inlet works, after screening.

Raw sewage inlet works


Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	n/a	n/a	n/a

NB. Any equipment in the hazardous zone was not accessible.

INLET WORKS



Plan



Elevation

CHECK PRINT DISTRIBUTION

ARC	
CIV	
ELE	
MEC	
PRO	
SER	
STR	
PPL	
HYD	

Tick for Distribution

ZONE LEGEND

ZONE 0	
ZONE 1	
ZONE 2	

CHECK PRINT REF: A1

PREPARED BY: _____ DATE: _____

PRELIMINARY CAD CHECKED BY (if required): _____

CAD CHECKED BY: _____ DATE: _____

CHECKED BY: _____ DATE: _____

REVIEWED BY: _____ DATE: _____

REASON FOR ISSUE: _____

AUTHORISE FOR ISSUE:

AUTHORISED BY: _____ DATE: _____

CHECK PRINT INFORMATION

RED - Item to modify
GREEN - Comment for CAD
BLUE - Modification complete
YELLOW - Item for clarification
 Pen colours for print mark-ups

DRAWING NO: KH.639382.030.222958.A REVISION: A

NOTES

- DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
- ALL IMAGES DERIVED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL.
- ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAINS SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.

CURRENT VERSION INFORMATION
 THIS IS MORRISON DRAWING (DRYER BUILDING ZONES)
 DRAWING NO:73863.0142 REVISION:00 24/01/06
 ALSO APPROVED BY :STEVEN MANCHESTER (BRE COMPANY)
 DATE: 23/05/2019.

23/05/2019	AP	SM	SM	A	BRE COMPANY
05/02/2019	AP	SM	SM	00	BRE COMPANY (AS BUILT)

DATE: 23/05/2019 REVISION: 001 REASON FOR ISSUE:

Copyright and other intellectual property rights in this document and all related documents, drawings, etc., including calculations, is invested in BTU, and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.



PROJECT TITLE: FULLERTON WTW
 ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER, HAMPSHIRE, SP117HR.

DRAWING TITLE: DSEAR
 INLET WORKS

SHEET 2 OF 10

SITE UNIT MEMORIC: FULLERTO NO: 101246

PRO: 639382 SCALE: NTS MASTER SIZE: A3

DRAWING NO: KH.639382.030.222958.A REVISION: A



5.1.2 Cess inlet

Cess is imported from tankers directly to the inlet works. Therefore, the zoning in section 5.1.1 applies.



Figure 3: Cess tanker inlet.

Cess inlet

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	1	2	2



5.2 Storm treatment

The storm treatment is unclassified.

5.3 Primary treatment

According to Southern Water's MED 4004 April 2015,^[3] the primary treatment process is unclassified.

5.4 Cake storage

The cake is undigested and is stored outside in open bays and is therefore unclassified.



Figure 4: Cake bays.



5.5 Sludge treatment

5.5.1 Digester 1

There are three digesters at Fullerton STC. Each digester is buried underground.


Zone 0 internally and zone 1 externally surrounding the Wesso valve on top of the digester.



Figure 5: Digester 1.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting; sparks & hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones not allowed to be taken into zoned areas. Signs present.	1	2	2
Lightening	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	3	2	6

DIGESTER (X3) & POST-DIGESTER (X2) PLAN



CHECK PRINT INFORMATION
 RED - Item to modify
 GREEN - Comment for CAD
 BLUE - Modification complete
 YELLOW - Item for clarification
 Pen colours for print mark-ups

CHECK PRINT REF: A1
 PREPARED BY: _____ DATE: _____
 PRELIMINARY CAD CHECKED BY (if required): _____
 CAD CHECKED BY: _____ DATE: _____
 CHECKED BY: _____ DATE: _____
 REVIEWED BY: _____ DATE: _____
 REASON FOR ISSUE: _____
 AUTHORISE FOR ISSUE:
 AUTHORISED BY: _____ DATE: _____

CHECK PRINT DISTRIBUTION	
ARC	
CIV	
ELE	
MEC	
PRO	
SER	
STR	
PPL	
HYD	
Tick for Distribution	

DRAWING NO: KH.639382.030.2Z2959.A REVISION: A

- DO NOT SCALE, WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
- ALL IMAGES DENOTED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL.
- ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAIN SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.

CURRENT VERSION INFORMATION
 THIS IS (BRE COMPANY) DRAWING (NOT AS BUILT)
 APPROVED BY: STEVEN MANCHESTER (BRE COMPANY)
 DATE: 23/05/2019.

DATE	BY	CHKD	REV	REASON FOR ISSUE
23/05/2019	AP	SM	SM	A BRE COMPANY
10/10/2005	SM	PF	OD	BRE COMPANY (AS BUILT)

Copyright and other intellectual property rights in this document and all related documents, drawings, etc. including calculations, is invested in BTU and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.

CLIENT:

BTU
 Southmoor Lane
 Havant
 Hampshire
 PO9 1JW

PROJECT TITLE: FULLERTON WTW
 ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER,
 HAMPSHIRE, SP117HR.


DRAWING TITLE: DSEAR
 DIGESTER & POST-DIGESTER PLAN


SHEET 3 OF 10




DATE: FULLERTO	DATE: 10/12/46
NO: 639382	SCALE: NTS
DRAWING NO: KH.639382.030.2Z2959.A	REVISION: A

ZONE LEGEND	REF	SITE AREA DESCRIPTION	ZONE	T CLASS	EXTENT OF ZONE (V-VERTICAL, H-HORIZONTAL) MEASURED FROM POINT OF POSSIBLE RELEASE
ZONE 0 	A	OVERFLOW CHAMBER (SEALED)	0		INTERNALLY
	B	EXTERNAL ZONE ON TOP OF DIGESTER & POST DIGESTER 2	1		EXTERNALLY
	C	EXTERNAL ZONE ON TOP OF POST DIGESTER 1	2		EXTERNALLY
ZONE 1 					EXTERNALLY 'V' + 'H' - 3m
ZONE 2 					

PRIMARY DIGESTERS (X3) & POST DIGESTERS (X2) ELEVATION



DRAWING NO.	KH. 639382.030.222960.A		REVISION	A
<p>1. DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE. 2. ALL IMAGES NOTED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL. 3. ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAINS SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.</p>				
<p>CURRENT VERSION INFORMATION THIS IS MORRISON DRAWING (NOT AS BUILT) DRAWING NO:73863.0118 REVISION:00 DATE:13/12/05 ALSO APPROVED BY :STEVEN MANCHESTER (BRE COMPANY) DATE: 23/05/2019.</p>				
DATE	APPROVED	BY	CHKD	REVISION
23/05/2019	AP	SM	SM	00
BRE COMPANY (AS BUILT)				
<p>Copyright and other intellectual property rights in this document and all related documents, drawings, etc., including calculations, is vested in BTU and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.</p>				
<p>CLIENT:</p> 				
<p>BTU Southmoor Lane Havant Hampshire PO9 1JW</p>				
<p>PROJECT TITLE FULLERTON WTW ROMSEY ROAD, GODDWORTH CLATFORD, ANDOVER, HAMPSHIRE, SP117HR.</p>				
<p>DRAWING TITLE DSEAR DIGESTER & POST DIGESTER ELEVATION</p>				
<p>SHEET 4 OF 10</p>				
SCALE	PROJECT NO.		SITE UNIT NO.	
FULLERTO	639382		101246	
DATE	SCALE	NTS	MASTER NO.	
639382	NTS		AS	
DRAWING NO.				REVISION
KH. 639382.030.222960.A				A

ZONE LEGEND	REF	SITE AREA DESCRIPTION	ZONE	T CLASS	EXTENT OF ZONE (V-VERTICAL, H-HORIZONTAL) MEASURED FROM POINT OF POSSIBLE RELEASE
	A	PRIMARY DIGESTERS (X3)	0	2	INTERNALLY
	B	PRIMARY DIGESTER ROOFS (X3)	1	2	EXTERNALLY - 'H' TO BOUNDARY FENCE AND 'V' 3M
	C	POST DIGESTER STORAGE TANK (2) ROOF	1	2	EXTERNALLY - 'H' TO BOUNDARY FENCE AND 'V' 3M
	D	POST DIGESTER STORAGE TANK (2)	0	2	INTERNALLY
	E	POST DIGESTER STORAGE TANK (1)	1	2	INTERNALLY
	F	POST DIGESTER STORAGE TANK (1) OPEN ROOF	2	2	EXTERNALLY - 'H' TO BOUNDARY FENCE AND 'V' 3M



5.5.2 Digester 2

Zone 0 internally and zone 1 externally surrounding the Wesso valve on top of the digester.



Figure 6: Digester 2.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks & hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones not allowed to be taken into zoned areas. Signs present.	1	2	2
Lightening	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	3	2	6

The drawing illustrating the extent of the hazardous zoning around the digesters and post-digesters is included in section 5.5.1.



5.5.3 Digester 3

Zone 0 internally and zone 1 externally surrounding the Wesso valve on top of the digester.



Figure 7: Digester 3.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks & hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones not allowed to be taken into zoned areas. Signs present.	1	2	2
Lightening	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	3	2	6

The drawing illustrating the extent of the hazardous zoning around the digesters and post-digesters is included in section 5.5.1.



5.5.4 Post digester 1 (secondary digester)

There are two post digesters at Fullerton STC. Post digester 1 is open due to the roof collapsing. Post digester 2 is closed and the lid is still intact, although there did appear to be some buckling damage.

According to Southern Water’s MED 4004 April 2015,³¹ open top post digestion storage tanks are allocated a zone 1 internally and a zone 2 extending 1m upwards and horizontally.



Figure 8: Post digester 1, open.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	2	2	4

The drawing illustrating the extent of the hazardous zoning around the digesters and post-digesters is included in section 5.5.1.



5.5.5 Post digester 2 (secondary digester)

Post digester 2 is closed and the lid is still intact, although there did appear to be some buckling damage.

Zone 0 internally and zone 1 externally surrounding the top of the post digester.



Figure 9: Post digester 2, closed.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	2	2	4

The drawing illustrating the extent of the hazardous zoning around the digesters and post-digesters is included in section 5.5.1.



5.5.6 Polyelectrolyte

There are two polyelectrolyte dust hopper / dispenser units on site. One in a stand-alone unit next to the gas bag compound and post digesters, the second in inside the pump house building.

Following Southern Water’s MED 4004 April 2015³¹, the receiving vessel is allocated a zone 21 classification internally and the external area is allocated a zone 22 classification for 1m.



Figure 10: Polyelectrolyte dispenser 2, pump house.




Figure 11: Polyelectrolyte dispenser 1.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment or IP5x must be used as a minimum – see catalogued equipment.	2	2	4

POLYELECTROLYTE DISPENSER (X2) PLAN

DRAWING NO: KH.639382.030.ZZ2961 REVISION: A

- DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
- ALL IMAGES DENOTED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL.
- ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAINS SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.



CHECK PRINT INFORMATION
 RED - Item to modify
 GREEN - Comment for CAD
 BLUE - Modification complete
 YELLOW - Item for clarification
 Pen colours for print mark-ups

CHECK PRINT REF: A1
 PREPARED BY: _____ DATE: _____
 PRELIMINARY CAD CHECKED BY (if required): _____
 CAD CHECKED BY: _____ DATE: _____
 CHECKED BY: _____ DATE: _____
 REVIEWED BY: _____ DATE: _____
 REASON FOR ISSUE: _____
 AUTHORISE FOR ISSUE:
 AUTHORISED BY: _____ DATE: _____

CHECK PRINT DISTRIBUTION

ARC	
CIV	
ELE	
MEC	
PRO	
SER	
STR	
PPL	
HYD	
Tick for Distribution	

CURRENT VERSION INFORMATION
 THIS IS MORRISON DRAWING (DSEAR)
 DRAWING NO:73863.0115 / 0116 REVISION:00 DATE:21/25/01/19
 ALSO APPROVED BY: STEVEN MANCHESTER (BRE COMPANY)
 DATE:23/05/2019.

23/05/2019	AP	SM	SM	00	BRE COMPANY (AS BUILT)		
	DATE	ISSUED	CHKD	REVISED	REVISED	REASON FOR ISSUE	

Copyright and other intellectual property rights in this document and all related documents, drawings, etc., including calculations, is invested in BTU, and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.

CLIENT:







BTU
 Southmoor Lane
 Havant
 Hampshire
 PO9 1JW

PROJECT TITLE: FULLERTON WTW
 ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER,
 HAMPSHIRE, SP117HR.


DRAWING TITLE: DSEAR
 POLYELECTROLYTE DISPENSER PLAN

SHEET 5 OF 10

SITE UNIT: FULLERTON SITE UNIT NO: 101246
 DSN: 639382 SCALE: NTS MASTER REF: A3
 DRAWING NO: KH.639382.030.ZZ2961 REVISION: A

ZONE LEGEND	REF	SITE AREA DESCRIPTION	ZONE	T CLASS	EXTENT OF ZONE (V-VERTICAL, H-HORIZONTAL) MEASURED FROM POINT OF POSSIBLE RELEASE
	A	POLYELECTROLYTE DISPENSER	22	4	EXTERNALLY - 1M 'H' AND 1M 'V' EXTENDING TO FLOOR
					
					

POLYELECTROLYTE SILO - INTERNAL



DRAWING NO: KH. 639382.030.2Z2962.A REVISION: A

1. DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
2. ALL IMAGES DENOTED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL.
3. ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAIN SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.

CURRENT VERSION INFORMATION
 THIS IS MORRISON DRAWING (NOT AS BUILT)
 DRAWING NO 73863.0118 REVISION:00 DATE:13/12/05
 ALSO APPROVED BY :STEVEN MANCHESTER (BRE COMPANY)
 DATE: 23/05/2019.

23/05/2019	AP	SM	SM	00	BRE COMPANY (AS BUILT)
DATE	DRAWN	CHECKED	REVISED	REV	REASON FOR ISSUE

Copyright and other intellectual property rights in this document and all related documents, drawings, etc., including calculations, is invested in BTU, and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.



PROJECT TITLE: FULLERTON WTW
 ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER, HAMPSHIRE, SP117HR.




DRAWING TITLE: DSEAR POLYELECTROLYTE DISPENSER ELEVATION

SHEET 6 OF 10

SITE UNIT: FULLERTO SITE UNIT NO: 101246

FIG: 639382 SCALE: NTS MASTER SIZE: A3

DRAWING NO: KH. 639382.030.2Z2962.A REVISION: A

ZONE LEGEND	REF	SITE AREA DESCRIPTION	ZONE	T CLASS	EXTENT OF ZONE (V-VERTICAL, H-HORIZONTAL) MEASURED FROM POINT OF POSSIBLE RELEASE
ZONE 20 	A	POLYELECTROLYTE SILO	21	4	INTERNALLY
ZONE 21 					
ZONE 22 					



5.6 Gas storage

5.6.1 Boiler house

There are two boilers at Fullerton STC. They are both located in the boiler house. They use both natural gas and biogas.


A zone 2 hazardous area is allocated extending 1m around all gas flanges and fittings on both natural and biogas pipelines.



Figure 12: Boilers 1 & 2.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	2	2	4

Biogas and Natural Gas pipe flange



CHECK PRINT INFORMATION

RED - Item to modify
 GREEN - Comment for CAD
 BLUE - Modification complete
 YELLOW - Item for clarification
 Pen colours for print mark-ups

CHECK PRINT REF: A1

PREPARED BY: _____ DATE: _____

PRELIMINARY CAD CHECKED BY (if required): _____

CAD CHECKED BY: _____ DATE: _____

CHECKED BY: _____ DATE: _____

REVIEWED BY: _____ DATE: _____

REASON FOR ISSUE: _____



AUTHORISE FOR ISSUE:

AUTHORISED BY: _____ DATE: _____

CHECK PRINT DISTRIBUTION

ARC	
CIV	
ELE	
MEC	
PRO	
SER	
STR	
PPL	
HYD	

Tick for Distribution

DRAWING NO. KH.639382.030.2Z2963.A		REVISION A
1. DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE. 2. ALL IMAGES DENOTED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL. 3. ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAINS SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.		
CURRENT VERSION INFORMATION THIS IS (BRE COMPANY) DRAWING (NOT AS BUILT) APPROVED BY: STEVEN MANCHESTER (BRE COMPANY) DATE: 23/05/2019.		
23/05/2019	AP	SM
DATE	DRAWN	CHECKED
	SM	SM
	SM	A
	BRE COMPANY (AS BUILT)	
		REASON FOR ISSUE
Copyright and other intellectual property rights in this document and all related documents, drawings, etc., including calculations, is invested in BTU and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.		
CLIENT: 		
 BTU Southmoor Lane Havant Hampshire PO9 1JW		
PROJECT TITLE: FULLERTON WTW ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER, HAMPSHIRE, SP117HR.		
DRAWING TITLE: DSEAR BIOGAS AND NATURAL GAS PIPE FLANGE		
SHEET 7 OF 10		
DRAWN BY: FULLERTO	DATE ONLY: 101246	
DRAWING NO. 639382	SCALE: NTS	REVISION: A3
DRAWING NO. KH.639382.030.2Z2963.A		REVISION: A



5.6.2 Gas storage area

5.6.2.1 Double membrane gas bag


A zone 0 was allocated inside inner membrane, zone 1 in outer membrane and zone 2 around PRVs extending 3m. This agrees with Southern Water's MED 4004 April 2015⁽⁹⁾.



Figure 13: Double membrane gas bag.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	1	2	2

GAS HOLDER PLAN



DRAWING NO: KH. 639382.030.2Z2964.A REVISION: A

1. DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
2. ALL IMAGES DENOTED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL.
3. ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAINS SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.

CURRENT VERSION INFORMATION
 THIS IS MORRISON DRAWING (NOT AS BUILT)
 DRAWING NO: 73863.0118 REVISION: 00 DATE: 13/12/05
 ALSO APPROVED BY: STEVEN MANCHESTER (BRE COMPANY)
 DATE: 23/05/2019.

DATE	BY	CHKD	REVD	REV	REASON FOR ISSUE
23/05/2019	AP	SM	SM	00	BRE COMPANY (AS BUILT)

Copyright and other intellectual property rights in this document and all related documents, drawings, etc., including calculations, is invested in BTU and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.



PROJECT TITLE:
 FULLERTON WTW
 ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER,
 HAMPSHIRE, SP117HR.

DRAWING TITLE:
 DSEAR
 GAS HOLDER PLAN

SHEET 8 OF 10

SITE UNIT / WORKING: FULLERTO	SITE UNIT NO: 101246	
PRN: 639382	SCALE: NTS	SHEET SIZE: A3
DRAWING NO: KH. 639382.030.2Z2964.A	REVISION: A	

ZONE LEGEND	REF	SITE AREA DESCRIPTION	ZONE	T CLASS	EXTENT OF ZONE (V-VERTICAL, H-HORIZONTAL) MEASURED FROM POINT OF POSSIBLE RELEASE
	A	INNER GAS BAG	0	2	INTERNALLY
	B	OUTER AIR BAG	1	2	INTERNALLY
	C	AIR BLOWERS (X2)	2	2	INTERNALLY
	D	PRESSURE RELIEF VESSEL	2	2	EXTERNALLY - 3m 'V' AND 'H'



5.6.3 CHP

There are two CHP plants on site at Fullerton STC, however only one is in use. The operational CHP plant is located next to the gas bag compound.

The CHP plant is not allocated a zoned area. The CHP plant appeared to be similar to those at Budds Farm, Millbrook and Ashford and therefore the air flow through the CHP plant is sufficient to ensure a flammable atmosphere is highly unlikely to develop. The zone is based on the continual operation of the ventilation system.



Figure 14: CHP plant, Veolia.

5.6.4 Flare stack area

The flare stack at Fullerton STC is located inside the gas bag compound.

According to Southern Water's MED 4004 April 2015,^[3] the flare stack area is unclassified.

BRE concludes the area should be unclassified, however internally the pipework will be allocated a zone 0 classification.

The equipment in the flare stack area was catalogued to determine Ex certification.



Figure 15: Flare stack.



5.7 Diesel storage

The two diesel storage tanks on site at Fullerton STC appeared to be double-skinned as they were not within a bund. Both are located near the main reception building outside the boiler house.

As both diesel tanks are double skinned, no hazardous area classification exists outside the tanks.

According to guidance given in the "Energy Institute: Model code of safe practice Part 15 – Area classification code for installation handling flammable fluids"^[4] the diesel tanks were allocated a zone 1 internally above the liquid level.




Figure 16: Diesel tank 1.



Figure 17: Diesel tank 2.

Hazards	Control measures	Likelihood	Severity	Risk rating
Naked flames	No smoking policy on site except in designated areas. Signs present.	1	2	2
Welding / cutting: sparks and hot surfaces	Permit to work required before maintenance works can be undertaken.	1	2	2
Sparks from mobile phones	Mobile phones are not allowed to be taken into zoned areas. Signs present	1	2	2
Lightning	Exposed zoned areas fitted with protection.	1	2	2
Electrostatic discharge	Earth bonding of equipment.	1	2	2
Sparks from equipment	Ex rated equipment must be used – see catalogued equipment.	n/a	n/a	n/a

DIESEL TANK - DOUBLE SKINNED (X2)



DRAWING NO. KH.639382.030.ZZ2966.A REVISION A

- DO NOT SCALE. WORK TO DIMENSIONS SHOWN. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
- ALL IMAGES DERIVED ON THIS DRAWING REMAIN AS BUILT INFORMATION SUPPLIED BY (BRE) GLOBAL.
- ALL INFORMATION, BUT NOT LIMITED TO, SUPPLIED BY (BRE) GLOBAL TO REPRESENT AS BUILT INFORMATION FOR THIS DRAWING REMAIN SOLE PROPERTY OF THE SURVEY CONTRACTOR (BRE) GLOBAL.

CURRENT VERSION INFORMATION
THIS IS (BRE COMPANY) DRAWING (NOT AS BUILT)
APPROVED BY :STEVEN MANCHESTER (BRE COMPANY)
DATE: 23/05/2019.

23/05/2019	AP	SM	SM	A	BRE COMPANY
25/01/2019	AP	SM	SM	SB	BRE COMPANY (NOT AS BUILT)
DATE	DRWN	CHG	REV	REV	REASON FOR ISSUE

Copyright and other intellectual property rights in this document and all related documents, drawings, etc., including calculations, is invested in BTU and cannot be used or reproduced for any other purpose than that for which they have been created without the express permission in writing by BTU.

CLIENT:



BTU
Southmoor Lane
Havant
Hampshire
PO9 1JW

PROJECT TITLE
FULLERTON WTW
ROMSEY ROAD, GOODWORTH CLATFORD, ANDOVER,
HAMPSHIRE, SP117HR.

DRAWING TITLE
DSEAR
DIESEL TANK - DOUBLE SKINNED

SHEET 10 OF 10

DATE SENT: FULLERTO DATE REC: 10/246

PROJ: 639382 SCALE: NTS DRAWER: A3

DRAWING NO. KH.639382.030.ZZ2966.A REVISION A

CHECK PRINT REF: A1

PREPARED BY: _____ DATE: _____

PRELIMINARY CAD CHECKED BY (if required): _____

CAD CHECKED BY: _____ DATE: _____

CHECKED BY: _____ DATE: _____

REVIEWED BY: _____ DATE: _____

REASON FOR ISSUE: _____

AUTHORISE FOR ISSUE:

AUTHORISED BY: _____ DATE: _____

CHECK PRINT INFORMATION

RED - Item to modify
GREEN - Comment for CAD
BLUE - Modification complete
YELLOW - Item for clarification

Pen colours for print mark-ups

CHECK PRINT DISTRIBUTION

ARC	
CIV	
ELE	
MEC	
PRO	
SER	
STR	
PPL	
HYD	

Tick for Distribution

ZONE LEGEND	REF	SITE AREA DESCRIPTION	ZONE	T CLASS	EXTENT OF ZONE (V-VERTICAL, H-HORIZONTAL) MEASURED FROM POINT OF POSSIBLE RELEASE
ZONE 0	A	ABOVE LIQUID SURFACE	1		INTERNALLY
	B	WITHIN THE SKIN	2		EXTERNALLY
	C	AROUND BREATHER VALVE	2		EXTERNALLY
ZONE 1					EXTERNALLY 'V' + 'H' - 3m
ZONE 2					



Appendix A Additional photographs



Figure 18: Digester fence.



Figure 19: Post-digester fence.



Figure 20: Gas holder compound PRV.

7 FIRE RISK ASSESSMENT

The Site Fire risk assessments need to be stored with this Grab Pack.

Electronic link to the site Fire Risk assessment. [FRA - Fullerton STC 8-11-22 PS286 Rev B.pdf](#)

8 COSHH DATA SHEET

COSHH data sheets for chemicals used on site should be Kept in a folder with the Grab Pack.

Electronic link to the Southern Water COSHH data sheets - [COSHH \(southernwater.co.uk\)](https://www.southernwater.co.uk/coshh)