

ENVIROARM LIMITED

WOODCOTE WOOD QUARRY LANDFILL SITE

DUST MANAGEMENT PLAN AND DUST ASSESSMENT



REF: DA/WWQ/NRS/1.00/2023

Enviroarm Limited
597 Walsall Road
Great Wyrley
Nr. Walsall
Staffs WS6 6AE
Tel: 01922 412209
Mobile: 07801 980984

PARTICULATES RISK ASSESSMENT WOODCOTE WOOD QUARRY LANDFILL SITE AND NON-HAZARDOUS WASTE TREATMENT FACILITY

1. INVENTORY OF DUST EMISSIONS TO AIR

The main dust emissions to air from Woodcote Wood Quarry landfill and the associated treatment by screening, crushing and washing and inert landfill will be generated by the use of mobile plant and transport, ground works (such as inert recycling, engineered barrier lining works, and restoration activities) on site and to some extent the delivery of waste to the site and despatch of stone and soils from site. The majority of dust emissions will be area and fugitive emissions.

Site Machinery and Plant

Weighbridge
Crusher
Screener
Washer
Tractor with Water Bowser and Road Sweeper
3 x Wheeled Loaders
1 x Excavator
1 x Track Type Dozer

Bund Construction, Engineering Works and Restoration

Fugitive emissions of particulates will be generated during the construction of screening bunds, crushing and screening of soils, placement of the clay engineered geological barrier and restoration engineering works.

The closest cell construction and landfilling will be from houses will be approximately 100 metre from the permit boundary principally. The remainder of residential development and properties are currently over 225 metres north west, 350 metres south and south west of the site.

A tree-screening belt is well developed around the site. There are also fields between the site and the houses.

The Company will operate a series of dust mitigation measures to reduce the potential for dust emission. A water bowser will be used when required to wet the excavated material and control dust during landfilling and used for damping down any wastes that are thought to

need it in the recycling area. Drop heights can be controlled by matching appropriately sized excavator and dump trucks.

All crushers and the washing plant will be supplied with water for dust suppression. The Company proposed to consider “industry standard” matching for effective production with minimum environmental impact. The correct matching of machines will also help to prevent overloading of dump trucks and hence additional dust emissions.

Soil emplacement will be undertaken in phases on a localised basis with material brought from stock and spread using low ground pressure machinery on the same day and in accordance with MAFF Good Practice for Handling Soils. Seeding will take place as soon as possible to bind the surface and prevent wind scouring from the bunds.

Landfill Operations

The main source of the potential dust emissions from these activities will be from inherently dusty dry soils imported to the site, waste placement, compaction and emissions covered waste surfaces and removal of the waste from Phase 1. The delivery of waste to the site will be via a paved fully concreted site access road to the edge of the landfill cells. Lorries are to be limited entering the site. A large proportion of the lorries will delivery waste directly to the recycling and treatment facility and this will significantly reduce the traffic travelling across the daily cover.

Small amounts of inherently dusty waste will be accepted at the site. This will include dry soils, foundry sands and some dry construction and demolition wastes. The majority of wastes are delivered in sheeted vehicles (under Duty of Care) and handled with care to minimise dust escape. The only emissions of dust which should take place therefore, if the waste is disturbed during blading out of the material during landfilling and compaction. Exposed clays and stockpiled restoration and cover materials could dry out during summer months and have potential to become windblown. This will be prevented by damping down periodically over the landfill and quarry using a tractor and water bowser, obtaining water from the surface water sump in the quarry.

All incoming wastes will be tipped for the majority of cases in the treatment area, however unsuitable inert wastes such as wet soils and soils with a high clay and silt content will be sent directly to active disposal area, spread and compacted by a landfill plant. The number of traverses the plant makes, and thus disturbance will be restricted to the minimum requirement (3-5 passes).

If the soil cover cannot be restored immediately then these areas will be watered and left inactive so a crust would form and seal the surface

to wind blow-off. This measure will be highly effective for as long as vehicles do not traverse the compacted material and break the surface crust.

Non-Hazardous Waste Recycling Area

The main source of the potential dust emissions from these activities will be from inherently dusty wastes imported to the site, waste tipping and emissions from the crushing and screening and yard surfaces. Waste will be normally transported to the site in covered tipper lorries.

It is anticipated that construction and demolition type waste and road plannings will comprise the main bulk of waste deliveries to the inert recycling area. The remainder will be a soils suitable for screening and recovery only. No waste will be putrescible. None of the materials are considered to have bio-aerosols, which would contain airborne endotoxins from bacteria and fungal spores, and thus the material is unlikely to cause breathing problems for on-site staff.

Small amounts of inherently dusty waste will be accepted at the site, primarily tipped directly into designated stockpiles then crushed and screened. This will include dry soils which will be screened only and construction and demolition wastes which will be crushed and screened. The majority of soils are delivered in sheeted vehicles (under Duty of Care) and handled with care to minimise dust escape. The only emissions of dust which should take place therefore, is if the material is disturbed during loading into the crusher or screener or for off-site removal. Stockpiles could dry out during summer months and have potential to become windblown. This will be prevented by damping down periodically using either the screeners or water obtained from on site.

The crusher and wash plant have dust suppression available to use at all times.

All incoming materials will be tipped in the active recycling and processing area.

Stockpiles

Long-term stockpiles of restoration material will be created within quarry. The stockpiles will comprise subsoil and topsoil and will not exceed 4 metres in height. These may be a potential source of dust.

Long-term stockpiles of soil making materials will be created within the treatment area footprint. The stockpiles will comprise subsoil, topsoil, 6F2, 6F5, and 20-40mm aggregates and road sub-base and will not exceed 4 metres in height. These may be a potential source of dust.

The operator will use conditioned on-site clays and material brought to site for the geological barrier and liner material for the permit area.

Stockpiles can be dampened down using a water bowser.

A number of best practice measures will be implemented to keep the fugitive emission of dust to a minimum and to clean up any deposits that do occur:

- ❑ Stockpiles of different materials will be clearly delineated to avoid mixing and lightly tamped to confine moisture and seal against erosion;
- ❑ Stockpiles will be graded to minimise wind blown dust and normally be kept damp by the application of water in sprays, as and when necessary, but particularly during periods of dry weather. The operator will provide and maintain at all times an adequate supply of water for watering equipment on site.
- ❑ All long-term screening mounds retained for longer than one growing season will be seeded to grass and have fast growing tree species planted such as alder and silver birch at the earliest opportunity and adequately maintained for their active life.
- ❑ Location of stockpiles to take advantage of shelter from the prevailing wind. The operator proposed to retain for as long as possible stockpiles within the void in the inert recycling area set behind a large bund and this will be the last phase of infilling and is as far from residential properties as possible.
- ❑ Recycled materials put in piles will have perimeter walls that are up to 4 metres in height so that the recycled material; can not be seen from the railway. No stockpiles occur on the landfill,

Site Perimeter

The site has fencing which to 1 metre high and does not allow cattle on to the site.

The entrance has trees on either side and the site has trees around it.

Movement of Haulage Vehicles

The potential main long-term source of the potential dust emissions will be the movement of haulage vehicles and slave dump trucks across the site on the access road and temporary haul roads to the tipping face and working quarry areas.

The internal unpaved haul roads within the site extension and from the material excavation area could potentially be a significant source of dust, which may become entrained and distributed by passage of

vehicles. Further general factors include (1) a continuous breakdown of the surface layer and potential dust emission via a passage of vehicles, (2) liberation of loose material during excavation works and on any haul roads by wind blow off and (3) loading and off-loading operations.

The most effective abatement measures for the control of fugitive dust on roads are good road design, layout, repair and maintenance, and cleaning. The following measures are proposed by the operator.

- The most regularly adopted, simple and effective method of reducing fugitive dust emission is by watering of haul roads during dry weather. Total suspended particular dust emissions could be reduced by up to 97% by the application of water to haul roads. The operator will provide sufficient bowser capacity on site at all times.
- A road sweeper will be available to regularly sweep the access road of excess dirt and debris brought to site when needed.
- All operators vehicles will be fitted with upward facing exhausts and radiator cowl. The use of vehicles with upward pointing exhausts and radiator cowls is moderately effective in reducing potential dust emissions.
- The design of haul roads will be undertaken to avoid sharp corners or steep gradients, which would encourage sharp braking. The layout of haul roads will be such to distance them from the sensitive receptors. Access to the active cells will be along a central core road, which will mean that haul roads are oriented as far as possible from residential housing.
- The regular grading of site haul roads removes loose material from the surface, it also increases fuel efficiency and minimises “wear and tear” on the vehicles and mobile plant. It is also a highly effective method of dust control as it removes loose debris and mud, one of the main potential sources of dust.

There are procedures for controlling fugitive emissions of dust from landfill operations and the relevant guidance will be adhered to. In determining their proposed abatement procedures the applicant consulted the procedures and practices recommended by the CIRIA, Site Planning Conditions, and their own operational procedures. The following Table 1 summarises the proposed dust mitigation measures.

Table 1: Summary of the proposed dust/bioaerosol control measures and estimate of effectiveness

Site Operation	Dust/bioaerosol control measures	Estimate of effectiveness
Cell construction and restoration	Water bowsters to be used as required and rain gun	High
	Avoid material handling during adverse weather conditions	High
	Reduction of drop height by matching sizes of excavator and dump tracks	High
Landfill operations	Water bowsters to be used as required	High
	Progressive restoration minimises the area exposed to wind erosion	Moderate
	Drop heights to be minimised at all times	Moderate
	Avoid double handling of material	Moderate
	Restrict access to restored areas	High
Stockpiles	Stockpiles graded to minimise wind blown dust	Moderate
	Water sprays to be available for stockpiles	High
	Discharged heights to be minimised where practicable	Moderate
	Location of stockpiles to take advantage of shelter from wind	Moderate/High
	Long-term screening mounds graded and seeded to minimise wind blown dust	High
Haul & access roads	Optimise separation distances to sensitive receptors	High
	Water bowser to be used as required	High
	Concreted site access road	High
	Use of road sweeper on concreted road when required	Moderate/High
Site general	Continuous dust monitoring across the site	Moderate
	Weather information assessment	High
	Dust complaints response system	High
Inert Treatment operations	Water bowsters and or hoses to be used as required	High
	Drop heights to be minimised at all times	Moderate
	Avoid double handling of material	Moderate

2. LOCAL WEATHER AND POLLUTION POTENTIAL

Wind data was assessed from Shawbury in terms of wind pattern, and the wind roses which have been generated. It shows that overall south-westerly winds have high frequency and higher wind speed. These winds are associated with Atlantic cyclones and thus lead to both high winds and precipitation. Easterly and southerly winds are equally dominant during the cold part of the year (October – March), whereas south-westerly and north-easterly winds are more common during the warm season. Strong winds are common throughout the year, as well as variable and light winds (2m/s), which account for 25% of time, and 2.5% calm weather conditions. The annual average wind speed is 16 knots.

In terms of dust pollution the local wind pattern would expose some potential local receptors. The most sensitive to the prevailing winds are

situated to the north and northwest of the site development and permit footprint, though there is a property 100metres south west of the site.

Potential dust emissions will be reduced during low wind periods and rainy/wet days. Based on data from Birmingham Airport on average there are 150 wet or rainy days per year. Therefore, dust emissions are suppressed for over 40% of days and the ground may remain wet for subsequent days. Generally light local winds (average 2m/s- 4 m/s) are below the critical wind speed at which dust becomes airborne, for most mineral dusts this is 5.6m/s. On average during 10% of time wind speed (average hourly, all directions) exceeds 5.6m/s marker, which promotes generation of dust. Overall, there will be few days a year when the ambient conditions (adverse wind speed and direction, coupled with dry weather) will favour the transport of significant dust from the landfill site towards the nearest receptors.

3. RECEPTORS TO DUST

Local Settlements

Woodcote Wood Quarry Landfill and Non-Hazardous Treatment Facility is located 250 metres. The ground surrounding the quarry is generally flat but rises to the south towards DR3 and DR6. The site north, east and south east has sparse residential surroundings with the majority of properties located on the southern fringe. The site has a tree screen belt all around and soil bunds currently in place or proposed additional screening as part of the landfill development programme.

The closest properties to the application site are: Woodcote Hall north/northwest 250 metres away, Brandon Court 400 metres north, Chadwell Lane 350 metres to the north east, Bloomsbury 350 metres south east of the site and Pine Ridge 100 metres south west of the site.

As potential receptors to the emissions from the landfill, and quarry site development these properties will be influenced by the local wind rose and the topography. The prevailing winds from south-westerly sector would blow any arising emission towards the DA2.

With respect to fugitive emissions of dust, properties are considered vulnerable within c.500m (the Department of Environment (DoE) publication 'Environmental Effects of Surface Mineral Workings (1991)') but the distance varies with local topography and prevailing wind. Severe impacts from dust are most likely, without mitigation, within 100m, but receptors can be affected at up to 250m. The nearest properties to the site are physically within 100 metres of the boundary upwind of the site.

DR1 is just to the north-west of the landfill and Pine Ridge is south west of the non-hazardous treatment facility.

Wildlife

The site is surrounded by trees. The results of the Habitat Survey concluded that flora and fauna associated with the land and its margins are typical of modern quarries and previously used for agriculture and has little nature conservation interest. The flora and fauna associated within the site exhibit greater diversity but do not contain any protected species or habitats.

The site is therefore not likely to have any impact on wildlife locally and

Fluvial Environment

The inert recycling area and landfill site is not near to a tributary or brook.

The fluvial environment has little potential for any major deposition and the brook is fast flowing and therefore any deposition would be quickly diluted and dispersed.

Highways and public rights of way

Traffic on the adjacent carriageway (A41) and users of a number of the site adjoining public paths may potentially be affected by fugitive emissions of dust, though these are to the north and south of the site. Vehicles use the A41 to gain access to the site.

4. **AIR QUALITY AT LOCAL RECEPTORS**

Shropshire County Council have completed the Statutory Air Quality Assessments (an inventory of emissions to air in the Metropolitan Borough), based on the current and the DEFRA objectives for 8 main pollutants (SO₂, CO, NO₂, O₃, PM₁₀, lead, benzene, 1,3-butadiene). The current ambient air quality for Oak Farm Quarry with regard to PM₁₀ therefore accords with the NAQS objectives.

The national archive for the regulated pollutants has been obtained from the www.airquality.co.uk website for the purpose of this assessment.

Both current and the projected background concentrations of pollutants in the area are well below the National Air Quality Standards

The Council does not undertake any ambient air quality monitoring in the vicinity of the site. With the exception of dust nuisance caused by operations of site, ambient air quality at all local receptors is understood to be representative of that in urban areas.

5. RECEPTOR SENSITIVITY TO DUST

Dust management procedures have been designed for Dorrington Quarry treatment and inert landfill site to reduce the potential dust generation and the cause for nuisance. When properly implemented there will be residual fugitive emissions of dust from the site. The following receptors were identified as having medium to high sensitivity to emissions of particulates from the site development:

- DR1 Woodcote Hall – 250 metres away is downwind the site. The area has a dense thick tree line which will be retained at the landfill and fields. The potential dust issues are dealt with in the dust management plan.
- DR2 is 400metres to Brandon House downwind of the site.
- DR3 is 350 metres north east of the site downwind. The potential dust issues are dealt with in the dust management plan.
- DR4 Bloomsbury is 400 metres from the site to the southeast.
- DR5 Pine Ridge is 100 metres southwest of the treatment area.
- DR6 is 400 metres from the non-hazardous treatment area.

Table 2 Source-Pathway-Receptor Risk Assessment, see Appendix 12

Source	Pathway	Receptor
Landfill	Air- Inert Landfill Area	DR1
Landfill	Air- Inert Landfill	DR2
Landfill	Air- Inert Landfill	DR3
Landfill and Non-Hazardous Waste Treatment	Air- Recycling Area and Inert Landfill	DR4
Landfill and Non-Hazardous Waste Treatment	Air- Recycling Area and Inert Landfill	DR5
Landfill and Non-Hazardous Waste Treatment	Air- Recycling Area and Inert Landfill	DR6
Non-Hazardous Waste Treatment	Air- Non-Hazardous Waste Treatment	DR7

Landfill and Non-Hazardous Waste Treatment	Air- Recycling Area and Inert Landfill	HA1
None	None	HA2-HA6
Landfill and Non-Hazardous Waste Treatment	Air-Inert Recycling Area and Landfill	IR1
None	None	SW1 to SW6

Stockpiles and inert waste in the recycling area will be no more than 4 metres high.

The site is checked for dust deposits when it is windy.

6. PARTICULAR MATTER MANAGEMENT AND MONITORING

5 monitoring points have been proposed to cover DR1, DR2, DR3, DR4 and DR6 and are shown on the attached drawing.

The proposal is for use of dust gauges of drop out type to be used twice per annum on a monthly basis. The benefits of the gauges are;

- Higher collection efficiency and considerably lower cost than the BS1747Pt1 deposit gauge
- Bird guard reduces risk of polluted samples from bird strikes
- Foam dust trap reduces sample contamination from falling leaves, etc. and prevents splash-out
- Large capacity collecting bottle will accommodate 120mm rain (240mm with the 10-litre bottle) and has wide neck permitting easy access for cleaning and removal of deposits.
- Tripod base, which can be spiked down, ensures stability on uneven surfaces
- Powder-coating and anodizing gives durability in hostile environments
- Bottle seal available for improved sample security

7. HOUSEKEEPING ON SITE

Site roads will be swept on a regularly basis.

Crushers and screeners will have water supply.

The tractor can be used to sweep roads if necessary.

A road sweeper can be hired if needed but to date has not been required.

Stockpiles will be kept at such heights as to not be seen and can be dampened down when necessary.

Any days where there could be dust will be monitored and any actions taken will be included in the site diary.

APPENDIX DMP1:

Particulate Matter Report Form

Dust Monitoring Sheet

Dust Monitoring Report Form								Date:
Location	1	2	3	4	5	6	7	8
Time of Test/Observation								
Weather Conditions								
Temperature								
Wind Strength								
Wind Direction								
Intensity								
Duration of Test/Observation								
Constant/Intermittent								
Is dust visible?								
Receptor Sensitivity								
Is the Source Evident?								
Any other Comments or Observations								

Dust Monitoring Sheet

March 2023

Report No. DA/WWQ/NRS/1/00/2023

APPENDIX DMP2:


Particulate Matter Complaint Report

Dust Complaints

Dust Complaint Information Form	
Time and Date of Complaint:	Name and Address of Complainant:
Telephone Number of Complainant:	

Date of Dust:	
Time of Dust Release/Complaint	
Location of Dust if Not at Above Address:	
Weather Conditions (i.e. dry, rain, fog, snow):	
Wind Strength (none, light, steady, strong, gusting):	
Temperature (very warm, warm, mild, cold):	
Wind Direction:	
Complainant's Description of Dust: <ul style="list-style-type: none"> • Damage/visual impact: • Intensity: • Duration: • Constant or Intermittent: • Any Other Comments regarding Dust: 	
Are there any other complaints relating to the installation, or to that location? (either previously or relating to the same exposure):	
Any Other Relevant Information:	
Activities on Site at the Time:	
Do You Accept that Dust Release likely to be From Site:	
Actions Taken:	
Form Completed By:	Date and Signature:


DRAWINGS



Legend

Permit Boundary

Wind Rose



Based upon the Ordnance Survey maps with the permission of the controller of Her Majesty's Stationery Office, © Crown Copyright reserved. Licence number AR100019096.

Client: **NRS Woodcote Aggregates Limited**

Project: **Woodcote Wood Quarry Landfill**


Title: **Source Pathway Receptor**

CAD Ref: EL/WQL/1	Version: 1	Drawn by: ARM	Scale: Plan 1:2500@A3	Date: March 2023
----------------------	---------------	------------------	--------------------------	---------------------



ENVIROARM LIMITED

Drawing:
ESSD 12



Legend

— Permit Boundary

Based upon the Ordnance Survey maps with the permission of the controller of Her Majesty's Stationery Office, © Crown Copyright reserved. Licence number AR100019096.


Client: **NRS Woodcote Aggregates Limited**

Project: **Woodcote Wood Quarry Landfill**

Title: **Site Layout and Waste Deposition**

CAD Ref: EL/WQL/1	Version: 1	Drawn by: ARM	Scale: Plan 1:2500@A3	Date: February 2023
----------------------	---------------	------------------	--------------------------	------------------------

Drawing: **ESSD 4**


ENVIROARM LIMITED



Legend
 — Permit Boundary

Based upon the Ordnance Survey maps with the permission of the controller of Her Majesty's Stationery Office, © Crown Copyright reserved. Licence number AR100019096.

Client: **NRS Woodcote Aggregates Limited**

Project: **Woodcote Wood Quarry Landfill**

Title: **Infrastructure**

CAD Ref: EL/WQL/1	Version: 1	Drawn by: ARM	Scale: Plan 1:2500@A3	Date: March 2023
----------------------	---------------	------------------	--------------------------	---------------------

Drawing: **ESSD 13**


ENVIROARM LIMITED