

Transport, Environment & Design

Zig Zag Quarry Environmental Setting and Site Design Report

January 2026



Document Control Sheet

Project Reference: HCE0269
Project Title: Zig Zag Quarry
Document Subject: Environmental Setting and Site Design Report
Document Reference: HCE0269.ESSD.Rev3
Author: Jamie Howourth
Checked: Alex Large
Client: BT Jenkins Limited
Initial Issue Date: 04 September 2024

Revision of Issue

Revision	Revision Author	Checked	Date
1	Jamie Howourth	Alex Large	12-Sept-24
2	Alex Large	Jamie Howourth	21-Nov-25
3	Alex Large	Jamie Howourth	30-Jan-26

Distribution

Organisation	Contact	Issue Format & No. of Copies *	Date
BT Jenkins Ltd	Russ Lowton	D1 DRAFT	04-Sep-2024
Harleyford Aggregates	Richard Agnew [RJA Planning Services]	D1 DRAFT	04-Sep-2024
BT Jenkins Ltd	Russ Lowton	D1	12-Sep-2024
Harleyford Aggregates	Richard Agnew [RJA Planning Services]	D1	12-Sep-2024
BT Jenkins Ltd	Russ Lowton	D1	21-Nov-2025
Harleyford Aggregates	Richard Agnew [RJA Planning Services]	D1	21-Nov-2025
BT Jenkins Ltd	Russ Lowton	D1	30-Jan-2026
Harleyford Aggregates	Richard Agnew [RJA Planning Services]	D1	30-Jan-2026

** D denotes digital copy / P denotes paper copy*

COPYRIGHT

© This Report is the copyright of Horizon Consulting Engineers Limited. Unauthorised reproduction or usage by any person other than the Client identified above is strictly prohibited.

Horizon Consulting Engineers Limited accepts no liability or responsibility for use of this document for purposes other than those originally intended.

Horizon Consulting Engineers Limited Registered in England and Wales. Registration Number: 8219514

Contents

Document Control Sheet	
Revision Schedule	
1. Introduction	1
1.1 Commission	1
1.2 Background & Planning Permission	1
1.3 Waste Recovery	3
1.4 Operator	3
1.5 Report Author	3
1.6 Report Structure	3
2. Site Details	4
2.1 Site Location & Access	4
2.2 Site Classification	4
2.3 Site Boundary & Security	4
2.4 Adjacent Waste Management Activities	5
2.5 Site Context	5
2.6 Interaction with Existing Operations	5
2.7 Impact of Climate Change	6
3. Conceptual Site Model	7
3.1 Conceptual Site Model	7
3.2 Gas Risk Assessment	7
3.3 Hydrogeological Risk Assessment	8
3.4 Stability Risk Assessment	8
4. Compliance Points	9
4.1 Groundwater	9
4.2 Surface Water	9
5. Pollution Control Measures	10
5.1 General & Phasing	10
5.2 Basal & Side Slope Engineering	11
5.3 Basal Liner Soil Chemistry	11
5.4 Surface Water Management	12
5.5 Amenity	13
5.6 Post Closure Controls (Aftercare)	13
5.7 Incident Response & Quarantine Area	14
6. Monitoring	15
6.1 Weather	15
6.2 Gas Monitoring & Infrastructure	15
6.3 Surface Water Monitoring	16
6.4 Groundwater Monitoring Infrastructure	16
6.5 Groundwater Monitoring	16
6.6 Amenity Monitoring	16

Tables

Table 6-1: Ground Gas Monitoring Frequency	15
--	----

Appendices

Appendix A	Horizon Drawings
Appendix B	Drawing Reproduced from FRA
Appendix C	Drawing Reproduced from 2021 HRA

Revision Schedule

Revision	Author	Description	Date
1	Jamie Howourth	Minor updates to take into account comments including surface water management, interaction with existing operations and updates to Site Infrastructure Plan.	12-Sep-2024
2	Alex Large	Report updated in 2025 to reflect changes to other permit reports (e.g. Gas Risk Assessment, Hydrogeological Risk Assessment, Dust & Emissions Management Plan).	21-Nov-2025
3	Alex Large	New Section 5.3 added in response to query from Environment Agency.	30-Jan-2026

1. Introduction

1.1 Commission

- 1.1.1 Horizon Consulting Engineers Limited (Horizon) was commissioned by BT Jenkins Limited (BTJ or “the Client”) behalf of the Operator (Harleyford Aggregates Limited) to prepare an updated Environmental Setting and Site Design Report (ESSD) for Zig Zag Quarry in support of an application to vary the existing Environmental Permit (Reference: HB3705XG). Zig Zag Quarry is located to the north of the town of Kingskerswell, Newton Abbot, Devon, TQ12 5AT.
- 1.1.2 A variation is required to the existing Environmental Permit to facilitate the final restoration of the Site under Devon County Council (DCC) Planning Permission Reference DCC/4339/2023.
- 1.1.3 The overarching aim is to infill the void, restoring the Site to pre-quarrying levels. The Site is to be restored to a long-term end use of pastoral grazing fields separated by Devon hedge banks together with scrub and woodland habitats.
- 1.1.4 A previous ESSD report¹ was prepared by Aardvark EM Limited (Aardvark) in 2021 to support the original environmental permit application. This version of the ESSD report has been prepared by Horizon to support a substantial variation to the existing permit increasing the mass of material to be deposited to circa 1.5 M tonnes, in line with both the approved 2024 Waste Recovery Plan (WRP²) and Planning Permission.

1.2 Background & Planning Permission

- 1.2.1 Zig Zag Quarry (the Site for the purposes of this report) is an existing sand and gravel quarry located approximate 2 km south-east of Newton Abbot and immediately north of the village of Kingskerswell. The approximate centre of the Site is located at Ordnance Survey grid reference: 288033E, 069043N. A Site Infrastructure Plan (**Drawing 0269.103**) is included in **Appendix A** with photographs showing the Site in Appendix C of the CSM report³.
- 1.2.2 The Site occupies an area of approximately 9.44 hectares and is bound by Torquay Road to the west and Under Way to the south. The Yew Tree Walk forms the eastern and northern border of the Site.
- 1.2.3 The Site comprises one void which slopes down from the north and east to a low point at the Site entrance in the west. The contour plans (see Appendix A in the CSM report³) show existing ground levels drop steadily around the perimeter of the Site from a high point of circa 87 m AOD in the north-east corner. The most northerly point is at an elevation of circa 65 m AOD, with the entrance in the west of the Site at an elevation of circa 34 m AOD.
- 1.2.4 A previous WRP⁴ for the Site (henceforth referred to as the “2019 WRP”) was approved by the EA on 23 December 2019 (EA Letter Reference: EPR/HB3705XG/A001) with the existing Environmental Permit (reference: EPR/HB3705XG) subsequently granted on 01 December 2021.

¹ Aardvark (April 2021) Zig Zag Quarry. Environmental Permit Application. Environmental Setting & Site Design Report. Ref: 1922-R005. Rev. Final v2

² Horizon (April 2024) Zig Zag Quarry. Waste Recovery Plan. Ref: HCE0269.WRP.Rev2

³ Horizon (November 2025). Zig Zag Quarry. Conceptual Site Model. Ref: HCE0269.CSM.Rev3

⁴ Aardvark (20 December 2019) Zig Zag Quarry Environmental Permit. Waste Recovery Plan. Ref: 1922-R001. Revision: FINAL 2

- 1.2.5 The 2019 WRP⁴ enabled the partial infilling of Zig Zag Quarry, plus the silt lagoons associated with Aller Quarry to the north to meet the restoration requirements as per the 2016 Planning Permission. Along with available indigenous material, a total of 285,000 tonnes of suitable material was approved for import in 2019 to support restoration works.
- 1.2.6 The import of suitable material has been undertaken both under the CL:AIRE DOWCOP⁵ scheme and the existing Environmental Permit with reference to the approved quantities in the 2019 WRP⁴. The import of material under the CL:AIRE DOWCOP is reported in a standalone Verification Report⁶.
- 1.2.7 Zig Zag Quarry is now subject to Planning Consent DCC/4339/2023, which was granted by Devon County Council (DCC) on 03 July 2023. The approved 2023 restoration scheme requires the import of a further 1.5 million tonnes of inert waste in order to provide a safe and stable landform that is in keeping with the surrounding landscape. Drawings from the 2023 Planning Permission are included in Appendix A of the CSM report³. The following observations are made:
- The 2023 restoration scheme changes the restoration and aftercare proposals at the Site. For example, the 2016 restoration scheme provided for a step-down profile from Milber Lane to the base of the quarry. This is no longer the case on the basis that the retail sales area and plant site will no longer be retained (it was originally envisaged this area would be used for the continued import and sale of construction material);
 - The 2016 restoration scheme excluded the eastern side of the quarry; this is no longer the case with the 2023 restoration scheme;
 - The 2023 restoration scheme looks to reverse the decline in agricultural practices, particularly species rich grassland and Devon hedge banks. The 2023 restoration scheme will facilitate the long-term use of the Site for an economically beneficial purpose (pastoral farming);
 - Works associated with the 2023 restoration scheme are planned to take place in three phases, over a circa ten-year period;
 - A requirement for topsoil to complete the restoration is set out within the agreed landscaping plan⁷ and includes 150 mm cover in grassed areas, locally deepened to 400 mm in some plant bed areas. The topsoil should conform to BS3882:2015⁸.
- 1.2.8 This ESSD report has been prepared with reference to Environment Agency (EA) guidance and report template for ESSD reports⁹ as part of the substantial variation to fully restore the Site in accordance with the 2023 Planning Permission. To reiterate, this 2025 ESSD report only relates to Zig Zag Quarry and does not include the Aller Quarry to the north, albeit Aller Quarry remains within the Environmental Permit boundary. A plan showing the Site boundary and Permit boundary is included in Drawing 0269.101 of Appendix D of the CSM report³.

⁵ CL:AIRE (March 2011) The Definition of Waste: Development Industry Code of Practice. Version 2

⁶ Horizon (July 2021) Zig Zag Quarry. DOWCOP Verification Report. Ref: HCE0269.VR.Rev1

⁷ Swan Paul Partnership (2023). Zig Zag Quarry, Aller. Landscape Planting Plan. Ref SPP09

⁸ BSI (2015). BS3882:2015 – Specification for topsoil

⁹ <https://www.gov.uk/guidance/landfill-operators-environmental-permits/what-to-include-in-your-environmental-setting-and-site-design-report> [Accessed 22 May 2024]

1.3 Waste Recovery

- 1.3.1 The EA has confirmed (letter dated 22 April 2024, reference EPR/HB3705XG/P002) that the proposed restoration works associated with the 2023 Planning Permission is agreed to be a recovery activity.

1.4 Operator

- 1.4.1 The permit is held in the name of the Site owner, Harleyford Aggregates Ltd. BT Jenkins will continue to be the Operator of the permit on behalf of Harleyford Aggregates.

1.5 Report Author

- 1.5.1 This ESSD report has been prepared by Horizon Consulting Engineers Ltd (company number 08219154) and approved by Dr Hailey Tamblyn. Dr Tamblyn is a Chartered Civil Engineer with a PhD in Mathematical modelling of landfill biodegradation processes. Dr Tamblyn has more than 20 years professional experience as an environmental engineer, is a Qualified Person under the CL:AIRE Development Industry Code of Practice and holds WAMITAB certificates for the treatment and transfer of hazardous waste plus landfilling of non-hazardous waste.

1.6 Report Structure

- 1.6.1 This ESSD report sets out the details of the conceptual model developed for the Site along with proposed installation design, control measures and monitoring based on the Site's environmental setting. The remainder of this report is structured as follows:
- Section 2 sets out the Site details and some of the key features of the Site's environmental setting and site design;
 - Section 3 summarises the output of the CSM, and the subsequent risk assessments undertaken;
 - Section 4 presents details of the compliance points;
 - Section 5 outlines the proposed essential and technical precautions to be adopted during the restoration works such that the assumptions in the hydrogeological assessment are met; and
 - Section 6 sets out details of proposed scope and nature of monitoring including proposed trigger levels and compliance limit.

2. Site Details

2.1 Site Location & Access

- 2.1.1 The Site is located approximately 2 km south-east of Newton Abbot and immediately north of the village of Kingskerswell in Devon. The approximate centre of the Site is located at Ordnance Survey grid reference: 288033E, 069043N. A plan showing the site location (including permit boundary) is in Appendix D of the CSM report³ (Drawing 0269.101).
- 2.1.2 The Site is accessed off Torquay Road, with the access located towards the south-west of the Site. The grid reference of the access is 287847E, 068976N.

2.2 Site Classification

- 2.2.1 The Site has an existing bespoke Environmental Permit for the deposit of waste for recovery. The waste recovery activities that will continue to be carried out at the Site as defined under Annex II of the Waste Framework Directive can be summarised as follows:
- R5: Recycling or reclamation of other inorganic materials'
 - R10: Land treatment resulting in benefit to agriculture or ecological improvement; and
 - R13: Storage of wastes pending any of the operations numbered R1 and R12 (excluding temporary storage, pending collection, on the site where it is produced).

2.3 Site Boundary & Security

- 2.3.1 No change to the permit boundary is proposed as part of this significant permit variation however further deposition is only planned within the Zig Zag Quarry area, refer to Site Infrastructure Plan (**Appendix A**).
- 2.3.2 Lorries will continue to enter the Site from the access off Torquay Road, pass over the weighbridge and drive to the deposition area. All lorries leaving the Site will exit via the weighbridge back onto Torquay Road.
- 2.3.3 The boundary of the permitted area will continue to be kept secure throughout the works to prevent unauthorised access. Post and wire fencing and, in some areas, dense vegetation and steep slopes, ensures a high level of security around the Site and deterrence to trespassers.
- 2.3.4 The boundary is inspected at least once per week by the Operator to check integrity. CCTV security cameras are installed at the Site, with associated movement sensors. A third-party security firm is retained to respond out-of-hours to any potential security breaches.
- 2.3.5 Equipment and tools are predominantly stored in the office building buildings located to the west of the Site near the entrance as shown on the Site Infrastructure Plan (**Appendix A**). Doors and windows are reinforced against vandalism as necessary. A padlocked gate is present at the entrance to the Site.
- 2.3.6 All site visitors are required to sign the visitors book on entry, and again on exiting the Site. The exception is drivers of vehicles depositing waste at the Site who are required to remain in their vehicles at all times.

2.4 Adjacent Waste Management Activities

- 2.4.1 With reference to the Envirocheck report (Appendix B of the CSM report³), there are no active registered landfill and waste facilities within a 500 m radius of the Site, other than the existing deposit for recovery permit on-Site.
- 2.4.2 Historical landfill sites within a 1 km radius include:
- **Colesville Quarry.** Historical landfill located approximately 360 m north-west of the Site, no details on waste types or dates available.
 - **Craxford, Kingskerswell.** Landfill accepting construction, demolition and dredging waste, licence expired.
 - **South Quarry.** Historical landfill accepting household waste, located approximately 850 m west of the Site. No dates available.

2.5 Site Context

- 2.5.1 The Site comprises one void which slopes down from the north and east to a low point at the Site entrance in the west. The contour plans (see Appendix A of the CSM report³) show existing ground levels drop steadily around the perimeter of the Site from a high point of circa 87 m AOD in the north-east corner. The most northerly point is at an elevation of circa 65 m AOD, with the entrance in the west of the Site at an elevation of circa 34 m AOD.
- 2.5.2 Sensitive receptors in the vicinity of the Site are shown on the Sensitive Receptors Plans (Appendix D of the CSM report³).

2.6 Interaction with Existing Operations

- 2.6.1 Imported subsoil will be brought to the relevant deposition area using existing internal half roads and tracks and unloaded. The subsoil will then be moved into position by bulldozer and deposited in layers.
- 2.6.2 Quarry operations are drawing to a close with the final mineral extraction process being carried out in the vicinity of the main plant processing area. It is anticipated that this will be completed within the next 12 months. Due to the location of the permitted operations' first phase, there will be limited interaction between quarry operations and permitted operations.
- 2.6.3 The existing storage and distribution yard at the front of the Site (towards south-west) will be retained and remain operational throughout the restoration period.
- 2.6.4 The bridleway and footpath that runs along the northern boundary of the Site will not be affected by the proposed restoration. The existing storage and distribution yard at the front of the Site (towards south-west) will be retained and remain operational throughout the restoration period.
- 2.6.5 On average, there are going to be 58 HGV trips and 18 car trips per day during the restoration period. This relates to a total 76 vehicle movements per day in total. This is significantly less than the number of trips associated with the extraction phase of the quarry. During the extraction phase, 234 vehicle trips were recorded on a typical day.

- 2.6.6 Appropriate car parking provision for workers and visitors will be provided within the wider Site and a temporary contractor compound. Further details relating to the above are provided in the Construction Environmental Management Plan (CEMP)¹⁰ agreed as part of the Planning Permission.

2.7 Impact of Climate Change

- 2.7.1 The overarching aim of the works is to infill the void, restoring the Site to pre-quarrying levels. A Flood Risk Assessment (FRA)¹¹ was submitted as part of the planning application that accompanies this permit variation. The report, which takes into account extreme rainfall events, concluded that the completed restoration will not be subject to unacceptable flood risk and should not increase the risk of flooding elsewhere. Periods of extreme drought will not impact the Site given the lack of water resources associated with the it.
- 2.7.2 In September 2023 DCC published a position statement on inert landfill capacity in Devon. This document was updated (Revision 1) in October 2023¹². Paragraph 6.17 states:
- *“Planning permission was granted in July 2023 [DCC/4339/2023] for the importation of 1.5 million tonnes of inert waste to facilitate the restoration of Zig Zag Quarry, between Newton Abbot and Kingskerswell. This waste recovery operation would provide capacity for approximately 940,000 cubic metres of waste materials.”*
- 2.7.3 DCC’s October 2023 Position Statement in Devon identifies a need for facilities to dispose of inert waste within the County. The restoration of Zig Zag Quarry is seen an important waste recovery operation, with the additional benefit of providing DCC with a facility that is located strategically that can beneficially recover inert soil and stone and reduce unnecessary haulage distance of waste soils to disposal facilities outside the county. This will reduce carbon dioxide emissions significantly and therefore reduce the impacts to climate change.

¹⁰ Western Ecology (March 2023). Construction Environmental Management Plan. Zig Zag Quarry. Ref: WOR 3623

¹¹ RMA Environmental (20 January 2023) Flood Risk Assessment and Surface Water Drainage Strategy. Zig Zag Quarry. Ref: RMA-RC2403. Issue 1.

¹² Position Statement: Inert Waste Landfill Capacity (Revision 1) - Planning (devon.gov.uk) [Accessed 21 November 2023]

3. Conceptual Site Model

3.1 Conceptual Site Model

- 3.1.1 A standalone CSM report³ has been developed for this project with reference to guidance on GOV.UK⁹. The CSM report³ draws on the data in earlier reports by Aardvark as part of the original permit application and looks to establish the environmental setting of the Site along with potential hazards associated the proposed restoration and receptors that might be affected by the works.
- 3.1.2 The CSM report³ includes details relating to:
- Historical activities at Zig Zag Quarry;
 - The approved restoration works including proposed waste types and phasing plus outline management measures and technical controls;
 - Precipitation data (i.e., rainfall record);
 - Local surface water features;
 - Geological and hydrogeological setting;
 - Man-made pathways that may be affected by the restoration works; and
 - Receptors in the vicinity of the Site including amenity, habitats and natural heritage.
- 3.1.3 Data and discussion presented in the CSM report³ is generally not repeated in this ESSD report. It is assumed the reader of this ESSD report has read and is familiar with the CSM report³.
- 3.1.4 The aim of the CSM report³ is to evaluate the scope of specific risk assessments that are required as part of the permit. With respect to this permit variation, three documents that have been produced, namely a Gas Risk Assessment (GRA)¹³, a Hydrogeological Risk Assessment (HRA)¹⁴ and a Stability Risk Assessment (SRA)¹⁵

3.2 Gas Risk Assessment

- 3.2.1 A GRA¹³ was carried out by Horizon on the basis of the thickness of waste being deposited being greater than 2 m.
- 3.2.2 A complete source-pathway-receptor linkage was identified given there is the potential for any landfill gas to impact overlying crops. However, the intention is to import inert subsoil under strict Waste Acceptance Procedures¹⁶ to restore the Site for beneficial agricultural purposes, on which basis the flux of landfill gases from the waste is anticipated to be very low. The crops are anticipated to be of low sensitivity and whilst a capping layer is not proposed, the overall risk associated with this contaminant linkage is considered to be very low.

¹³ Horizon (November 2025). Zig Zag Quarry. Gas Risk Assessment. Ref: HCE0269.GRA.Rev2

¹⁴ Horizon (November 2025) Zig Zag Quarry. Hydrogeological Risk Assessment. Ref: HCE0269.HRA

¹⁵ Slope Stability Southwest (September 2024). Restoration Works at Zig Zag Quarry, Aller, Newton Abbot, Devon. Stability Risk Assessment Report. Ref: TJG/SRA/GO43.Zig Zag Quarry.Rev1

¹⁶ Horizon (November 2025). Zig Zag Quarry. Waste Acceptance Procedures (2025 Permit Variation). HCE0269.WAP.Rev1

3.3 Hydrogeological Risk Assessment

- 3.3.1 A previous HRA for the original permit was carried out by JH Groundwater in April 2021¹⁷. The updated HRA¹⁴ prepared by Horizon looks to build on the original work, taking into account the updated restoration proposals, additional data obtained on ground conditions along with the results of monitoring obtained.
- 3.3.2 The quantitative assessment considers that risks to receptors associated with the water environment are low notwithstanding the presence of sensitive receptors including a Principal Aquifer located directly beneath the Site.
- 3.3.3 The key outputs of the updated HRA¹⁴ are as follows:
- Material import is subject to strict waste acceptance procedures.
 - Part of the Site footprint has already been restored with indigenous and imported restoration material. The restoration area varies in thickness (see plans and cross sections in **Appendix A**). The material has been described as being generally cohesive and is interpreted to be generally low permeability.
 - It is proposed that where this is greater than 1 m in thickness, the currently placed material would form the geological barrier for the new materials to be placed, subject to some confirmatory permeability testing prior to tipping in those areas. Newly imported material would be placed directly on this.
 - In areas where material is yet to be placed, or where this is less than 1 m thickness, the use of compacted indigenous or greenfield derived imported materials is proposed in order to form a suitable geological barrier before placement.

3.4 Stability Risk Assessment

- 3.4.1 An SRA¹⁵ was carried out by Slope Stability Southwest (SSSW) in September 2024. The stability analysis undertaken as part of the assessment demonstrated that adequate Factors of Safety (long-term stability) will be attained for the proposed restoration provided it is correctly constructed with material of suitable strength and condition. All works should be undertaken in accordance with recognised standards and best practice for earthworks as detailed below.
- The inspection and assessment of all imported material to ensure the imported material is in accordance with planning conditions and specification of the Permit;
 - Material is to be placed and compacted in horizontal layers and compacted in accordance with the Construction Management Plan and established best practice; and
 - Surface water and run-off is to be controlled during the construction works and restoration profiling to ensure the imported material and restoration works are not subject to saturation or erosion due to run-off.

¹⁷ JH Groundwater (September 2021) Zig Zag Quarry Restoration. Hydrogeological Risk Assessment. Rev: 1164/001_r1_Rev3

4. Compliance Points

4.1 Groundwater

- 4.1.1 No Site-specific groundwater quality data was collected historically and following consultation with the Environment Agency as part of the April 2021 HRA¹⁷, groundwater monitoring was not a requirement of the existing Environmental Permit.
- 4.1.2 Subsequently 6No. groundwater boreholes have been installed at the Site in 2025, as shown on the Monitoring Point Plan (**Appendix A**). Moving forwards, it is proposed that monitoring of groundwater quality will provide the principal mechanism for evaluating effectiveness of the engineering measures. The proposed groundwater monitoring regime is presented in Section 8 of the HRA¹⁴.
- 4.1.3 Control and trigger levels have been derived on a borehole-specific basis for key indicator parameters for downgradient monitoring wells BH01 and BH02 (refer to Table 8-3 of the HRA¹⁴).

4.2 Surface Water

- 4.2.1 Surface water monitoring is being undertaken under the existing Environmental Permit with reference to the monitoring regime set out in the April 2021 HRA¹⁷. No change is proposed to this monitoring regime in the 2025 HRA¹⁴, with surface water samples continuing to be obtained from two sampling points, one upstream and one downstream of the restoration area (shown on the Site Infrastructure Plan (**Appendix A**)).

5. Pollution Control Measures

5.1 General & Phasing

5.1.1 The principal pollution control measure at the Site is strict adherence to the Waste Acceptance Procedures¹⁶ along with limiting the potential for unauthorised waste deposition. Details of the security infrastructure plus details of equipment and fuel storage are shown on the Site Infrastructure Plan in **Appendix A**.

5.1.2 It is proposed to carry out the works broadly in three phases working from the rear (north-east) of the quarry, towards the south-west, progressing the final landform shape. Phasing drawings are included in **Appendix A**. In relation to the works the outline sequencing is as follows:

- Enabling works will include site establishment, construction of surface water ditches and containment ponds plus review of security measures.
- Prior to the commencement of filling the existing topsoil placed on previously deposited soils will be stripped and stockpiled.
- A basal liner / side liner is to be constructed prior to waste deposition in areas where material has not been placed to date or the thickness of existing soils is less than 1 m. Details of the proposed liner are set out in Section 5.2 below.
- **Drawing 0269.601 (Appendix A)** shows where material is to be placed during Phase 1, with **Drawing 0269.602 (Appendix A)** showing how restoration will continue during Phase 2.
- Suitable waste soil is to be sourced from local development sites and imported to Site using sheeted lorries. The lorries will enter and exit the Site using the access in the west of the Site.
- During the works lorries are to deposit the imported waste soil as close to the working area as possible. This will then be compacted by excavator or bulldozer.
- The existing attenuation basins are to be retained as part of Phases 1 & 2. An existing Surface Water Management Plan has been approved as part of the agreed Planning Permission. Modification of the existing attenuation basins in anticipation of the start of Phase 1 works has already commenced.
- New attenuation basins are to be installed as part of the Phase 3 and final restoration period. Final restored levels are shown on the phasing drawings included in the planning permission drawings (see Appendix A of the CSM report³) however the Site Owner proposes to revise the Planning Permission to take into account more appropriately designed attenuation basins. On that basis, two versions of the works to take place in Phase 3 are shown:
 - **Drawing 0269.604 (Appendix A)**. This drawing retains the existing drainage basins; however, the final restoration levels at the west of the Site are slightly lower than those envisaged in the Planning Permission; and
 - **Drawing 0269.603 (Appendix A)**. This drawing is based on a revised drainage scheme, with final restoration levels at the west of the Site consistent with those envisaged in the Planning Permission.
- Cross-sections showing the restoration profile with and without the existing drainage basins are included in **Appendix A (Drawings 0269.605 and 0269.606)**.

- A veneer of topsoil (typically 150 mm thick) is to be placed over the subsoil to complete the restoration works. Topsoil is to be placed on a staged basis as final levels are achieved with the Site returning to agricultural land. Details with regards to proposed topsoil thicknesses is set out within the Landscape Planting Plan⁷ and summarised in Section 1.2 of this ESSD report.
- The land is to be seeded with grass and returned to agricultural use upon completion.
- All works are to be undertaken in accordance with any requirements of the Planning Permission.

5.2 Basal & Side Slope Engineering

- 5.2.1 Details of the earthworks, including identification of source material, placement and testing to confirm liner suitability will be set out in the CQA Design Report.
- 5.2.2 The 2025 HRA¹⁴ requires a basal liner to extend up from the base of the Site to line the sides of the existing quarry.
- 5.2.3 Where the existing soils are greater in thickness than 1 m, testing will be undertaken to confirm these soils are of suitable quality to provide protection equivalent to a layer 1 m thick with a permeability of less than or equal to 1×10^{-7} m/s.
- 5.2.4 Elsewhere a basal liner is to be installed beneath all deposited waste henceforth. Where the waste tapers to less than 1.0 m thick, any deposited waste will be formed of suitable liner material, placed and compacted under CQA procedures. An indicative cross-section showing the basal liner is included **Appendix A (Drawing 0269.109)**.
- 5.2.5 The material to form the liner will comprise suitable existing soils (either natural soils of the Aller Formation or existing restoration soils) or imported soils and will be subject to CQA procedures. Details of the specification for the liner (i.e., material properties and testing) is to be provided in the CQA Design Report.

5.3 Basal Liner Soil Chemistry

- 5.3.1 At Zig Zag Quarry, the basal liner must reduce emissions of contaminants in the fill and not cause an unacceptable discharge. On that basis, material used for the attenuation layer must be physically and chemically suitable, *“with a pollution potential less than or equal to the natural quality of the surrounding geology.”*
- 5.3.2 Furthermore, as a minimum the waste used for basal liner construction must be inert. This is consistent with the requirements for fill material at the Site. With reference to UK.GOV¹⁸, inert waste is *“waste that does not undergo any significant physical, chemical or biological transformations. Inert waste will not dissolve, burn or otherwise physically or chemically react, biodegrade or adversely affect other matter that it comes into contact with, in a way likely to cause environmental pollution or harm to human health.”*
- 5.3.3 For material imported historically and placed under the CL:AIRE DOWCOP⁵ scheme, the material suitability requirements specified that *“inert waste and sand and gravel”* per the Planning Permission were used for restoration material. Inert waste is defined in the planning permission as material that is not chemically or biologically reactive and will not decompose.

¹⁸ <https://www.gov.uk/guidance/landfill-operators-environmental-permits/landfills-for-inert-waste> [Accessed 30 January 2026]

- 5.3.4 Under the CL:AIRE DOWCOP scheme only soils meeting EWC 17 05 04 were to be imported to Site. These were only to comprise clean naturally occurring soils that met the inert waste leachate criteria. In addition, any soils were required to have concentrations of substances (such as geologically derived metals, metalloids etc) at a level that was consistent with or lower than background concentrations at the Zig Zag Quarry site.
- 5.3.5 The Verification Report⁶ prepared upon completion of material import under the CL:AIRE DOWCOP⁵ scheme evaluated the material imported and placed, to confirm it met the requirements set out above. This report was submitted to CL:AIRE and the Environment Agency as part of the transition between the use of the CL:AIRE DOWCOP⁵ scheme and the Environmental Permit on-Site.
- 5.3.6 On the basis that the Verification Report demonstrated that only clean naturally occurring soils from greenfield Site, with naturally occurring contaminants at a level consistent with or below background concentrations at Zig Zag Quarry were imported and placed it is considered that the requirement for using waste in construction is met and that the material imported under the DOWCOP scheme has a pollution potential equal or lower than the natural ground.
- 5.3.7 Although any future soils imported for the basal liner elsewhere across the Site will be imported under the Environmental Permit as opposed to the CL:AIRE DOWCOP⁵ scheme it is proposed to continue to use the approach set out above (i.e., inert, only clean naturally occurring soils from greenfield site, concentrations of contaminants equal to or below background concentrations at Zig Zag Quarry) such that requirement for using waste in construction continues to be met.
- 5.3.8 Confirmation that the above requirements are met for imported soils used as part of the future basal liner construction will be set out in the CQA Validation Report.

5.4 Surface Water Management

- 5.4.1 The potential for contamination of surface water and / or groundwater during construction as a result of general construction-related activities was assessed during the planning process (Chapter 6¹⁹ of the Environmental Statement plus the supporting Flood Risk Assessment (FRA¹¹). In summary, during the restoration works, the runoff from the reinstated surfaces will be attenuated within a basin in the southern part of the Site (refer to Drawing DR-001 from the FRA¹¹ reproduced in **Appendix B**). This is consistent with the approach adopted to date on-Site.
- 5.4.2 During earthwork filling operations suspended solids contained within the runoff as a result of the exposed fill surface will need to be managed. As with all large-scale earthwork operations the primary concern is the interception of surface water runoff containing large quantities of suspended solids. To address this the scheme incorporates two attenuation basins / settlement lagoons at the low point of the fill area which will be used to enable the suspended solids to settle out. If necessary, to promote early settlement of suspended solids the basins will comprise of two to three settlement bays divided by earthwork weirs.
- 5.4.3 Overland flow will be conveyed from the fill area to the basins via a combination of interception ditches and proprietary silt fences adjusted as necessary to suit the operational requirements of the Site. The ditches will discharge to the basins via a weir parallel to the upstream end, this lateral inflow will reduce the potential for settled silts being forced back into suspension by sudden high

¹⁹ Aardvark (February 2023) Environmental Statement – Chapter 6 Technical Chapter – Hydrology and Hydrogeology. Ref: 2149-R003 - Hydrology and Hydrogeology

flows entering the primary settlement bay. The level of silt built up in the ditches can be easily monitored during the works to determine the appropriate intervals for the de-silting of the main basins; the volume of silt removed from the ditches on a regular basis determining the amount conveyed from the fill area towards the basins.

- 5.4.4 As discussed in Section 5.2, the Site Owner is redesigning the attenuation basins / settlement lagoons as part of the final restoration profile. Any redesign would be subject to approval by Devon County Council. This ESSD provides final contour plans to cover both eventualities.

5.5 Amenity

- 5.5.1 The CSM³ identified numerous receptors which could be impacted by the development including nearby residential and commercial properties (see Sensitive Receptors Plan included in Appendix A of the CSM³).
- 5.5.2 With respect to the proposed development, the biggest impact to amenity use is likely to be from dust. Given the Site has a history of industry, specifically the quarrying and processing of sand and gravel, effective dust management practices are already in place.
- 5.5.3 An assessment of the risk to amenity use from dust was carried out under planning for the proposed development (Chapter 6 of the Environmental Statement²⁰). In summary, the assessment demonstrated that the overall air quality effect of the proposed scheme will be 'not significant'; restoration dust emissions will not have a significant effect on amenity or human health and the development-generated traffic emissions will not have a significant effect on local air quality. Nevertheless, it is good practice for measures to be implemented to ensure dust emissions are minimised, particularly during adverse (dry and windy) weather conditions.
- 5.5.4 On that basis no additional control measures (i.e., over and above dust management etc) are proposed. Details of the dust management controls, and monitoring are set out within the Dust & Emissions Management Plan (DEMP)²¹ prepared by Horizon in 2025 to take account of the increased volume of material to be placed.

5.6 Post Closure Controls (Aftercare)

- 5.6.1 Drawings showing the approved restoration scheme are included in Appendix A of the CSM report³. The proposal is to infill the Site to pre-quarrying levels. This provides for a restoration scheme that results in a landform in keeping with the surrounding area and providing a safer and more ecologically beneficial landscape.
- 5.6.2 The 2023 restoration proposals are considered in the Landscape and Visual Impact Assessment (LVIA²²) to provide a positive permanent change including:
- *“New field pattern with hedge banks and hedgerow trees;*
 - *New areas of woodland;*
 - *Long-term management changes to hedges – cut less frequently and higher;*
 - *Retention and enhancement of the existing drainage attenuation;*

²⁰ Air Quality Consultants (2023). Zig Zag Quarry Restoration. Environmental Statement – Chapter 6 Technical Chapter – Air Quality and Dust. Ref: 2149-R003-Chapter 6 –Air Quality and Dust

²¹ Horizon (November 2025) Zig Zag Quarry. Dust & Emissions Management Plan. Ref: HCE0269.DEMP.Rev1

²² Swan Paul Associates (2023) Zig Zag Quarry. Landscape and Visual Impact Assessment.

- *Restored Site levels; and*
- *Improved levels of tranquillity.”*

- 5.6.3 The significance and nature of the effect of returning the Site to its historic pre-quarrying baseline was considered in the LVIA²² and is considered to provide a moderate and permanent positive change to the existing situation. Additional restoration phase mitigation set out in the LVIA²² includes a commitment to maintain hedges for wildlife benefit in the longer term. They will continue to be cut longer and less frequently. Hedges will be on traditional Devon hedge banks and there will be hedgerow trees in some locations and additional woodland copses to the perimeters.
- 5.6.4 Following placement of the soil layer the Site is to be restored in accordance with the Masterplan approved in the 2024 Planning Permission. This will include decommissioning and removal of plant and equipment not associated with the long-term use of the Site (e.g. weighbridge) and placement of overlying surface materials (e.g., areas of grassland / woodland / scrub / bushes etc).
- 5.6.5 The post-closure controls are considered to represent on-going operational requirements associated with the new landscape, as opposed to post-closure controls. Provided the material is imported as per the requirements of the Waste Acceptance Procedures¹⁶, placed as required by the SRA¹⁵ and this ESSD report, no post closure controls is required for the Site.
- 5.6.6 Aftercare of the Site will be undertaken for a minimum of three years post placement of the capping layer to demonstrate that the restoration scheme has met the design objectives. During this period, it is envisaged that public access will be permitted to the Site however overall responsibility for access and security will remain with BTJ.
- 5.6.7 Monitoring during the aftercare period will include:
- Groundwater quality monitoring;
 - Surface water quality monitoring; and
 - Topographic surveys.
- 5.6.8 Site completion will occur when sufficient monitoring has been undertaken to demonstrate that the Site has met the design objectives, does not pose a significant risk to the environment and the Environmental Permit can be surrendered.

5.7 Incident Response & Quarantine Area

- 5.7.1 Any waste deemed to be unacceptable based on visual inspection following importation and deposition at the Site (i.e., prior to material being compacted by excavator or bulldozer) will be excavated and placed in a dedicated quarantine area (location shown on Site Infrastructure Plan included in **Appendix A**).
- 5.7.2 On the basis of the visual or olfactory observations (i.e., the rationale for moving material to the Quarantine area) a plan of action will be determined for the quarantined material. This may involve consultation with the EA and/or additional chemical testing of the material.
- 5.7.3 Should the Quarantine area become full, then the Site will cease to accept waste for deposition until such time as space is available within the Quarantine area and/or a course of action is agreed with the EA.

6. Monitoring

6.1 Weather

- 6.1.1 A Dust Management Plan²³ was prepared for the Site as part of the original permit application. No complaints have been received to date relating to dust. The updated DEMP²¹ has been prepared taking into account the effective existing mitigation measures.
- 6.1.2 Monitoring weather conditions is a requirement of the DEMP²¹ with details recorded in the Site diary. This includes reviewing the weather forecast in advance of works, monitoring wind conditions and visual monitoring to assess if dust control measures, such as damping down exposed surfaces, are required during the works. This is to include comments along the lines of whether the source of any dust is evident, is the dust constant or intermittent, can the dust be seen to be settling on surfaces.
- 6.1.3 During periods of particularly inclement weather the Site Manager has the authority to shut the Site to minimise potential for trafficking dust / mud off-Site.
- 6.1.4 It is not proposed to install a weather station at the Site given measurements of wind speed are less important than visual observations from the Site Manager or his nominated deputy.

6.2 Gas Monitoring & Infrastructure

- 6.2.1 No gas monitoring was proposed in the original ESSD report⁴ on the basis that the “*application was for inert waste and topsoil*” only and no gas monitoring infrastructure has been installed at the Site.
- 6.2.2 More recently, gas monitoring commenced from boreholes BH01, BH02, BH03 and BH04 in March 2025, with monitoring of boreholes BH05 and BH06 scheduled to commence in November 2025. Given boreholes are available, it is proposed that moving forwards gas monitoring be conducted on as per **Table 6-1** below.

Monitoring Point	Parameter (s)	Monitoring Frequency	Method	Notes
During Infilling				
BH01, BH02, BH03, BH04, BH05* & BH06*	Atmospheric Pressures	Quarterly	As specified in Environment Agency Guidance TGN03 ²⁴	Record ground conditions (e.g., whether ground is waterlogged, frozen or snow covered) plus meteorological conditions at time of monitoring.
	Differential Pressure			
	Flow Rate**			
	Methane**			
	Carbon Dioxide**			
	Carbon Monoxide**			
	Hydrogen Sulphide**			
	Oxygen**			
Notes: * Borehole to be monitored whilst available until location is lost during restoration. ** During each monitoring visit, both peak and steady-state values for parameter to be recorded.				

Table 6-1: Ground Gas Monitoring Frequency

²³ Aardvark (May 2021) Zig Zag Quarry. Environmental Permit Application. Dust Management Plan. Ref: 1922-R008. Rev. Final v3

²⁴ Environment Agency (September 2004) Guidance on the Management of Landfill Gas. Ref: LFTGN03

- 6.2.3 The risk from ground gas is evaluated in the GRA¹³. Given the Site is to be restored primarily with inert subsoil under strict Waste Acceptance Procedures, with no biodegradable wastes (e.g. paper, cardboard, wood, garden refuse, textiles, sewage sludge) accepted, the potential for gas generation is considered to be very low.
- 6.2.4 In the absence of a significant source of off-site ground gas, it is proposed to adopt Completion Criteria 1 values (as set out in GOV.UK landfill surrender guidance²⁵) of 1.5% (methane) and 5% (carbon dioxide) as control levels during operation of the Site. Should elevated gas concentrations be recorded, consideration will be given to installation of in-waste gas monitoring wells.

6.3 Surface Water Monitoring

- 6.3.1 Monitoring surface water quality is considered to represent an important data source through which performance and effectiveness of the works is evaluated. Monitoring on the Aller Brook is to continue; details of the surface water monitoring are set out in Section 8.2 of the HRA¹⁴.
- 6.3.2 Water samples are currently obtained from two locations on the Aller Brook as shown on the Site Infrastructure Plan (**Appendix A**) and drawing in **Appendix C**.

6.4 Groundwater Monitoring Infrastructure

- 6.4.1 No groundwater monitoring was required in the existing Environmental Permit however subsequently six groundwater boreholes have been installed at the Site. Borehole locations shown on Monitoring Point Plan (**Appendix A**).

6.5 Groundwater Monitoring

- 6.5.1 Groundwater monitoring was not a requirement of the existing Environmental Permit however is being undertaken currently to establish a baseline with future monitoring of groundwater quality proposed to evaluate effectiveness of the engineering measures. The proposed groundwater monitoring regime is presented in Section 8.3 of the HRA¹⁴.
- 6.5.2 Compliance limits for boreholes BH01 and BH02 are set out in the HRA¹⁴.

6.6 Amenity Monitoring

- 6.6.1 Amenity monitoring is not specified with the requirements of the DEMP²¹.
- 6.6.2 The Site Manager or his deputy is required in the EMS to walk the Site boundary at least once per week or more frequently during periods of extreme weather. This walkover is intended to confirm the effectiveness of mitigation measures on-Site and that nuisance is not occurring.

²⁵ <https://www.gov.uk/government/publications/landfill-epr-502-and-other-permanent-deposits-of-waste-how-to-surrender-your-environmental-permit> [Accessed 21 November 2025]

Appendix A

Horizon Drawings

NOTES: GENERAL

1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT SCHEME DRAWINGS AND SPECIFICATIONS.
2. INSET IN TOP RIGHT OF DRAWING SHOWING OTHER SAMPLING LOCATION ZZSW1. FOR INDICATIVE PURPOSES ONLY. FOR DETAILED PLAN SHOWING MONITORING LOCATIONS REFER TO DRAWING 0269.105.
3. NO BUILDINGS OR PERMANENT SERVICES WITHIN PERMITTED AREA.

NOTE: SITE SECURITY

- SECURE SITE BOUNDARY INCLUDING POST AND WIRE FENCING. PADLOCK GATED ENTRANCE.
- DENSE VEGETATION GROWTH AND STEEP SIDES ACT AS A DETERRENT TO TRESPASSERS.
- WEEKLY BOUNDARY CHECKS.
- ON-SITE CCTV AND THIRD PARTY SECURITY FOR OUT OF HOURS CALL OUTS.
- EQUIPMENT AND TOOLS STORED IN LOCKED CONTAINERS BY SITE OFFICES.
- DOORS AND WINDOWS RE-ENFORCED AS APPROPRIATE.
- ALL VISITORS TO SIGN IN AND OUT.

DEPOSITION AREA DEFINED BY RED LINE BOUNDARY. NO DEPOSITION TO OCCUR OUTSIDE OF PERMIT BOUNDARY (ONLY RE-PROFILING OF EXISTING SOILS)

EXISTING WASH PLANT USED FOR QUARRYING PURPOSES (NOT ASSOCIATED WITH ENVIRONMENTAL PERMIT)

EXISTING SITE OFFICES, WELFARE FACILITIES, WEIGHBRIDE AND PARKING, MAINS WATER


SITE ENTRANCE FOR ALL VEHICLES INCLUDING EMERGENCY SERVICES

EXISTING SAND AND GRAVEL BATCHING AREA (NOT ASSOCIATED WITH ENVIRONMENTAL PERMIT)

EXISTING SETTLEMENT LAGOON

KEY:

- SITE BOUNDARY (2023 PLANNING PERMISSION)
- PERMIT BOUNDARY (TO REMAIN UNCHANGED FROM EXISTING PERMIT)
- SURFACE WATER MONITORING POINT
- GROUNDWATER MONITORING POINT
- WATER SERVICES
- ELECTRICITY SERVICES



Tresco House, Westpoint Crt, Sidmouth Rd, Exeter EX5 1DJ
T: 01392 363364 www.horizon-ce.co.uk



JOB TITLE

ZIG ZAG QUARRY
KINGSKERSWELL

DRAWING TITLE


SITE INFRASTRUCTURE PLAN

A	Plan updated to include October 2025 boreholes.	JH	AL	31.10.25
Rev	Description	Drn	Chk	Date
REVISIONS				
Preliminary	Approval	Tender	Const.	
DRAWING STATUS				
DATE	JUN' 24	DRAWN	JH	CHECKED
DRAWING No.	0269.103	REV		SCALE 1:2,500 @ A3
© This drawing is the copyright of Horizon Consulting Engineers (Horizon) Limited. It may not be reproduced or amended without the written approval of Horizon.				

NOTES: GENERAL

- 1. DO NOT SCALE FROM THIS DRAWING
- 2. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT SCHEME DRAWINGS AND SPECIFICATIONS.
- 3. INDICATIVE SECTION SHOWN NOTING EXISTING PLACEMENT OF RESTORATION MATERIAL TO VARIES ACROSS THE SITE THEREFORE PLACEMENT OF AEGB WILL VARY ON THAT BASIS.

INDICATIVE CROSS SECTION THROUGH COMPLETED RESTORATION FOR THE PURPOSES OF SHOWING DESIGN OF LINER AND SIDE SLOPE ENGINEERING





Horizon
Consulting Engineers

The Dairy Barn, Westpoint Crt, Sidmouth Rd, Exeter EX5 1DJ
T: 01392 363364 www.horizon-ce.co.uk



JENKINS
LTD


JOB TITLE

ZIG ZAG QUARRY
KINGSKERSWELL

DRAWING TITLE

INDICATIVE LINER AND SIDE SLOPE ENGINEERING
ENVIRONMENTAL SETTING AND SITE DESIGN

Rev	Description	Drn	Chk	Date
REVISIONS				
Preliminary	Approval	Tender	Const.	
DRAWING STATUS				
DATE	DRAWN	CHECKED	ISSUE CHECKBOX	
SEP '24	JH	AL		
DRAWING No.	REV	SCALE	@	
0269.109	-	NTS	A3	
© This drawing is the copyright of Horizon Consulting Engineers (Horizon) Limited. It may not be reproduced or amended without the written approval of Horizon.				



PHASE 1 CUT / FILL
FILL 580,000 m³
CUT 30,000 m³
NET FILL 550,000 m³

EXISTING STOCKPILES TO BE RELOCATED
OR INCORPORATED INTO WASTE MASS

EXISTING WASH PLANT TO REMAIN OPERATIONAL
FOR DURATION OF PHASE 1 WORKS

EXISTING CEMENT BAGGING PLANT TO REMAIN
OPERATIONAL FOR DURATION OF PHASE 1 WORKS

EXISTING BOUNDARY LEVEL TO BE CONFIRMED,
CONTRACTOR TO GRADE IMPORTED FILL TO
EXISTING GROUND LEVEL AT SITE BOUNDARY

QUARRY WORKS HAVE BEEN UNDERTAKEN SINCE 2022 LIDAR
SURVEY, CONTRACTOR TO ENSURE PROPOSED SURFACE TIES
INTO EXISTING AT SUITABLE GRADE NO STEEPER THAN 1:3

PROPOSED BASIN AND ASSOCIATED
DRAINAGE INFRASTRUCTURE CONSTRUCTED
IN ACCORDANCE WITH APPROVED PLANS

NOTES: GENERAL

- DO NOT SCALE FROM THIS DRAWING
- ALL DIMENSIONS SHOWN ARE IN METRES UNLESS STATED OTHERWISE
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT SCHEME DRAWINGS AND SPECIFICATIONS
- COMPOSITE MODEL REF: 220628 PROVIDED BY 4DES COMPARED WITH PROPOSED MODEL USED FOR VOLUMETRIC CALCULATIONS AS PER APPROVED PLANNING DRAWINGS. ASSUMPTIONS MADE IN COMPOSITE MODEL HAVE NOT BEEN VALIDATED, CIRCA 100,000m³ VOLUME REMOVED WHEN COMPARED TO JUNE 2022 LIDAR MODEL REF 240221

Rev	Description	Drn	Chk	Date
REVISIONS				
Preliminary Issue	30.05.24	Submitted for S104		
Planning Issue		Issued for Tender		
Submitted for S38		Issued for Construction		
Submitted for S278		As Built		
DRAWING STATUS				



JOB TITLE
ZIG ZAG RESTORATION

DRAWING TITLE
PHASE 1 PLAN
PROPOSED

DATE MAY '24 DRAWN GB CHECKED HT
DRAWING NO. 0269.601 REV -- SCALE AS SHOWN @ A1

© This drawing is the copyright of Horizon Consulting Engineers Limited (Horizon) and shall not be reproduced or amended without the written approval of Horizon.



- NOTES: GENERAL
- DO NOT SCALE FROM THIS DRAWING
 - ALL DIMENSIONS SHOWN ARE IN METRES UNLESS STATED OTHERWISE
 - THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT SCHEME DRAWINGS AND SPECIFICATIONS
 - COMPOSITE MODEL REF. 220628 PROVIDED BY ADE'S COMPARED WITH PROPOSED MODEL USED FOR VOLUMETRIC CALCULATIONS AS PER APPROVED PLANNING DRAWINGS. ASSUMPTIONS MADE IN COMPOSITE MODEL HAVE NOT BEEN VALIDATED, CIRCA 100,000m³ VOLUME REMOVED WHEN COMPARED TO JUNE 2022 LIDAR MODEL REF 240221

Rev	Description	Drn	Chk	Date
REVISIONS				
Preliminary Issue	30.05.24	Submitted for S104		
Planning Issue		Issued for Tender		
Submitted for S38		Issued for Construction		
Submitted for S278		As Built		
DRAWING STATUS				




JOB TITLE
ZIG ZAG RESTORATION

DRAWING TITLE
PHASE 2 PLAN
PROPOSED

DATE	0269.602	DRW	GB	CHECKED	HT
MAY '24					
SCALE	AS SHOWN @ A1				

© This drawing is the copyright of Horizon Consulting Engineers Limited (Horizon) and shall not be reproduced or amended without the written approval of Horizon.



FINAL RESTORATION PHASE CUT / FILL

FILL 107,000 m³
CUT <1,000 m³
NET FILL 107,000 m³

TOTAL CUT / FILL
FILL 860,000 m³
CUT 10,000 m³
NET FILL 850,000 m³

EXISTING BOUNDARY LEVEL TO BE CONFIRMED,
CONTRACTOR TO GRADE IMPORTED FILL TO
EXISTING GROUND LEVEL AT SITE BOUNDARY

QUARRY WORKS HAVE BEEN UNDERTAKEN SINCE 2022 LIDAR
SURVEY, CONTRACTOR TO ENSURE PROPOSED SURFACE TIES
INTO EXISTING AT SUITABLE GRADE NO STEEPER THAN 1:3

BASINS OMITTED FROM FINAL RESTORATION ON
THE ASSUMPTION THAT AN ALTERNATIVE DRAINAGE
STRATEGY, DESIGN BY OTHERS, IS ACCEPTABLE

NOTES: GENERAL

- DO NOT SCALE FROM THIS DRAWING
- ALL DIMENSIONS SHOWN ARE IN METRES UNLESS STATED OTHERWISE
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT SCHEME DRAWINGS AND SPECIFICATIONS
- COMPOSITE MODEL REF: 220628 PROVIDED BY ADE'S COMPARED WITH PROPOSED MODEL USED FOR VOLUMETRIC CALCULATIONS AS PER APPROVED PLANNING DRAWINGS. ASSUMPTIONS MADE IN COMPOSITE MODEL HAVE NOT BEEN VALIDATED, CIRCA 100,000m³ VOLUME REMOVED WHEN COMPARED TO JUNE 2022 LIDAR MODEL REF 240221

Rev	Description	Drn	Chk	Date
REVISIONS				
Preliminary Issue	21.06.24	Submitted for S104		
Planning Issue		Issued for Tender		
Submitted for S38		Issued for Construction		
Submitted for S278		As Built		
DRAWING STATUS				

Horizon
Consulting Engineers

The Dairy Barn, Westpoint Crt, Sidmouth Rd, Exeter EX5 1DJ
T: 01392 363364 www.horizon-ce.co.uk


JENKINS
LLP

JOB TITLE
ZIG ZAG RESTORATION

DRAWING TITLE
RESTORATION PLAN
PROPOSED
WITHOUT BASINS

DATE	0269.603	DRW	GB	CHECKED	HT
MAY '24					
SCALE	AS SHOWN @ A1				

© This drawing is the copyright of Horizon Consulting Engineers Limited (Horizon) and shall not be reproduced or amended without the written approval of Horizon.



FINAL RESTORATION PHASE CUT / FILL

FILL 68,000 m³
CUT 2,000 m³
NET FILL 66,000 m³

TOTAL CUT / FILL

FILL 811,000 m³
CUT 34,000 m³
NET FILL 777,000 m³

EXISTING BOUNDARY LEVEL TO BE CONFIRMED,
CONTRACTOR TO GRADE IMPORTED FILL TO
EXISTING GROUND LEVEL AT SITE BOUNDARY

QUARRY WORKS HAVE BEEN UNDERTAKEN SINCE 2022 LIDAR
SURVEY, CONTRACTOR TO ENSURE PROPOSED SURFACE TIES
INTO EXISTING AT SUITABLE GRADE NO STEEPER THAN 1:3

PROPOSED BASIN AND ASSOCIATED
DRAINAGE INFRASTRUCTURE CONSTRUCTED
IN ACCORDANCE WITH APPROVED PLANS

NOTES: GENERAL

- DO NOT SCALE FROM THIS DRAWING
- ALL DIMENSIONS SHOWN ARE IN METRES UNLESS STATED OTHERWISE
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT SCHEME DRAWINGS AND SPECIFICATIONS
- COMPOSITE MODEL REF: 220628 PROVIDED BY ADE'S COMPARED WITH PROPOSED MODEL USED FOR VOLUMETRIC CALCULATIONS AS PER APPROVED PLANNING DRAWINGS. ASSUMPTIONS MADE IN COMPOSITE MODEL HAVE NOT BEEN VALIDATED, CIRCA 100,000m³ VOLUME REMOVED WHEN COMPARED TO JUNE 2022 LIDAR MODEL REF 240221

Rev	Description	Drn	Chk	Date
REVISIONS				
Preliminary Issue	30.05.24	Submitted for S104		
Planning Issue		Issued for Tender		
Submitted for S38		Issued for Construction		
Submitted for S278		As Built		
DRAWING STATUS				



The Dairy Barn, Westpoint Crt, Sidmouth Rd, Exeter EX5 1DJ
T: 01392 363364 www.horizon-ce.co.uk





JOB TITLE
ZIG ZAG RESTORATION

DRAWING TITLE
RESTORATION PLAN
PROPOSED
WITH BASINS

DATE MAY '24 DRAWN GB CHECKED HT
DRAWING NO. 0269.604 REV - SCALE AS SHOWN @ A1

© This drawing is the copyright of Horizon Consulting Engineers Limited (Horizon) and shall not be reproduced or amended without the written approval of Horizon.




ZIG ZAG RESTORATION

DRAWING TITLE



SECTIONS
PROPOSED
SHEET 1

DATE	0269.605	ORIGIN	GB	CHECKED	HT
DRAWING No.	0269.605	REV	-	SCALE	AS SHOWN @ A1


© This drawing is the copyright of Horizon Consulting Engineers Limited (Horizon) and shall not be reproduced or amended without the written approval of Horizon



SECTION B-B' PHASE 1
SCALE 1:1000 HORIZ / 1:1000 VERT



SECTION B-B' PHASE 2
SCALE 1:1000 HORIZ / 1:1000 VERT



SECTION B-B' FINAL RESTORATION
SCALE 1:1000 HORIZ / 1:1000 VERT

NOTES: GENERAL

- DO NOT SCALE FROM THIS DRAWING
- ALL DIMENSIONS SHOWN ARE IN METRES UNLESS STATED OTHERWISE
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT SCHEME DRAWINGS AND SPECIFICATIONS
- REFER TO DRAWING 0269-601 FOR SECTION LINE LOCATIONS
- JUNE 2022 LIDAR SURVEY, REF: 240221 AND COMPOSITE MODEL, REF: 220628 PROVIDED BY 4DES

Rev	Description	Drn	Chk	Date
REVISIONS				
Preliminary Issue	30.05.24	Submitted for S104		
Planning Issue		Issued for Tender		
Submitted for S38		Issued for Construction		
Submitted for S278		As Built		
DRAWING STATUS				



JOB TITLE
ZIG ZAG RESTORATION

DRAWING TITLE
**SECTIONS
PROPOSED
SHEET 2**

DATE
MAY '24

DRAWN
GB

CHECKED
HT


DRAWING NO.
0269.606

REV
-

SCALE
AS SHOWN @ A1

© This drawing is the copyright of Horizon Consulting Engineers Limited (Horizon) and shall not be reproduced or amended without the written approval of Horizon.

Appendix B
Drawing Reproduced from FRA



PHASING PLAN

Phase 1
Construct Basin/Pond 1 and conduits 1.004-1.005
Reinstate Phase 1A sub-catchment
Construct swale/ditch and conduits 1.000 to 1.003

Phase 2
Reinstate Phase 2 sub-catchment
Construct swale/ditch and conduits 3.000 to 3.001
Replace Hydro-Brake in Basin/Pond 1

Phase 3
Construct Basin/Pond 2 and conduit 4.000

Appendix C

Drawing Reproduced from 2021 HRA

SITE	Zig Zag Quarry. Aller Brook upgradient of restoration area.													
Visit date and time	22_7_21 11:00:00													
Name of sampler	Julian Hatherall.													
Weather conditions	Hot, Dry													
Ground Conditions	Dry													
Sample Ref	Grid Reference	Approx. Elevation	Type of sample	Location	Purpose	Water Conditions in Stream	Analysis type - In-situ +/-or laboratory	Temp	pH	EC	TDS	Visual / Olfactory Description	Laboratory	Notes
ZZ SW1	SX 87810 67655	22mAOD	Surface Water	Adjacent to public footpath. Upstream of restoration.	Initial sampling visit.	At the time of sampling sediment load was low. Flow reasonable.	In-situ and Laboratory samples collected	16	8	660	330	Light sediment loading, no other discolouration. No odour.	QTS Environmental - collected 22_7_21.	
Units		mAOD						°C		µS/cm	mg/l or ppm			
  SAMPLING LOCATIONS RELATIVE TO RESTORATION AREA.														
GENERAL NOTES	Add any general notes about the sampling location catchment or other observations here. This should also include any planned, near future operations close to the sampling point which could impact water quality data.													
Sampling point is adjacent to a public footpath upstream of the restoration area. It has been chosen as being upstream and accessible and safe. Closer locations are either inaccessible due to height or on private land.														
The sampling point is approximately 2m in width and <1m deep. The location is accessed from the footpath in playing fields.														
Surrounding land use is predominantly roads and housing. There is some private sewage treatment plants discharging to surface water locally. There may also be formal and informal road drainage points. Road runoff in heavy rainfall has the potential to transmit pollutants to the brook both from the road and surrounding areas.														
It is likely that water quality will be variable and reflect changes in flow and seasonal runoff. A small snapshot has been collected for baseline monitoring and changes in water quality during the operational phase will need to take account of the presence of this anticipated variability where this is identified in the water quality monitoring results.														
INTERPRETATION - SEE ATTACHED SHEET FOR RESULTS OF ANALYSIS														
Local conditions were dry preceding the visit.														
Results similar for up and down stream samples.														
Further changes to parameters are anticipated as a result of seasonal change in runoff within the catchment. This will need to be taken into account during the review of subsequent results.														
Given the nature of the catchment and potential seasonal changes to water quality it is considered appropriate at this stage to review changes in water quality trends rather than apply strict control and trigger levels .														
If control and trigger levels are to be applied then they should be relatively broad at this time.														

SITE	Zig Zag Quarry. Aller Brook downgradient of restoration area.												
Visit date and time	22_7_21 11:00:00												
Name of sampler	Julian Hatherall.												
Weather conditions	Hot, Dry												
Ground Conditions	Dry												

Sample Ref	Grid Reference	Approx. Elevation	Type of sample	Location	Purpose	Water Conditions in Stream	Analysis type - In-situ +/-or laboratory	Field Chemistry and Appearance					Laboratory	Notes
								Temp	pH	EC	TDS	Visual / Olfactory Description	Sample Collected for Lab Analysis? Any storage issues?	
ZZ SW2	SX 87625 68928	13mAOD	Surface Water	Within roof supplies yard. downstream of restoration.	Quarterly sampling visit.	At the time of sampling sediment load was low in the river. Flow reasonable.	In-situ and Laboratory samples collected	16	8	630	310	Light sediment loading. No odour.	QTS Environmental - collected 22_7_21.	
Units		mAOD						°C		µS/cm	mg/l or ppm			



SAMPLING LOCATION 22/7/21



RESTORATION AREA

ZZSW2

EST. GW FLOW DIRECTION FOLLOWING TOPOGRAPHY

ROAD DRAINAGE

ZZSW1

SAMPLING LOCATIONS RELATIVE TO RESTORATION AREA.

GENERAL NOTES	Add any general notes about the sampling location catchment or other observations here. This should also include any planned, near future operations close to the sampling point which could impact water quality data.
Sampling point is in a roofing supplies yard adjacent to a road bridge downstream of the restoration area. It has been chosen as being on the down stream. Unable to access private land further downstream.	
The sampling point is approximately 5m in width and <1m deep. The location is accessed from the yard.	
Surrounding land use is predominantly roads and housing. There is some private sewage treatment plants discharging to surface wate locally. There may also be formal and informal road drainage points. Road runoff in heavy rainfall has the potential to transmit pollutants to the brook both from the road and surrounding areas.	
It is likely that water quality will be variable and reflect changes in flow and seasonal runoff. A small snapshot has been collected for baseline monitoring and changes in water quality during the operational phase will need to take account of the presence of this anticipated variability where this is identified in the water quality monitoring results.	

INTERPRETATION - SEE ATTACHED SHEET FOR RESULTS OF ANALYSIS
Local conditions were dry preceding the visit.
Results similar for up and down stream samples.
Further changes to parameters are anticipated as a result of seasonal change in runoff within the catchment. This will need to be taken into account during the review of subsequent results.
Given the nature of the catchment and potential seasonal changes to water quality it is considered appropriate at this stage to review changes in water quality trends rather than apply strict control and trigger levels .
If control and trigger levels are to be applied then they should be relatively broad at this time.

Horizon Consulting Engineers Ltd.

Tresco House,
Westpoint Court
Sidmouth Road
Exeter
EX5 1DJ

Tel : 01392 363364
www.horizon-ce.co.uk