

Phase 2: Site Investigation

MF6 Building, Fujifilm

Fujifilm

S220451

Solmek Ltd

12 Yarm Road
Stockton-on-Tees
TS18 3NA
Tel: 01642 607083

www.solmek.com

info@solmek.com



PHASE 2 SITE INVESTIGATION REPORT



MF6 BUILDING, FUJIFILM

TABLE OF CONTENTS

1	EXECUTIVE SUMMARY	2
2	INTRODUCTION	3
3	SITE DESCRIPTION AND FIELDWORK	3
4	GROUND CONDITIONS	4
5	CONTAMINATION TESTING RESULTS	5
6	CONCEPTUAL MODEL AND CONTAMINATION ANALYSIS.....	9
7	GROUND GAS ASSESSMENT.....	11
8	GEOTECHNICAL TESTING AND ANALYSIS.....	11
TABLE 1: SUMMARY OF GROUNDWATER STRIKES		5
TABLE 2: SUMMARY OF INORGANIC CONTAMINATION TESTING RESULTS.....		6
TABLE 3: SUMMARY OF ORGANIC CONTAMINATION TESTING RESULTS		7
TABLE 4: SUMMARY OF LEACHATE CONTAMINATION TESTING RESULTS.....		8

APPENDICES

Appendix A:	Drawings
Appendix B:	Borehole Logs
Appendix C:	Contamination Laboratory Results
Appendix D:	Geotechnical Laboratory Results
Appendix E:	Notes on Limitations & Contamination Guidelines

Revision	Date	Prepared By	Signed
Final	June 2022	L Cassidy <i>Senior Environmental Engineer</i>	
		Checked By	
		A Lowry <i>Consultant</i>	<i>A Lowry</i>
		Approved By	
		R Woods <i>Principal Geotechnical Engineer</i>	

1 EXECUTIVE SUMMARY

Site Address	MF6 Building, Fujifilm
Proposed Development	The site is outlined for an industrial development.
Fieldwork	<ul style="list-style-type: none"> • 3no cable percussive boreholes (BH01 to BH03) drilled to a maximum of 20.00mbgl with 2no. monitoring pipes in BH01 and BH03.
Ground Conditions	<ul style="list-style-type: none"> • Made ground was encountered to depths of between 0.90mbgl and 1.90mbgl. • Soft becoming firm to stiff sandy gravelly low improving to medium to high strength clay encountered to between 9.55 and 11.55mbgl. • Cohesive deposits underlain by medium dense to very dense sandy gravel/gravelly. • In BH01 only, sandy silty clay overlying clayey silt was encountered at the base of the granular deposits. • Groundwater was noted between 15.00m and 17.00mbgl.
Contamination Testing Results	<ul style="list-style-type: none"> • Four made ground samples tested. • No exceedances recorded. • No asbestos fibres encountered. • 2no leachate samples tested with no exceedances recorded. • Slightly alkaline pH.
Contamination Analysis	<ul style="list-style-type: none"> • Given the site's proposed commercial land use, the levels of contamination recorded on site are unlikely to pose a risk to the current and future users of the site. • If any zones of odorous, brightly coloured or suspected contaminated ground or groundwater are encountered then work should cease in that area until the material has been investigated. The results of the investigation will therefore determine whether or not remediation will be required. • Made ground classed as posing a low risk with respect to construction workers. PPE for workers. Damping down of site during dry windy conditions. • With respect to utilities pH was elevated; as a minimum all services should be laid in clean trenches. • Sub surface concrete should be designed to DS-1 ACEC (Class AC-1s). This assumes static groundwater conditions.
Geotechnical Testing Results	<ul style="list-style-type: none"> • Cohesive deposits low to high strength based on triaxial testing (26kPa-259kPa) and SPT N values. • Granular deposits dense to very dense based on SPT N values. • Cohesive materials on site have a medium volume change potential. • Moisture contents between 16 and 30%. • Sulphates between 20-150mg/l, pH slightly alkaline.
Geotechnical Analysis & Foundation Recommendations	<ul style="list-style-type: none"> • Piled foundations recommended – this report should be made available to a competent piling contractor. • Normal earthworks plant for excavations.

2 INTRODUCTION

2.1 Authorisation

The site investigation described in this report was carried out by Solmek to the instructions of Fujifilm, on land located at Fujifilm, Billingham.

2.2 Scope of Works

The site is expected to be developed with new industrial buildings within the existing Fujifilm site.

The following steps may be required in the investigation and remediation of potentially contaminated land:

- Phase 1: Desk Study
- Phase 2: Intrusive Investigation
- Phase 3: Remediation Statement
- Phase 4: Validation Reports

Phases 1 and 2 are generally required in the redevelopment of most sites. Phases 3 and 4 are subject to the findings of the initial stages.

A Phase 1 Desk Study was not requested.

A geotechnical and environmental (Phase 2) investigation including a ground gas risk assessment was requested. The fieldwork and testing was generally carried out according to;

- BS 5930:2015+A1:2020 Code of Practice for Ground Investigations
- BS 10175:2011+A1:2013 Investigation of Potentially Contaminated Sites – Code of Practice.
- CIRIA C665:2007 Assessing Risks Posed by Hazardous Ground Gas to Buildings
- BS 8485:2015+A1:2019 Code of Practice for the Characterization and Remediation from Ground Gas in Affected Developments
- Rock and soil descriptions shall be in accordance with BS EN ISO 14689-1:2003, BS EN ISO 14688-1:2002 and BS EN ISO 14688-2:2004

This report forms part of a Stage 1 Risk Assessment (Generic Quantitative Risk Assessment) with respect to the Environment Agency's guidance document Environment Agency *Land Contamination Risk Management*, which replaced the now-withdrawn *Contaminated Land Report 11 – Model Procedures for the Management of Land Contamination (2004)*.

The information provided in this report is based on the investigation fieldwork and is subject to the comments and approval of the various regulatory authorities. There may be other conditions prevailing on the site which have not been disclosed by this investigation and which have not been taken into account by this report. Solmek reserve the right to alter conclusions and recommendations should further information be available or provided. Any schematic representation or opinion of the possible configuration of ground conditions between exploratory holes is conjectural and given for guidance only and confirmation of intermediate ground conditions should be considered if deemed necessary.

3 SITE DESCRIPTION AND FIELDWORK

A site inspection, as recommended in BS 5930 and BS 10175, was undertaken on Tuesday 6th September 2021. The site is centred at Ordnance Survey Co-ordinates 446649, 522649 and covers approximately 0.13Ha.

The site is a rectangular shaped parcel of land of level topography located within the existing Fujifilm complex, currently partly occupied by cabin offices, with the remainder of the site having a gravelled surfacing.

The surrounding areas of the site are predominantly industrial.

3.1 Fieldwork

The fieldwork was carried out on 10th May 2022. The extent of the investigation was:

- 3no cable percussive boreholes (BH01 to BH03 inclusive) to a maximum depth of 20.00m below ground level (bgl).
 - The boreholes were evenly spread around the site to achieve maximum site coverage.
- Gas monitoring wells were installed in BH's 01 & 03.
 - The wells were spaced at <25m centres evenly around the site
- Insitu testing in the exploratory positions as Standard Penetration Tests (SPTs) and hand shear vanes.
- Retrieval of samples for geotechnical and chemical testing.

The boreholes were backfilled bentonite/installations upon completion.

Descriptions of the strata encountered in the boreholes together with details of sampling and groundwater are presented in Appendix B of this report. A plan showing the location of the boreholes can be found in Appendix A (Figure 2).

4 GROUND CONDITIONS

A summary of the ground conditions encountered is given below.

4.1 Made Ground

Made ground was relatively uniform across the site and was encountered to a minimum depth of 0.90mbgl and a maximum depth of 1.90mbgl. The made ground broadly consisted of a surface covering of gravel underlain by concrete (0.15-0.30m thick).

The concrete was in turn underlain by further made ground, variably comprising sandy gravelly clay or granular made ground.

4.2 Natural Deposits

Proven to underlie the made ground deposits across the site, natural ground initially comprised soft improving to firm to stiff sandy gravelly low improving to medium to high strength clay, proven to depths of between 9.15 & 11.55mbgl. At shallow depths the clay was generally noted as silty.

Granular deposits were then encountered, comprising dense to very dense gravelly sands and sandy gravels. BH02 & BH03 terminated within this strata however, within BH01 a band of sandy medium strength silty clay was encountered from 17.00-19.20mbgl, underlain by clayey silt to a termination depth of 20.00mbgl.

4.3 Groundwater

Groundwater strikes, where encountered, are presented on the exploratory logs (Appendix B) and are summarised below in Table 1:

TABLE 1: SUMMARY OF GROUNDWATER STRIKES

Exploratory Position	Depth Encountered (mbgl)	Depth after 20 minutes (mbgl)	Strata
BH01	15.20	-	Sand
	17.00	-	Sand
BH02	15.00	-	Sand
	16.20	16.00	Gravel
BH03	15.30	14.70	Gravel

It should be noted the rapid rate of advancement of the exploratory holes may mask minor seepages and it should be borne in mind that water levels fluctuate with a number of influences including season, rainfall, dewatering and pumping activities. Therefore, water levels significantly higher than those found during this investigation may be encountered.

5 CONTAMINATION TESTING RESULTS

The proposed development of the site is to involve the construction of industrial buildings. The chemical samples were generally retrieved in line with BS ISO 18400-105:2017 *Soil Quality. Sampling*. The chemical results are presented in Appendix C.

5.1 Contamination Testing and Rationale

To provide information upon the possibility of ground contamination four samples of made ground were selected for shallow contamination testing. Given the commercial current and proposed use, four samples are considered appropriate for testing. The samples selected are detailed below:

- BH01 – 0.30-0.40m (Made ground – cohesive)
- BH02 – 0.30-0.40m (Made ground – granular)
- BH02 – 1.20-1.40m (Made ground – granular)
- BH03 – 0.40-0.50m (Made ground – granular)

The samples selected are considered to provide coverage of the made ground strata from across the site that would be most likely to be exposed during future site works. The samples were tested for the following contaminant suites:

- 4no Metals, semi-metals, non-metals, inorganic determinants
- 4no Asbestos identification screenings
- 4no Speciated Polycyclic Aromatic Hydrocarbons (PAHs)
- 2no Total Petroleum Hydrocarbon Criteria Working Group fractions (TPHCWG)

Leachate analysis was also undertaken on the below samples:

- BH01 – 0.30-0.40m (Made ground – cohesive)
- BH03 – 0.40-0.50m (Made ground – granular)

5.2 Test Results

Based on the proposed development at the site, the test results have been compared to a series of Land Quality Management (LQM) Suitable for Use Levels (S4UL) based on a Commercial land use. These are the most up to date thresholds published in December 2014.

The value for lead has been compared with the Category 4 Screening Level (March 2014) developed by Contaminated Land: Applications In Real Environments (CL:AIRE).

The test results are presented in Appendix C, and a summary is provided below in Tables 2 and 3.

TABLE 2: SUMMARY OF INORGANIC CONTAMINATION TESTING RESULTS

Determinand	Units	Number of Samples above Level of Detection	Minimum Recorded Level	Maximum Recorded Level	Commercial Threshold Value	Number of Results Exceeding Threshold Value
Metals						
Cadmium	mg/kg	1	<0.1	0.4	190	0
Chromium	mg/kg	4	8	16	8600	0
Copper	mg/kg	4	8.1	10	68000	0
Lead	mg/kg	4	12	22	2300*	0
Mercury	mg/kg	1	<0.1	0.2	1100	0
Nickel	mg/kg	4	8.1	17	980	0
Zinc	mg/kg	4	30	40	730000	0
Semi metals and non metals						
Arsenic	mg/kg	4	3	3.8	640**	0
Boron	mg/kg	3	0.4	0.8	240000	0
Selenium	mg/kg	4	0.37	0.68	12000	0
Inorganic chemicals						
Cyanide (Total)	mg/kg	0	<0.5	-	1580**	0
Sulphate (2:1 Water Soluble)	mg/l	3	<10	150	2000^	0
Other						
pH	pH	-	8.5	9.5	5.5^	0
* Category 4 Screening Levels, March 2014						
** CLEA Software Version 1.06 (pH7 and 1%SOM)						
^ EA Threshold Values						

5.3 Metals, Semi Metals and Non Metals

No samples indicated raised levels of contamination above the S4UL threshold values, based on the two samples tested.

5.4 Inorganic Chemicals

Soluble sulphates (potentially aggressive to foundation concrete) were recorded between <10 and 150mg/l. None of the samples were elevated above levels affecting human health or the BRE Special Digest 1 500mg/l limit for the sulphate classification of concrete.

The results of the pH testing were between 8.5 and 9.5, which is consistent with slightly alkaline conditions.

5.5 Organic Chemicals

The organic thresholds vary depending on the levels of soil organic matter (SOM).

The average SOM recorded across the site was 1.61% therefore a SOM of 6% has been used to determine the S4UL thresholds. Table 3, below, summarises the results.

TABLE 3: SUMMARY OF ORGANIC CONTAMINATION TESTING RESULTS

Determinand	Units	Number of Samples above Level of Detection	Minimum Recorded Level	Maximum Recorded Level	Commercial Threshold Value at 1% SOM	Number of Results Exceeding Threshold Value
TPH Aliphatic Fractions						
Aliphatic (C5-C6)	mg/kg	0	<1	-	3200	0
Aliphatic (C6-C8)	mg/kg	0	<1	-	77800	0
Aliphatic (C8-C10)	mg/kg	0	<1	-	2000	0
Aliphatic (C10-C12)	mg/kg	0	<1	-	9700	0
Aliphatic (C12-C16)	mg/kg	0	<1	-	59000	0
Aliphatic (C16-C21)	mg/kg	0	<1	-	1600000	0
Aliphatic (C21-C35)	mg/kg	0	<1	-	1600000	0
Aliphatic (C35-C44)	mg/kg	0	<1	-	1600000	0
TPH Aromatic Fractions						
Aromatic (C5-C7)	mg/kg	0	<1	-	26000	0
Aromatic (C7-C8)	mg/kg	0	<1	-	56000	0
Aromatic (C8-C10)	mg/kg	0	<1	-	3500	0
Aromatic (C10-C12)	mg/kg	0	<1	-	16000	0
Aromatic (C12-C16)	mg/kg	0	<1	-	36000	0
Aromatic (C16-C21)	mg/kg	0	<1	-	28000	0
Aromatic (C21-C35)	mg/kg	0	<1	-	28000	0
Aromatic (C35-C44)	mg/kg	0	<1	-	28000	0
Speciated PAH						
Naphthalene	mg/kg	0	<0.1	-	190	0
Acenaphthylene	mg/kg	0	<0.1	-	83000	0
Acenaphthene	mg/kg	0	<0.1	-	84000	0
Fluorene	mg/kg	0	<0.1	-	63000	0
Phenanthrene	mg/kg	0	<0.1	-	22000	0
Anthracene	mg/kg	0	<0.1	-	520000	0
Fluoranthene	mg/kg	1	<0.1	0.11	23000	0
Pyrene	mg/kg	1	<0.1	0.14	54000	0
Benzo[a]anthracene	mg/kg	0	<0.1	-	170	0
Chrysene	mg/kg	0	<0.1	-	350	0
Benzo[b]fluoranthene	mg/kg	0	<0.1	-	44	0
Benzo[k]fluoranthene	mg/kg	0	<0.1	-	1200	0
Benzo[a]pyrene	mg/kg	0	<0.1	-	35	0
Benzo[g,h,i]perylene	mg/kg	0	<0.1	-	3900	0
Dibenz(a,h)Anthracene	mg/kg	0	<0.1	-	3.5	0
Indeno(1,2,3-c,d)Pyrene	mg/kg	0	<0.1	-	500	0
Total PAH	mg/kg	0	<2	-	1000*	0
Total Phenol	mg/kg	0	<0.3	-	760	0
* EA Threshold Values						

No samples indicated raised levels of contamination above the S4UL threshold values, based on the two samples tested.

5.6 Asbestos

From the four samples subject to asbestos screening, no asbestos fibres were recorded in any of the samples.

5.7 Leachates

Two samples have been subject to leachate testing. The results have been compared, where available, to UK Drinking Water Standards (DWS), otherwise EA Leachate Quality Thresholds and WHO Guidelines (2005) have been used. Results are summarised within Table 4 below.

TABLE 4: SUMMARY OF LEACHATE CONTAMINATION TESTING RESULTS

Determinand	Units	Number of Samples above Level of Detection	Minimum Recorded Level	Maximum Recorded Level	UK Drinking Water Standards	Number of Results Exceeding Threshold Value
Inorganic Contaminants						
Boron	µg/l	2	130	140	2000	0
Cadmium	µg/l	0	<0.11	-	5	0
Chromium	µg/l	2	7.6	9.4	50	0
Copper	µg/l	2	8.0	8.8	2000	0
Lead	µg/l	2	5.8	11	25	0
Mercury	µg/l	0	<0.05	-	1	0
Nickel	µg/l	2	1.7	3.1	20	0
Zinc	µg/l	2	65	80	5000	0
Arsenic	µg/l	2	1.8	3.4	10	0
Selenium	µg/l	2	4.1	8.7	10	0
Cyanide	µg/l	0	<0.05	-	50	0
pH	pH	-	10.6	10.9	5.5	0
W.S. Sulphate	mg/l	2	1	33	250	0
PAH						
Acenaphthene	µg/l	0	<0.1	-	0.1	0
Acenaphthylene	µg/l	0	<0.1	-	0.1	0
Anthracene	µg/l	0	<0.1	-	0.1	0
Benzo[a]anthracene	µg/l	0	<0.1	-	0.1	0
Benzo[a]pyrene	µg/l	0	<0.1	-	0.1	0
Benzo[b]fluoranthene	µg/l	0	<0.1	-	0.1	0
Benzo[k]fluoranthene	µg/l	0	<0.1	-	0.1	0
Benzo[g,h,i]perylene	µg/l	0	<0.1	-	0.1	0
Chrysene	µg/l	0	<0.1	-	0.1	0
Dibenz(a,h)Anthracene	µg/l	0	<0.1	-	0.1	0
Fluoranthene	µg/l	0	<0.1	-	0.1	0
Fluorene	µg/l	0	<0.1	-	0.1	0
Indeno(1,2,3-c,d)Pyrene	µg/l	0	<0.1	-	0.1	0
Naphthalene	µg/l	0	<0.1	-	0.1	0
Phenanthrene	µg/l	0	<0.1	-	0.1	0
Pyrene	µg/l	0	<0.1	-	0.1	0
Total PAH	µg/l	0	<2	-	0.2**	0
Total Phenol	µg/l	0	<0.03	-	0.5*	0
TPH Aliphatic Fractions						
Aliphatic (C5-C6)	µg/l	0	<0.1	-	15000*	0
Aliphatic (C6-C8)	µg/l	0	<0.1	-	15000*	0
Aliphatic (C8-C10)	µg/l	0	<0.1	-	300*	0
Aliphatic (C10-C12)	µg/l	0	<0.1	-	300*	0
Aliphatic (C12-C16)	µg/l	0	<0.1	-	300*	0
Aliphatic (C16-C35)	µg/l	0	<0.1	-	300*	0
Aliphatic (C16-C35)	µg/l	0	<0.1	-	300*	0
Aliphatic (C35-C44)	µg/l	0	<0.1	-	300*	0
TPH Aromatic Fractions						
Aromatic (C5-C7)	µg/l	0	<0.1	-	10*	0
Aromatic (C7-C8)	µg/l	0	<0.1	-	10*	0
Aromatic (C8-C10)	µg/l	0	<0.1	-	100*	0
Aromatic (C10-C12)	µg/l	0	<0.1	-	100*	0
Aromatic (C12-C16)	µg/l	0	<0.1	-	100*	0
Aromatic (C16-C21)	µg/l	0	<0.1	-	90*	0
Aromatic (C21-C35)	µg/l	0	<0.1	-	90*	0
Aromatic (C35-C44)	µg/l	0	<0.1	-	90*	0
* WHO Guidelines 2005 ** EA leachate quality thresholds *** EQS Freshwater						

From the two samples tested for leachates, no exceedances were recorded.

5.8 Environmental Protection Act 1990: Part 2A Revised Statutory Guidance (April 2012)

This revised document explains how the Local Authority should decide if land, based on a legal interpretation, is contaminated. The document replaces the previous guidance given in Annex 3 of DEFRA Circular 01/2006, issued in accordance with section 78YA of the 1990 Environmental Protection Act.

The main objectives of the Part 2A regime are to *“identify and remove unacceptable risks to human health and the environment”* and to *“seek to ensure that contaminated land is made suitable for its current use”*. Part 2A uses a risk based approach to defining contaminated land whereby the “risk” is interpreted as *“the likelihood that harm, or pollution of water, will occur as a result of contaminants in, on or under the land”* and by *“the scale and seriousness of such harm or pollution if it did occur”*.

For a relevant risk to exist a contaminant, pathway and receptor linkage must be present before the land can be considered to be contaminated. The document explains that *“for a risk to exist there must be contaminants present in, on or under the land in a form and quantity that poses a hazard, and one or more pathways by which they might significantly harm people, the environment, or property; or significantly pollute controlled waters.”*

A conceptual model is used to develop and communicate the risks associated with a particular site.

To determine if land is contaminated the local authority use various categories from 1 to 4. Categories 1 and 2 include *“land which is capable of being determined as contaminated land on grounds of significant possibility of significant harm to human health.”* Categories 3 and 4 *“encompass land which is not capable of being determined on such grounds”*.

See Appendix E for additional notes on contamination guidelines.

6 CONTAMINATION ANALYSIS

6.1 Users of the Site Once Development is Complete

The users of the site, particularly construction workers, are likely to be exposed to contaminants present in the soils beneath the site during redevelopment work. **Potential** exposure pathways include dermal absorption after contact with contaminated ground, inhalation of soil or dust, inhalation of volatised compounds, and inadvertent soil ingestion.

To establish if the levels of contaminants present on site may pose a risk to the health of the future users of the site the results of the contamination testing have been compared to a series of LQM/CIEH S4UL based on a Commercial land-use.

The levels of contaminants across the site are generally low with no exceedances of the relevant thresholds.

The new development is expected to comprise new industrial buildings. Based on the **shallow** soil contamination testing, it is considered that the levels of contamination are unlikely to pose a risk to future users of the site.

6.2 Construction Workers and Users of Surrounding Sites

Short term human exposure to contaminants present in soils can occur via several pathways during the construction and ground works phase of the development. These include dermal absorption after contact with contaminated ground, inhalation of soil or dust (including windblown dust), inhalation of volatised compounds, inadvertent soil ingestion and contact with contaminated groundwater.

It is considered that the encountered levels of contamination are unlikely to pose a risk to construction workers and users of surrounding sites. As good practice, full PPE must be employed in accordance with Health and Safety Executive: *Protection of Workers and the General Public During the Development of Contaminated Land* and safeguards should be taken to limit dust during ground works, and access to the public should be restricted. Construction workers should use gloves as a precaution when handling any fill materials. Provision of suitable hygiene facilities are needed for site workers. Wheel washers should be provided and used for any vehicle entering or leaving site to prevent cross contamination.

Although asbestos was not detected from the soil samples subjected to testing within this investigation, the possibility still exists that asbestos containing materials may still be present on site and currently lie undetected. It is therefore advised that a 'watching brief' is undertaken during the initial site strip and any excavation works and advice sought if asbestos is found or suspected.

During dry weather, any excavations may require clean water to be sprinkled at shallow depth to prevent excess dust escaping to off-site receptors. Monitoring of dust concentrations during construction should be given careful consideration to ensure Monitoring of dust concentrations during construction should be given careful consideration to ensure occupational exposure levels are not exceeded. A moisture content of >15% is required to inhibit dust migration. Works should be undertaken in line with BRE: *The Control of Dust and Emissions from Construction and Demolition, Best Practice Guidance*.

6.3 Vegetation

Plants can be affected by soil contamination in a number of ways resulting in growth inhibition, nutrient deficiencies and yellowing of leaves. Contaminants are taken up by plants through the roots and through foliage. Contaminants identified as being highly phytotoxic include boron, cadmium, copper, nickel, and zinc.

For this development, no vegetation is proposed therefore vegetation is not considered to be a sensitive receptor.

6.4 Ground and Surface Water

The principal pathway by which soil contamination may reach the water environment is through a slow seepage or leaching to groundwater or surface water. The potential for contaminants to migrate along such pathways is dependent on the chemical and physical characteristics of the contaminants and the local hydrogeology.

A Phase 1 Desk Study has not been undertaken therefore a full risk assessment for controlled waters cannot be undertaken.

From the site investigation undertaken, ground conditions broadly comprise thin made ground (<1.90m) over drift deposits initially comprising low permeability clays, with higher permeability granular deposits at depth.

From the 4no soil samples and 2no leachate samples tested, no exceedances have been recorded.

Due to the generally low contamination found across the site, the low permeability deposits underlying the site and the distance to surface waters, the development is considered to represent a low risk to groundwater or surface water receptors.

6.5 Construction Materials

Materials at risk from potential soil contamination include inorganic matrices such as cement and concrete and also organic material; e.g. plastics and rubbers. Acid ground conditions and elevated levels of sulphates can accelerate the corrosion of building materials. Plastics and rubbers are generally used for piping and service ducts and are potentially attacked by a range of chemicals, most of which are organic, particularly petroleum-based substances. Drinking water supplies can be tainted by substances that can penetrate piping and water companies enforce stringent threshold values.

6.5.1 Concrete Classification

BRE Special Digest One: *Concrete in Aggressive Ground*: 2005 3rd Edition has been used to assess the risks posed to underground concrete and to establish the design measures required to mitigate the risks. The results of the pH and water-soluble sulphate tests (when converted to total potential sulphate) fall into Class DS-1 ACEC (Class AC-1s) requirements for concrete protection. This assumes static groundwater conditions.

6.5.2 Water Supply Pipes Material Selection

The levels of potential contaminants should be compared to thresholds supplied in the UK Water Industry Research (UKWIR) publication *Guidance for the selection of Water Supply Pipes to be used in Brownfield*

Sites (January 2011). A Brownfield Site is defined in the document as “Land or premises that have previously been used or developed that may be vacant or derelict”. It should be noted that Brownfield sites may not be contaminated. The guidance does not apply to Greenfield Sites however water companies may have their own assessment criteria which should be checked by the developer.

Level of acidic to alkaline pH (8.5 to 9.5) were recorded across the site at depths of between 0.30mbgl and 18.45mbgl within the made ground and natural samples.

The concentrations of the selected determinants should be compared to the pipe material selection table in Appendix E, and consultation with the appropriate utility supply company is required to identify the most suitable service fabric. However, the pH levels preclude the use of copper pipes.

6.6 Unexpected Contamination

If during the initial site strip or subsequent ongoing construction activities, any zones of odorous, brightly coloured or suspected contaminated ground are encountered, then the following procedure should be followed:

- Stop work in the affected area
- Contact Solmek and provide pictures of the affected area
- Solmek can visit site to investigate the material and provide guidance
- If required – Solmek can sample and test the material
- Once test results are returned, this will determine whether or not remediation will be required

6.7 Waste Classification and WAC Testing

During the site strip and construction activities, material may be required to be removed from site. Any such material would require classification, in line with Environment Agency Technical Guidance *Waste Classification: Guidance on the classification and assessment of waste* (2015). This would classify the material as either Non-Hazardous or Hazardous Waste.

Once the material has been classified, determining the suitable landfill for disposal is governed by landfill directive Waste Acceptance Criteria (WAC) testing, with landfills categorized as Inert Waste, Stable Non-Reactive Hazardous Waste and Hazardous Waste.

If waste classification and/or WAC testing are not undertaken, material taken off site may be subject to WAC testing by the appropriate waste disposal company. The decision on whether or not to accept waste, or whether further testing is required, is at the discretion of the waste disposal company.

For this project, Waste Classification has not been requested by the client. Waste classification, in line with the aforementioned EA guidance, would be needed to classify the material as Hazardous or Non-Hazardous Waste. WAC testing would then be required to determine the suitability of the material for the relevant landfill.

7 GROUND GAS ASSESSMENT

The proposed development includes the construction of an industrial building.

Ground gases such as carbon dioxide (CO₂), methane (CH₄), carbon monoxide (CO) and volatile organic compounds (VOCs) can be classed as a form of contamination where there is a potential risk to human health.

For this report, gas monitoring is via measuring emissions from two standpipes (BH01 & BH03) that were installed during the sitework. The gas monitoring will consist of six visits over a period of three months. The gas monitoring results will be presented as an addendum to this report.

8 GEOTECHNICAL TESTING AND ANALYSIS

Samples taken from the boreholes underwent a series of geotechnical tests (BS 1377:1990) to aid foundation design and soil description. In addition, insitu Standard Penetration Tests (SPTs) were undertaken at regular intervals during drilling. The geotechnical results are presented in Appendix D.

8.1 Strength and Density

8.1.1 Undisturbed Triaxial Tests

Five U100 samples were subjected to undrained triaxial testing from BH01 (3.00m & 18.00m) BH02 (3.00m & 10.50m) and BH03 10.50m. The samples from BH01 (3.00m) & BH02 (10.50m) had to be subsampled to a U38 due to a poor recovery. The results ranged from 26kPa to 259kPa (low to high strength).

8.1.2 SPT N Values

Standard Penetration Tests undertaken within the natural cohesive deposits yielded N values of between 4 and 37, with these results indicating low becoming high strength deposits.

Standard Penetration Tests undertaken within the natural granular deposits yielded N values of between 30 and 50+, indicative of dense to very dense deposits.

8.2 Moisture Contents

Five samples recovered from the boreholes have been subject to moisture content tests to determine the moisture profile at depths of between 3.00 and 18.00mbgl. Moisture levels were between 16% and 30%.

8.3 Atterberg Limit Determinations

Four Atterberg Limit Determination tests were carried out on samples of cohesive material to classify the fine grained soils. The results were compared to the Casagrande Chart published in BS 5930 and showed the samples to generally be clay/silt of low to high plasticity.

The Plasticity Indices ranged from 9 to 20 with equivalent moisture contents recorded above and below the corresponding plastic limits. The cohesive material can be assessed as having a **medium** shrinkage potential in relation to current guidance.

8.4 Particle Size Distribution Testing

One sample from the boreholes was subject to a Particle Size Distribution (PSD) test in accordance with BS1377 Part 2 to aid soil descriptions. The results have been used to prepare precise soil descriptions in accordance with BS5930:2015 Section 6 and are presented in Appendix D.

8.5 pH and Sulphate Results

Three natural samples from the boreholes were tested for acidity and soluble sulphate content to assess whether the material may be potentially aggressive to building fabric. The results of the testing for pH ranged from 9.0 to 9.3 indicating slightly alkaline conditions. Soluble sulphates were recorded at levels ranging from 20mg/l to 150mg/l.

8.6 Foundations

8.6.1 Piled Foundations

It is understood the proposed building will be piled. Information provided in this report should be made available to a competent piling contractor who can design appropriate foundations in accordance with Section 7: Pile foundations of BS EN 1997 – 1:2004 which applies to end-bearing piles, friction piles, tension piles and transversely loaded piles installed by driving, by jacking, and by screwing or boring. The piling contractor will need to take into consideration the possible effects of negative skin friction from made ground and soft deposits. Allowance should be made for breaking through known and unknown buried obstructions, including buried concrete.

Given the close proximity of sensitive industrial land use in the area it is likely a bored CFA piled would be required. Consultation with Fujifilm is recommended prior to installing any piled foundations to determine limits of ground vibration/disturbance when installing the piles. In addition, consideration should be given to the amount and type of waste produced from CFA piling operations on the site and the safe disposal of

potentially contaminative arisings.

The precise method of pile installation and the applicability of proprietary systems, diameters and depths required would need to be determined by a specialist piling contractor.

8.6.2 *Ground Slabs*

Made ground is in excess of 600mm and a suspended or piled reinforced ground slab should therefore be used.

8.7 **Excavation**

Based on the nature of the ground conditions encountered, excavations should be within the capacity of normal earthworks plant although breaking out of buried concrete and other obstructions should be anticipated, whilst its noted that chiselling was required to advance BHs 02 & 03. Stability of excavations will be poor in the made ground but should improve in the natural clay. Excavation sides should be designed, constructed and supported in accordance with the recommendations given in CIRIA Report No. 97: *Trenching Practice*.

8.8 **Groundwater**

Groundwater was encountered within the three boreholes between 15.00 and 17.00mbgl.

It should be noted the rapid rate of advancement of the exploratory holes may mask minor seepages and it should be borne in mind that water levels fluctuate with a number of influences including season, rainfall, dewatering and pumping activities. Therefore, water levels significantly higher than those found during this investigation may be encountered.

SOLMEK

**APPENDIX A:
Figures and Drawings**



12-16 Yarm Road, Stockton on Tees, TS18 3NA
 Tel: 01642 607083 Email: info@solmek.com

Figure Title
Site Location Plan
Project Number
S220451
Project Name
MF6 Building, Fujifilm, Billingham
Client
Fujifilm
Date
June 2022
DRG Number
Figure 1
Scale
1:2000 @ A4 [DO NOT SCALE]

Legend Key

 Project Bounds - Project Bounds



12-16 Yarm Road, Stockton on Tees, TS18 3NA
Tel: 01642 607083 Email: info@solmek.com

Figure Title

Exploratory Hole Location Plan

Project Number

S220451

Project Name

MF6 Building, Fujifilm, Billingham

Client

Fujifilm

Date

June 2022




DRG Number

Figure 2

Scale

1:500 @ A4 [DO NOT SCALE]

Legend Key

-  Locations By Type - Empty
-  Locations By Type - BH
-  Project Bounds - Project Bounds

APPENDIX B: Borehole Logs



12-16 Yarm Road
Stockton on Tees
TS18 3NA
01642 607083
info@solmek.com

Borehole Log

Scale 1:50 Sheet 1 of 2

BH01

Contract no: S220451	Site: MF6 Building, Fujifilm, Billingham	Driller: BBL	GL (AOD):
Client: Fujifilm		Plant used: Dando 2000	Eastings: 446627
Method: Cable percussive		Started: 10/05/2022	Northing: 522625
		Ended: 10/05/2022	Logged: SM
		Backfilled: 10/05/2022	Status: FINAL



Backfill / Installation	Legend	Depth (m)	Level (m AOD)	Stratum Description	Samples and Insitu Testing		
					Depth (m)	Type	Results
		0.10		MADE GROUND: Decorative 20mm gravel. Gravel is coarse subangular to rounded of mixed lithologies.			
		0.25		MADE GROUND: Concrete.	0.30	B	
				MADE GROUND: Dark greenish brown sandy gravelly clay. Sand is medium to coarse grained. Gravel is subangular to subrounded, fine to coarse of red brick, concrete, dolomite, hardcore and quartz.	0.30 - 0.40	ES	
					0.60 - 0.80	ES	
		0.80		MADE GROUND: Black slightly clayey silty slightly gravelly sand. Sand is medium to coarse grained, gravel is subangular to subrounded, fine to coarse of concrete, mudstone and quartz.	0.90	B	
				MADE GROUND: Black slightly clayey silty slightly gravelly sand. Sand is medium to coarse grained, gravel is subangular to subrounded, fine to coarse of concrete, mudstone and quartz.	0.90 - 1.00	ES	
		1.20		Soft to firm light brown sandy slightly gravelly low strength CLAY. Sand is medium to coarse grained. Gravel is subangular to subrounded, fine to coarse of sandstone, mudstone and quartz.	1.20 - 1.65	SPT (S)	N=4 (1,1/1,1,1,1)
					1.20 - 1.65	B+D	
					1.40 - 1.60	ES	
					2.00 - 2.45	SPT (S)	N=5 (1,1/1,1,1,2)
					2.00 - 2.45	B+D	
		2.90		Firm becoming stiff dark brown mottled grey thinly laminated slightly sandy slightly gravelly low to medium strength silty CLAY of intermediate plasticity. Sand is medium to coarse grained, gravel is subangular to subrounded, fine to medium of sandstone, mudstone and quartz.	3.00 - 3.45	U	39 blows [450mm]
					3.45 - 3.50	D	
					4.00 - 4.45	SPT (S)	N=8 (1,1/2,2,1,3)
					4.00 - 4.45	B+D	
					5.00 - 5.45	U	42 blows [450mm]
					5.45 - 5.50	D	
					6.00 - 6.45	SPT (S)	N=10 (1,1/2,2,3,3)
					6.00 - 6.45	B+D	
					7.50 - 7.95	U	46 blows [450mm]
					7.95 - 8.00	D	
		8.05		Stiff to very stiff dark brown slightly sandy slightly gravelly CLAY. Sand is fine to medium grained, gravel is subangular to subrounded, fine to medium of mudstone, siltstone, sandstone and quartz.			
					9.00 - 9.45	SPT (S)	N=50+
				Very dense dark reddish brown silty slightly gravelly SAND, with occasional clay lenses. Sand is medium to coarse grained, gravel is angular to subrounded, fine to medium of sandstone, mudstone and quartz.	9.00 - 9.45	B+D	(4,9/17,18,15,15)

Hole Diameter				Casing Depths				General Remarks			Chiselling			Ground Water				
Depth Base (m)	Diameter (mm)	Depth Base (m)	Diameter (mm)	From (m)			To (m)	Time (hr)	Depth Strike (m)	Depth Casing (m)	Depth Sealed (m)	Time Elapsed (min)	Water Level (m)					
20.00	150	19.50	150	1.2m hand excavated inspection pit dug.					15.20									
				Groundwater encountered at 15.2m					17.00									

Borehole Log

BH01

Contract no: S220451	Site: MF6 Building, Fujifilm, Billingham	Driller: BBL	GL (AOD):
Client: Fujifilm		Plant used: Dando 2000	Eastings: 446627
Method: Cable percussive		Started: 10/05/2022	Northing: 522625
		Ended: 10/05/2022	Logged: SM
		Backfilled: 10/05/2022	Status: FINAL

Backfill / Installation	Legend	Depth (m)	Level (m AOD)	Stratum Description	Samples and Insitu Testing		
					Depth (m)	Type	Results
		10.50 - 10.95		Very dense dark reddish brown silty slightly gravelly SAND, with occasional clay lenses. Sand is medium to coarse grained, gravel is angular to subrounded, fine to medium of sandstone, mudstone and quartz.	10.50 - 10.95	SPT (S) B+D	N=50+ (9,12/20,21,9,10)
					12.00 - 12.45	SPT (S) B+D	N=50+ (10,15/20,22,8,10)
					13.50 - 13.95	SPT (S) B+D	N=50+ (8,13/18,19,13,25)
					15.00 - 15.45	SPT (S) B+D	N=50+ (10,15/20,20,10,50)
					16.50 - 16.95	SPT (S) B+D	N=50+ (9,14/17,17,16,60)
		17.00		Stiff dark brown sandy silty medium strength CLAY of low plasticity. Sand is fine to medium coarse grained.	18.00 - 18.45	B U	115 blows [450mm]
		19.20		Soft to firm dark brown sandy high strength clayey SILT. Sand is medium to coarse grained.	19.50 - 19.95	SPT (S) B+D	N=22 (3,4/5,5,6,6)
		20.00		End of Borehole at 20.000m			

Hole Diameter				Casing Depths				General Remarks			Chiselling			Ground Water			
Depth Base (m)	Diameter (mm)	Depth Base (m)	Diameter (mm)	1.2m hand excavated inspection pit dug. Groundwater encountered at 15.2m			From (m)	To (m)	Time (hr)	Depth Strike (m)	Depth Casing (m)	Depth Sealed (m)	Time Elapsed (min)	Water Level (m)			
20.00	150	19.50	150							15.20 17.00							



12-16 Yarm Road
Stockton on Tees
TS18 3NA
01642 607083
info@solmek.com

Borehole Log

Scale 1:50 Sheet 1 of 2

BH02

Contract no: S220451	Site: MF6 Building, Fujifilm, Billingham	Driller: BBL	GL (AOD):
Client: Fujifilm		Plant used: Dando 2000	Easting: 446673
Method: Cable percussive		Started: 10/05/2022	Northing: 522653
		Ended: 11/05/2022	Logged: SM
		Backfilled: 11/05/2022	Status: FINAL

Backfill / Installation	Legend	Depth (m)	Level (m AOD)	Stratum Description	Samples and Insitu Testing		
					Depth (m)	Type	Results
		0.15		MADE GROUND: Decorative 20mm gravel. Gravel is coarse subangular to rounded of mixed lithologies.			
		0.30		MADE GROUND: Concrete.	0.30 - 0.40	B+ES	
				MADE GROUND: Light greenish brown sandy slightly gravelly clay. Gravel is subangular to subrounded, fine to coarse of red brick, concrete, dolomite and quartz.	0.90 - 1.00	B+ES	
					1.20 - 1.65	SPT (S)	N=4 (1,1/1,1,1,1)
					1.20 - 1.40	B+D	
					1.20 - 1.65	B+ES	
		1.90		Soft to firm brown sandy slightly gravelly low strength CLAY. Sand is medium to coarse grained, gravel is subangular to subrounded, fine to coarse of sandstone, siltstone, mudstone and quartz.	2.00 - 2.45	SPT (S)	N=5 (1,1/1,1,1,2)
					2.00 - 2.45	B+D	
		2.80		Firm dark brown mottled grey thinly laminated slightly sandy slightly gravelly low to medium strength CLAY of high plasticity. Gravel is subangular to subrounded, fine to coarse of sandstone, mudstone, coal and quartz.	3.00 - 3.45	U	38 blows [450mm]
					3.45 - 3.50	D	
					4.00 - 4.45	SPT (S)	N=8 (2,2/2,2,2,2)
					4.00 - 4.45	B+D	
					5.00 - 5.45	U	42 blows [450mm]
					5.45 - 5.50	D	
					6.00 - 6.45	SPT (S)	N=10 (1,2/2,2,3,3)
					6.00 - 6.45	B+D	
					7.50 - 7.95	U	55 blows [450mm]
		7.90		Stiff brown slightly sandy slightly gravelly high strength CLAY of intermediate plasticity. Sand is fine to medium grained, gravel is subangular to subrounded, fine to coarse of sandstone, mudstone and quartz.	7.95 - 8.00	D	
					9.00 - 9.45	SPT (S)	N=37 (3,5/8,9,9,11)
					9.00 - 9.45	B+D	

Hole Diameter		Casing Depths		General Remarks	Chiselling			Ground Water				
Depth Base (m)	Diameter (mm)	Depth Base (m)	Diameter (mm)		From (m)	To (m)	Time (hr)	Depth Strike (m)	Depth Casing (m)	Depth Sealed (m)	Time Elapsed (min)	Water Level (m)
18.45	150	18.00	150	1.2m hand excavated inspection pit dug. Groundwater encountered at 15.0m	17.80	18.00	01:00	15.00 16.20			20	16.00

Borehole Log

BH02

Contract no: S220451	Site: MF6 Building, Fujifilm, Billingham	Driller: BBL	GL (AOD):
Client: Fujifilm		Plant used: Dando 2000	Eastings: 446673
Method: Cable percussive		Started: 10/05/2022	Northing: 522653
		Ended: 11/05/2022	Logged: SM
		Backfilled: 11/05/2022	Status: FINAL

Backfill / Installation	Legend	Depth (m)	Level (m AOD)	Stratum Description	Samples and Insitu Testing		
					Depth (m)	Type	Results
		11.55		Stiff brown slightly sandy slightly gravelly high strength CLAY of intermediate plasticity. Sand is fine to medium grained, gravel is subangular to subrounded, fine to coarse of sandstone, mudstone and quartz.	10.50 - 10.95	U	125 blows [450mm]
					10.95 - 11.00	B+D	
		13.50		Very dense light reddish brown silty slightly gravelly SAND. Sand is medium to coarse grained, gravel is subangular to subrounded, fine to coarse of coal, mudstone, sandstone and quartz.	12.00 - 12.45	SPT (S)	N=50+ (7,9/17,19,14,10)
					12.00 - 12.45	B+D	
		15.00		Dense light brown very gravelly SAND. Gravel is angular to subrounded, fine to coarse of sandstone, siltstone and quartz.	13.50 - 13.95	SPT (S)	N=30 (4,5/6,6,9,9)
					13.50 - 13.95	B+D	
		16.00		Very dense light brown gravelly SAND. Gravel is subangular to subrounded, fine to coarse of coal, siltstone, mudstone and quartz.	15.00 - 15.45	SPT (S)	N=50+ (6,12/17,17,16,25)
					15.00 - 15.45	B+D	
		18.00		Dense becoming very dense slightly sandy GRAVEL. Gravel is subangular to rounded, fine to coarse of mudstone, siltstone, sandstone and quartz.	16.50 - 16.95	SPT (S)	N=36 (4,6/9,9,9,9)
					16.50 - 16.95	B+D	
				End of Borehole at 18.000m	18.00 - 18.45	SPT (S)	N=50+ (10,15/31,19,20,20)
					18.00 - 18.45	B+D	

Hole Diameter				Casing Depths				General Remarks			Chiselling			Ground Water				
Depth Base (m)	Diameter (mm)	Depth Base (m)	Diameter (mm)				From (m)	To (m)	Time (hr)	Depth Strike (m)	Depth Casing (m)	Depth Sealed (m)	Time Elapsed (min)	Water Level (m)				
18.45	150	18.00	150	1.2m hand excavated inspection pit dug. Groundwater encountered at 15.0m			17.80	18.00	01:00	15.00 16.20			20	16.00				

Borehole Log

BH03

Contract no: S220451	Site: MF6 Building, Fujifilm, Billingham	Driller: BBL	GL (AOD):
Client: Fujifilm		Plant used: Dando 2000	Easting: 446658
Method: Cable percussive		Started: 12/05/2022	Northing: 522643
		Ended: 13/05/2022	Logged: SM
		Backfilled: 13/05/2022	Status: FINAL

Backfill / Installation	Legend	Depth (m)	Level (m AOD)	Stratum Description	Samples and Insitu Testing		
					Depth (m)	Type	Results
		0.10		MADE GROUND: Decorative 20mm gravel. Gravel is coarse subangular to rounded of mixed lithologies.			
		0.40		MADE GROUND: Concrete.	0.40 - 0.50	B+ES	
		0.90		MADE GROUND: Dark brown sandy gravel, with occasional clay partings. Gravel is angular to subrounded, fine to coarse of red brick, concrete, sandstone, mudstone and quartz.	0.90 - 1.00	B+ES	
				Soft light brown sandy slightly gravelly low to medium strength CLAY. Gravel is subangular to subrounded, fine to coarse of sandstone, mudstone and quartz.	1.20 - 1.65	SPT (S)	N=5 (1,1/1,1,1,2)
					1.20 - 1.65	B+D	
					2.00 - 2.45	SPT (S)	N=8 (1,1/2,2,2,2)
					2.00 - 2.45	B+D	
		2.80		Firm mottled grey thinly laminated slightly sandy slightly gravelly medium strength CLAY. Sand is fine to medium grained, gravel is subangular to subrounded, fine to coarse of mudstone, sandstone and quartz.	2.80 - 2.90	ES	
					3.00 - 3.45	U	31 blows [450mm]
					3.45 - 3.50	D	
					4.00 - 4.45	SPT (S)	N=9 (1,1/2,2,2,3)
					4.00 - 4.45	B+D	
					5.00 - 5.45	U	38 blows [450mm]
					5.45 - 5.50	D	
					6.00 - 6.45	SPT (S)	N=11 (2,2/2,3,3,3)
					6.00 - 6.45	B+D	
					7.50 - 7.95	U	42 blows [450mm]
					7.95 - 8.00	D	
		8.95		Stiff dark greyish brown slightly sandy slightly gravelly high strength CLAY. Gravel is subangular to subrounded, fine to coarse of sandstone, siltstone, mudstone and quartz.	9.00 - 9.45	SPT (S)	N=31 (3,4/4,8,9,10)
					9.00 - 9.45	B+D	

Hole Diameter				Casing Depths				General Remarks			Chiselling			Ground Water				
Depth Base (m)	Diameter (mm)	Depth Base (m)	Diameter (mm)	From (m)			To (m)			Time (hr)	Depth Strike (m)	Depth Casing (m)	Depth Sealed (m)	Time Elapsed (min)	Water Level (m)			
18.45	150	18.00	150	1.2m hand excavated inspection pit dug.			14.50			01:00	15.30			20	14.70			
				Groundwater encountered at 15.3m			16.00			01:00								
							17.00			01:00								

Borehole Log

BH03

Contract no: S220451	Site: MF6 Building, Fujifilm, Billingham	Driller: BBL	GL (AOD):
Client: Fujifilm		Plant used: Dando 2000	Eastings: 446658
Method: Cable percussive		Started: 12/05/2022	Northing: 522643
		Ended: 13/05/2022	Logged: SM
		Backfilled: 13/05/2022	Status: FINAL

Backfill / Installation	Legend	Depth (m)	Level (m AOD)	Stratum Description	Samples and Insitu Testing		
					Depth (m)	Type	Results
				Stiff dark greyish brown slightly sandy slightly gravelly high strength CLAY. Gravel is subangular to subrounded, fine to coarse of sandstone, siltstone, mudstone and quartz.	10.50 - 10.95	U	125 blows [450mm]
					10.95 - 11.00	D	
		11.40		Very dense light brown sandy GRAVEL. Sand is medium to coarse grained, gravel is angular to rounded, fine to coarse of mixed lithologies.	12.00 - 12.45	SPT (S)	N=50+
					12.00 - 12.40	B+D	(7,12/18,19,13,55)
					13.50 - 13.95	SPT (S)	N=50+
					13.50 - 13.95	B+D	(10,15/20,20,10,40)
		14.00		Dense becoming very dense slightly sandy GRAVEL. Sand is medium to coarse grained, gravel is subangular to subrounded, fine to coarse of mixed lithologies.	15.00 - 15.45	SPT (S)	N=39 (6,8/9,10,10,10)
					15.00 - 15.95	B+D	
					16.50 - 16.95	SPT (S)	N=46
					16.50 - 16.95	B+D	(6,9/11,11,12,12)
					18.00 - 18.45	SPT (S)	N=50+
					18.00 - 18.45	B+D	(10,15/25,25,25,70)
		18.45		End of Borehole at 18.450m			

Hole Diameter				Casing Depths				General Remarks			Chiselling			Ground Water				
Depth Base (m)	Diameter (mm)	Depth Base (m)	Diameter (mm)	1.2m hand excavated inspection pit dug. Groundwater encountered at 15.3m			From (m)	To (m)	Time (hr)	Depth Strike (m)	Depth Casing (m)	Depth Sealed (m)	Time Elapsed (min)	Water Level (m)				
18.45	150	18.00	150				14.50	15.00	01:00	15.30			20	14.70				
							16.00	16.30	01:00									
							17.00	17.70	01:00									

**APPENDIX C:
Contamination Laboratory Results**



Final Report

Report No.: 22-19009-1
Initial Date of Issue: 27-May-2022
Client: Solmek Ltd
Client Address: 12 Yarm Road
Stockton-on-Tees
TS18 3NA
Contact(s): Lab
Leo Cassidy
Office
Project: S220451 MF6 Building, Fujifilm
Quotation No.: **Date Received:** 23-May-2022
Order No.: SOL-6225 **Date Instructed:** 23-May-2022
No. of Samples: 4
Turnaround (Wkdays): 5 **Results Due:** 27-May-2022
Date Approved: 27-May-2022

Approved By:

Details: Stuart Henderson, Technical
Manager

Results - Leachate

Project: S220451 MF6 Building, Fujifilm

Client: Solmek Ltd		Chemtest Job No.:		22-19009	22-19009	
Quotation No.:		Chemtest Sample ID.:		1433348	1433351	
		Sample Location:		BH01	BH03	
		Sample Type:		SOIL	SOIL	
		Top Depth (m):		0.30	0.40	
		Bottom Depth (m):		0.40	0.50	
		Date Sampled:		10-May-2022	13-May-2022	
Determinand	Accred.	SOP	Type	Units	LOD	
pH	U	1010			N/A	10.6 10.9
Sulphate	U	1220		mg/l	1.0	33 29
Cyanide (Total)	U	1300		mg/l	0.050	< 0.050 < 0.050
Hardness	U	1415		mg/l	15	99 150
Arsenic (Dissolved)	U	1455		µg/l	0.20	1.8 3.4
Boron (Dissolved)	U	1455		µg/l	10.0	140 130
Cadmium (Dissolved)	U	1455		µg/l	0.11	< 0.11 < 0.11
Chromium (Dissolved)	U	1455		µg/l	0.50	7.6 9.4
Copper (Dissolved)	U	1455		µg/l	0.50	8.0 8.8
Mercury (Dissolved)	U	1455		µg/l	0.05	< 0.05 < 0.05
Nickel (Dissolved)	U	1455		µg/l	0.50	1.7 3.1
Lead (Dissolved)	U	1455		µg/l	0.50	5.8 11
Selenium (Dissolved)	U	1455		µg/l	0.50	8.7 4.1
Zinc (Dissolved)	U	1455		µg/l	2.5	65 80
Aliphatic TPH >C5-C6	N	1675		µg/l	0.10	< 0.10
Aliphatic TPH >C6-C8	N	1675		µg/l	0.10	< 0.10
Aliphatic TPH >C8-C10	N	1675		µg/l	0.10	< 0.10
Aliphatic TPH >C10-C12	N	1675		µg/l	0.10	< 0.10
Aliphatic TPH >C12-C16	N	1675		µg/l	0.10	< 0.10
Aliphatic TPH >C16-C21	N	1675		µg/l	0.10	< 0.10
Aliphatic TPH >C21-C35	N	1675		µg/l	0.10	< 0.10
Aliphatic TPH >C35-C44	N	1675		µg/l	0.10	< 0.10
Total Aliphatic Hydrocarbons	N	1675		µg/l	5.0	< 5.0
Aromatic TPH >C5-C7	N	1675		µg/l	0.10	< 0.10
Aromatic TPH >C7-C8	N	1675		µg/l	0.10	< 0.10
Aromatic TPH >C8-C10	N	1675		µg/l	0.10	< 0.10
Aromatic TPH >C10-C12	N	1675		µg/l	0.10	< 0.10
Aromatic TPH >C12-C16	N	1675		µg/l	0.10	< 0.10
Aromatic TPH >C16-C21	N	1675		µg/l	0.10	< 0.10
Aromatic TPH >C21-C35	N	1675		µg/l	0.10	< 0.10
Aromatic TPH >C35-C44	N	1675		µg/l	0.10	< 0.10
Total Aromatic Hydrocarbons	N	1675		µg/l	5.0	< 5.0
Total Petroleum Hydrocarbons	N	1675		µg/l	10	< 10
Naphthalene	U	1800		µg/l	0.10	< 0.10 < 0.10
Acenaphthylene	U	1800		µg/l	0.10	< 0.10 < 0.10
Acenaphthene	U	1800		µg/l	0.10	< 0.10 < 0.10
Fluorene	U	1800		µg/l	0.10	< 0.10 < 0.10
Phenanthrene	U	1800		µg/l	0.10	< 0.10 < 0.10
Anthracene	U	1800		µg/l	0.10	< 0.10 < 0.10

Results - Leachate

Project: S220451 MF6 Building, Fujifilm

Client: Solmek Ltd		Chemtest Job No.:		22-19009	22-19009		
Quotation No.:		Chemtest Sample ID.:		1433348	1433351		
		Sample Location:		BH01	BH03		
		Sample Type:		SOIL	SOIL		
		Top Depth (m):		0.30	0.40		
		Bottom Depth (m):		0.40	0.50		
		Date Sampled:		10-May-2022	13-May-2022		
Determinand	Accred.	SOP	Type	Units	LOD		
Fluoranthene	U	1800		µg/l	0.10	< 0.10	< 0.10
Pyrene	U	1800		µg/l	0.10	< 0.10	< 0.10
Benzo[a]anthracene	U	1800		µg/l	0.10	< 0.10	< 0.10
Chrysene	U	1800		µg/l	0.10	< 0.10	< 0.10
Benzo[b]fluoranthene	U	1800		µg/l	0.10	< 0.10	< 0.10
Benzo[k]fluoranthene	U	1800		µg/l	0.10	< 0.10	< 0.10
Benzo[a]pyrene	U	1800		µg/l	0.10	< 0.10	< 0.10
Indeno(1,2,3-c,d)Pyrene	U	1800		µg/l	0.10	< 0.10	< 0.10
Dibenz(a,h)Anthracene	U	1800		µg/l	0.10	< 0.10	< 0.10
Benzo[g,h,i]perylene	U	1800		µg/l	0.10	< 0.10	< 0.10
Total Of 16 PAH's	U	1800		µg/l	2.0	< 2.0	< 2.0
Total Phenols	U	1920		mg/l	0.030	< 0.030	< 0.030

Results - Soil

Project: S220451 MF6 Building, Fujifilm

Client: Solmek Ltd		Chemtest Job No.:		22-19009	22-19009	22-19009	22-19009
Quotation No.:		Chemtest Sample ID.:		1433348	1433349	1433350	1433351
Sample Location:		BH01	BH02	BH02	BH03		
Sample Type:		SOIL	SOIL	SOIL	SOIL		
Top Depth (m):		0.30	0.30	1.20	0.40		
Bottom Depth (m):		0.40	0.40	1.40	0.50		
Date Sampled:		10-May-2022	10-May-2022	10-May-2022	13-May-2022		
Asbestos Lab:		DURHAM	DURHAM	DURHAM	DURHAM		
Determinand	Accred.	SOP	Units	LOD			
ACM Type	U	2192		N/A	-	-	-
Asbestos Identification	U	2192		N/A	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected
Moisture	N	2030	%	0.020	18	13	20
Soil Colour	N	2040		N/A	Brown	Brown	Brown
Other Material	N	2040		N/A	None	Roots and Stones	None
Soil Texture	N	2040		N/A	Clay	Clay	Clay
pH	M	2010		4.0	8.5	8.9	8.8
Boron (Hot Water Soluble)	M	2120	mg/kg	0.40	0.42	0.80	0.40
Sulphate (2:1 Water Soluble) as SO4	M	2120	mg/l	10	< 10	130	27
Cyanide (Total)	M	2300	mg/kg	0.50	< 0.50	< 0.50	< 0.50
Arsenic	M	2455	mg/kg	0.5	3.4	3.0	3.4
Cadmium	M	2455	mg/kg	0.10	0.40	< 0.10	< 0.10
Chromium	M	2455	mg/kg	0.5	9.6	8.0	15
Copper	M	2455	mg/kg	0.50	9.6	8.1	10
Mercury	M	2455	mg/kg	0.05	0.20	< 0.05	< 0.05
Nickel	M	2455	mg/kg	0.50	8.7	8.1	17
Lead	M	2455	mg/kg	0.50	12	14	22
Selenium	M	2455	mg/kg	0.25	0.61	0.37	0.61
Zinc	M	2455	mg/kg	0.50	38	30	37
Organic Matter	M	2625	%	0.40	2.2	1.7	1.6
Aliphatic TPH >C5-C6	N	2680	mg/kg	1.0	< 1.0		< 1.0
Aliphatic TPH >C6-C8	N	2680	mg/kg	1.0	< 1.0		< 1.0
Aliphatic TPH >C8-C10	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aliphatic TPH >C10-C12	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aliphatic TPH >C12-C16	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aliphatic TPH >C16-C21	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aliphatic TPH >C21-C35	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aliphatic TPH >C35-C44	N	2680	mg/kg	1.0	< 1.0		< 1.0
Total Aliphatic Hydrocarbons	N	2680	mg/kg	5.0	< 5.0		< 5.0
Aromatic TPH >C5-C7	N	2680	mg/kg	1.0	< 1.0		< 1.0
Aromatic TPH >C7-C8	N	2680	mg/kg	1.0	< 1.0		< 1.0
Aromatic TPH >C8-C10	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aromatic TPH >C10-C12	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aromatic TPH >C12-C16	M	2680	mg/kg	1.0	< 1.0		< 1.0
Aromatic TPH >C16-C21	U	2680	mg/kg	1.0	< 1.0		< 1.0
Aromatic TPH >C21-C35	M	2680	mg/kg	1.0	< 1.0		< 1.0

Results - Soil

Project: S220451 MF6 Building, Fujifilm

Client: Solmek Ltd		Chemtest Job No.:		22-19009	22-19009	22-19009	22-19009
Quotation No.:		Chemtest Sample ID.:		1433348	1433349	1433350	1433351
		Sample Location:		BH01	BH02	BH02	BH03
		Sample Type:		SOIL	SOIL	SOIL	SOIL
		Top Depth (m):		0.30	0.30	1.20	0.40
		Bottom Depth (m):		0.40	0.40	1.40	0.50
		Date Sampled:		10-May-2022	10-May-2022	10-May-2022	13-May-2022
		Asbestos Lab:		DURHAM	DURHAM	DURHAM	DURHAM
Determinand	Accred.	SOP	Units	LOD			
Aromatic TPH >C35-C44	N	2680	mg/kg	1.0	< 1.0		< 1.0
Total Aromatic Hydrocarbons	N	2680	mg/kg	5.0	< 5.0		< 5.0
Total Petroleum Hydrocarbons	N	2680	mg/kg	10.0	< 10		< 10
Naphthalene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Acenaphthylene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Acenaphthene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Fluorene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Phenanthrene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Anthracene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Fluoranthene	M	2700	mg/kg	0.10	0.11	< 0.10	< 0.10
Pyrene	M	2700	mg/kg	0.10	0.14	< 0.10	< 0.10
Benzo[a]anthracene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Chrysene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Benzo[b]fluoranthene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Benzo[k]fluoranthene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Benzo[a]pyrene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Indeno(1,2,3-c,d)Pyrene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Dibenz(a,h)Anthracene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Benzo[g,h,i]perylene	M	2700	mg/kg	0.10	< 0.10	< 0.10	< 0.10
Total Of 16 PAH's	M	2700	mg/kg	2.0	< 2.0	< 2.0	< 2.0
Total Phenols	M	2920	mg/kg	0.10	< 0.10	< 0.10	< 0.10

Test Methods

SOP	Title	Parameters included	Method summary
1010	pH Value of Waters	pH	pH Meter
1220	Anions, Alkalinity & Ammonium in Waters	Fluoride; Chloride; Nitrite; Nitrate; Total; Oxidisable Nitrogen (TON); Sulfate; Phosphate; Alkalinity; Ammonium	Automated colorimetric analysis using 'Aquakem 600' Discrete Analyser.
1300	Cyanides & Thiocyanate in Waters	Free (or easy liberatable) Cyanide; total Cyanide; complex Cyanide; Thiocyanate	Continuous Flow Analysis.
1415	Cations in Waters by ICP-MS	Sodium; Potassium; Calcium; Magnesium	Direct determination by inductively coupled plasma - mass spectrometry (ICP-MS).
1455	Metals in Waters by ICP-MS	Metals, including: Antimony; Arsenic; Barium; Beryllium; Boron; Cadmium; Chromium; Cobalt; Copper; Lead; Manganese; Mercury; Molybdenum; Nickel; Selenium; Tin; Vanadium; Zinc	Filtration of samples followed by direct determination by inductively coupled plasma mass spectrometry (ICP-MS).
1675	TPH Aliphatic/Aromatic split in Waters by GC-FID(cf. Texas Method 1006 / TPH CWG)	Aliphatics: >C5-C6, >C6-C8, >C8-C10, >C10-C12, >C12-C16, >C16-C21, >C21-C35, >C35-C44 Aromatics: >C5-C7, >C7-C8, >C8-C10, >C10-C12, >C12-C16, >C16-C21, >C21-C35, >C35-C44	Pentane extraction / GCxGC FID detection
1800	Speciated Polynuclear Aromatic Hydrocarbons (PAH) in Waters by GC-MS	Acenaphthene; Acenaphthylene; Anthracene; Benzo[a]Anthracene; Benzo[a]Pyrene; Benzo[b]Fluoranthene; Benzo[ghi]Perylene; Benzo[k]Fluoranthene; Chrysene; Dibenz[ah]Anthracene; Fluoranthene; Fluorene; Indeno[123cd]Pyrene; Naphthalene; Phenanthrene; Pyrene	Pentane extraction / GCMS detection
1920	Phenols in Waters by HPLC	Phenolic compounds including: Phenol, Cresols, Xylenols, Trimethylphenols Note: Chlorophenols are excluded.	Determination by High Performance Liquid Chromatography (HPLC) using electrochemical detection.
2010	pH Value of Soils	pH	pH Meter
2030	Moisture and Stone Content of Soils(Requirement of MCERTS)	Moisture content	Determination of moisture content of soil as a percentage of its as received mass obtained at <37°C.
2040	Soil Description(Requirement of MCERTS)	Soil description	As received soil is described based upon BS5930
2120	Water Soluble Boron, Sulphate, Magnesium & Chromium	Boron; Sulphate; Magnesium; Chromium	Aqueous extraction / ICP-OES
2192	Asbestos	Asbestos	Polarised light microscopy / Gravimetry
2300	Cyanides & Thiocyanate in Soils	Free (or easy liberatable) Cyanide; total Cyanide; complex Cyanide; Thiocyanate	Alkaline extraction followed by colorimetric determination using Automated Flow Injection Analyser.
2625	Total Organic Carbon in Soils	Total organic Carbon (TOC)	Determined by high temperature combustion under oxygen, using an Eltra elemental analyser.
2680	TPH A/A Split	Aliphatics: >C5-C6, >C6-C8,>C8-C10, >C10-C12, >C12-C16, >C16-C21, >C21-C35, >C35-C44 Aromatics: >C5-C7, >C7-C8, >C8-C10, >C10-C12, >C12-C16, >C16-C21, >C21-C35, >C35-C44	Dichloromethane extraction / GCxGC FID detection
2700	Speciated Polynuclear Aromatic Hydrocarbons (PAH) in Soil by GC-FID	Acenaphthene; Acenaphthylene; Anthracene; Benzo[a]Anthracene; Benzo[a]Pyrene; Benzo[b]Fluoranthene; Benzo[ghi]Perylene; Benzo[k]Fluoranthene; Chrysene; Dibenz[ah]Anthracene; Fluoranthene; Fluorene; Indeno[123cd]Pyrene; Naphthalene; Phenanthrene; Pyrene	Dichloromethane extraction / GC-FID (GC-FID detection is non-selective and can be subject to interference from co-eluting compounds)

Test Methods

SOP	Title	Parameters included	Method summary
2920	Phenols in Soils by HPLC	Phenolic compounds including Resorcinol, Phenol, Methylphenols, Dimethylphenols, 1-Naphthol and Trimethylphenols Note: chlorophenols are excluded.	60:40 methanol/water mixture extraction, followed by HPLC determination using electrochemical detection.

Report Information

Key

U	UKAS accredited
M	MCERTS and UKAS accredited
N	Unaccredited
S	This analysis has been subcontracted to a UKAS accredited laboratory that is accredited for this analysis
SN	This analysis has been subcontracted to a UKAS accredited laboratory that is not accredited for this analysis
T	This analysis has been subcontracted to an unaccredited laboratory
I/S	Insufficient Sample
U/S	Unsuitable Sample
N/E	not evaluated
<	"less than"
>	"greater than"
SOP	Standard operating procedure
LOD	Limit of detection

Comments or interpretations are beyond the scope of UKAS accreditation

The results relate only to the items tested

Uncertainty of measurement for the determinands tested are available upon request

None of the results in this report have been recovery corrected

All results are expressed on a dry weight basis

The following tests were analysed on samples as received and the results subsequently corrected to a dry weight basis TPH, BTEX, VOCs, SVOCs, PCBs, Phenols

For all other tests the samples were dried at < 37°C prior to analysis

All Asbestos testing is performed at the indicated laboratory

Issue numbers are sequential starting with 1 all subsequent reports are incremented by 1

Sample Deviation Codes

A - Date of sampling not supplied

B - Sample age exceeds stability time (sampling to extraction)

C - Sample not received in appropriate containers

D - Broken Container

E - Insufficient Sample (Applies to LOI in Trommel Fines Only)

Sample Retention and Disposal

All soil samples will be retained for a period of 30 days from the date of receipt

All water samples will be retained for 14 days from the date of receipt

Charges may apply to extended sample storage

If you require extended retention of samples, please email your requirements to:

customerservices@chemtest.com

**APPENDIX D:
Geotechnical Laboratory Results**

Laboratory Report Front Sheet

Solmek
12-16 Yarm Road,
Stockton on Tees,
TS18 3NA
01642 607083
lab@solmek.com



Site name	Job number
MF6 Building, Fujifilm	S220451

Client details:

Reference: S220451
Name: Solmek
Address: 12 Yarm Road,
Stockton-on-tees,
TS18 3NA

Telephone: 01642 607083
Email: lcassidy@solmek.com

FAO: Leo Cassidy


Date commenced: 23/05/2022

Date reported: 01/06/2022

Observations and interpretations are outside of the UKAS Accreditation

A copy of the Laboratory Schedule of accredited tests as issued by UKAS is attached to this report. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced in full, without the prior written approval of the laboratory.

Samples will be held at the laboratory for a period of 4 weeks after the report date. After the above reporting date the samples will be disposed of. Should further testing be required then the office should be informed before the above date.

Signature: 	Approved Signatories: <input type="checkbox"/> D.Anderson (Associate Director) <input checked="" type="checkbox"/> J. Brischuk (Laboratory Manager) <input type="checkbox"/>
--	--


PARTICLE SIZE DISTRIBUTION

Solmek
12-16 Yarm Road,
Stockton on Tees,
TS18 3NA
01642 607083
lab@solmek.com



Site name	Job number
MF6 Building, Fujifilm	S220451

Hole	BH03	Lab sample ID	SLMK2022052326
Depth (Top)	m 12.00	Test Method	BS 1377 - 2 : 1990 Clause 9.2
Depth (Base)	m	Soil Description	Slightly Gravelly, Very Sandy CLAY
Sample type	B		



CLAY	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	COBBLES	BOULDERS
	SILT			SAND			GRAVEL				

Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	99		
1.18	98		
0.6	96		
0.425	95		
0.3	94		
0.212	88		
0.15	72		
0.063	72		

Dry Mass of sample, g 987

Sample Proportions	% dry mass
Very coarse	0.0
Gravel	1.2
Sand	27.3
Fines <0.063mm	72.0


Grading Analysis	
D100	mm
D60	mm
D30	mm
D10	mm
Uniformity Coefficient	
Curvature Coefficient	

Remarks
Preparation and testing in accordance with test method unless noted below

Accreditation status

Hydrometer is the usual Sedimentation method carried out by Solmek and is part of the Solmek UKAS accreditation schedule.

Approved by	JBrischuk
Approval date	31/05/2022 15:47

	Unconsolidated Undrained Triaxial Compression Test without measurement of pore pressure - single specimen		Job Ref	S220451	
			Borehole/Pit No.	BH01	
Site Name	MF6 Building, Fujifilm		Sample No.		
Soil Description			Depth	3.00	
Specimen Reference		Specimen Depth	m	Sample Type	U
Specimen Description	Low strength CLAY		KeyLAB ID	SLMK2022052321	
Test Method	BS1377 : Part 7 : 1990, clause 8, single specimen		Date of test	31/05/2022	


Test Number	1
Length	76.0 mm
Diameter	38.0 mm
Bulk Density	1.93 Mg/m ³
Moisture Content	30.1 %
Dry Density	1.48 Mg/m ³

Tracable Equipment Record


Test Frame	TRI 004
Load Ring	LOAD CELL 003
Pressure Gauge	PRE 006
Digital Caliper	CAL-005
Balance	BAL-007

Rate of Strain	1.0 %/min
Cell Pressure	60 kPa
At failure	
Axial Strain	20.0 %
Deviator Stress, (σ ₁ - σ ₃) _f	52 kPa
Undrained Shear Strength, c _u	26 kPa ½(σ ₁ - σ ₃) _f
Mode of Failure	Compound

Deviator Stress v Axial Strain




Mohr Circles



Deviator stress corrected for area change and membrane effects

Mohr circles and their interpretation is not covered by BS1377. This is provided for information only.

No of membranes used	1
Total thickness (mm)	0.25
Membrane Correction	
Membrane Type	


	Unconsolidated Undrained Triaxial Compression Test without measurement of pore pressure - single specimen		Job Ref	S220451	
			Borehole/Pit No.	BH01	
Site Name	MF6 Building, Fujifilm		Sample No.		
Soil Description			Depth	18.00	
Specimen Reference		Specimen Depth	m	Sample Type	B
Specimen Description	Medium strength CLAY		KeyLAB ID	SLMK2022052322	
Test Method	BS1377 : Part 7 : 1990, clause 8, single specimen		Date of test	25/05/2022	

Test Number	1
Length	76.0 mm
Diameter	38.0 mm
Bulk Density	1.98 Mg/m ³
Moisture Content	27.3 %
Dry Density	1.56 Mg/m ³
Rate of Strain	1.0 %/min
Cell Pressure	360 kPa
At failure	
Axial Strain	17.5 %
Deviator Stress, (σ ₁ - σ ₃) _f	108 kPa
Undrained Shear Strength, c _u	54 kPa ½(σ ₁ - σ ₃) _f
Mode of Failure	Compound


Tracable Equipment Record

Test Frame	TRI 004
Load Ring	LOAD CELL 003
Pressure Gauge	PRE 006
Digital Caliper	CAL-005
Balance	BAL-007

Deviator Stress v Axial Strain




Mohr Circles



Deviator stress corrected for area change and membrane effects

Mohr circles and their interpretation is not covered by BS1377. This is provided for information only.

No of membranes used	1
Total thickness (mm)	0.25
Membrane Correction	
Membrane Type	

	Unconsolidated Undrained Triaxial Compression Test without measurement of pore pressure - single specimen		Job Ref	S220451	
			Borehole/Pit No.	BH02	
Site Name	MF6 Building, Fujifilm		Sample No.		
Soil Description			Depth	3.00	
Specimen Reference		Specimen Depth	m	Sample Type	U
Specimen Description	Low strength CLAY		KeyLAB ID	SLMK2022052323	
Test Method	BS1377 : Part 7 : 1990, clause 8, single specimen		Date of test	31/05/2022	


Test Number	1
Length	202.0 mm
Diameter	103.0 mm
Bulk Density	1.89 Mg/m ³
Moisture Content	32.1 %
Dry Density	1.43 Mg/m ³

Tracable Equipment Record


Test Frame	TRI 004
Load Ring	LOAD CELL 001
Pressure Gauge	PRE 006
Digital Caliper	CAL-005
Balance	BAL-007

Rate of Strain	1.0 %/min
Cell Pressure	60 kPa
At failure	
Axial Strain	12.0 %
Deviator Stress, ($\sigma_1 - \sigma_3$) _f	64 kPa
Undrained Shear Strength, c_u	32 kPa $\frac{1}{2}(\sigma_1 - \sigma_3)_f$
Mode of Failure	Compound

Deviator Stress v Axial Strain




Mohr Circles



Deviator stress corrected for area change and membrane effects

Mohr circles and their interpretation is not covered by BS1377. This is provided for information only.

No of membranes used	1
Total thickness (mm)	0.25
Membrane Correction	
Membrane Type	

	Unconsolidated Undrained Triaxial Compression Test without measurement of pore pressure - single specimen		Job Ref	S220451	
			Borehole/Pit No.	BH02	
Site Name	MF6 Building, Fujifilm		Sample No.		
Soil Description			Depth	10.50	
Specimen Reference		Specimen Depth	m	Sample Type	U
Specimen Description	Very high strength CLAY		KeyLAB ID	SLMK2022052324	
Test Method	BS1377 : Part 7 : 1990, clause 8, single specimen		Date of test	31/05/2022	


Test Number	1
Length	76.0 mm
Diameter	38.0 mm
Bulk Density	2.20 Mg/m ³
Moisture Content	16.6 %
Dry Density	1.89 Mg/m ³

Tracable Equipment Record


Test Frame	TRI 004
Load Ring	LOAD CELL 003
Pressure Gauge	PRE 006
Digital Caliper	CAL-005
Balance	BAL-007

Rate of Strain	1.0 %/min
Cell Pressure	210 kPa
At failure	
Axial Strain	20.0 %
Deviator Stress, ($\sigma_1 - \sigma_3$) _f	519 kPa
Undrained Shear Strength, c_u	259 kPa $\frac{1}{2}(\sigma_1 - \sigma_3)_f$
Mode of Failure	Compound

Deviator Stress v Axial Strain




Mohr Circles



Deviator stress corrected for area change and membrane effects

Mohr circles and their interpretation is not covered by BS1377. This is provided for information only.

No of membranes used	1
Total thickness (mm)	0.25
Membrane Correction	
Membrane Type	

	Unconsolidated Undrained Triaxial Compression Test without measurement of pore pressure - single specimen		Job Ref	S220451
			Borehole/Pit No.	BH03
Site Name	MF6 Building, Fujifilm		Sample No.	
Soil Description			Depth	10.50
Specimen Reference		Specimen Depth	m	
Specimen Description	High strength CLAY		Sample Type	U
Test Method	BS1377 : Part 7 : 1990, clause 8, single specimen		KeyLAB ID	SLMK2022052325
			Date of test	31/05/2022


Test Number	1
Length	204.0 mm
Diameter	102.0 mm
Bulk Density	2.17 Mg/m3
Moisture Content	16.6 %
Dry Density	1.86 Mg/m3

Tracable Equipment Record


Test Frame	TRI 004
Load Ring	LOAD CELL 001
Pressure Gauge	PRE 006
Digital Caliper	CAL-005
Balance	BAL-007

Rate of Strain	1.0 %/min
Cell Pressure	210 kPa
At failure	
Axial Strain	14.2 %
Deviator Stress, ($\sigma_1 - \sigma_3$)f	228 kPa
Undrained Shear Strength, cu	114 kPa $\frac{1}{2}(\sigma_1 - \sigma_3)$ f
Mode of Failure	Compound

Deviator Stress v Axial Strain



Mohr Circles



Deviator stress corrected for area change and membrane effects

Mohr circles and their interpretation is not covered by BS1377. This is provided for information only.

No of membranes used	1
Total thickness (mm)	0.25
Membrane Correction	
Membrane Type	




7607

**ONE DIMENSIONAL CONSOLIDATION TEST
BS1377:Part 5:1990, clause 3**

Job Ref	S220451
Borehole/Pit No.	BH01
Sample No.	
Depth	3
Sample Type	U
KeyLAB ID	SLMK2022052321
Date started	20/05/2022

Site Name	MF6 Building, Fujifilm	
Soil Description		
Specimen Reference	Specimen Depth	m
Specimen Description		
Test Method	BS1377:Part 5:1990, clause 3	



Applied Pressure kPa	Voids ratio	Mv m2/MN	Cv (t50, log) m2/yr	Cv (t90, root) m2/yr	Csec
0.0	0.750	-	-	-	-
20	0.706	1.3		64	0.00086
40	3.925	0.52	4.7	25	0.00064
80	3.865	0.31	6.6	9	0.0017
160	3.769	0.25	3	15	0.0018
320	0.602	0.13	2.9	4.5	0.0018

Preparation				
Index tests	Liquid limit	%	Plastic limit	%
Particle density		assumed	2.65	Mg/m3
Specimen details				
Diameter	Initial	Final		mm
Height	75.06	-		mm
Moisture Content	19.98	18.29		%
Bulk density	29.1	26.2		Mg/m3
Dry density	1.95			Mg/m3
Voids Ratio	1.51			
Saturation	0.750			%
Average temperature for test	103			oC
Swelling Pressure	21.0			kPa
Settlement on saturation				%
Remarks				

Final values should be used with caution	Tested	Checked	Approved	Printed : 01/06/2022 12:15	Fig. No 1
Cv plotted at mid point of load increments					
Cv corrected to 20oC					



Final Report

Report No.: 22-19039-1
Initial Date of Issue: 25-May-2022
Client: Solmek Ltd
Client Address: 12 Yarm Road
Stockton-on-Tees
TS18 3NA
Contact(s): B Atkinson
Joe Brischuk
Lab
Office
Leo Cassidy
Project: S220451 MF6 Building, Fujifilm

Quotation No.:		Date Received:	23-May-2022
Order No.:	LAB1467	Date Instructed:	23-May-2022
No. of Samples:	3		
Turnaround (Wkdays):	5	Results Due:	27-May-2022
Date Approved:	25-May-2022		

Approved By:

Details: Stuart Henderson, Technical
Manager

Results - Soil

Project: S220451 MF6 Building, Fujifilm

Client: Solmek Ltd		Chemtest Job No.:			22-19039	22-19039	22-19039
Quotation No.:		Chemtest Sample ID.:			1433447	1433448	1433449
		Sample Location:	BH01	BH02	BH03		
		Sample Type:	SOIL	SOIL	SOIL		
		Top Depth (m):	18.0	10.5	12.0		
		Bottom Depth (m):	18.45	10.95	12.45		
		Date Sampled:	10-May-2022	10-May-2022	10-May-2022		
Determinand	Accred.	SOP	Units	LOD			
Moisture	N	2030	%	0.020	19	12	16
pH	U	2010		4.0	9.0	9.2	9.3
Sulphate (2:1 Water Soluble) as SO4	U	2120	mg/l	10	150	20	26

Test Methods

SOP	Title	Parameters included	Method summary
2010	pH Value of Soils	pH	pH Meter
2030	Moisture and Stone Content of Soils(Requirement of MCERTS)	Moisture content	Determination of moisture content of soil as a percentage of its as received mass obtained at <37°C.
2040	Soil Description(Requirement of MCERTS)	Soil description	As received soil is described based upon BS5930
2120	Water Soluble Boron, Sulphate, Magnesium & Chromium	Boron; Sulphate; Magnesium; Chromium	Aqueous extraction / ICP-OES

Report Information

Key

U	UKAS accredited
M	MCERTS and UKAS accredited
N	Unaccredited
S	This analysis has been subcontracted to a UKAS accredited laboratory that is accredited for this analysis
SN	This analysis has been subcontracted to a UKAS accredited laboratory that is not accredited for this analysis
T	This analysis has been subcontracted to an unaccredited laboratory
I/S	Insufficient Sample
U/S	Unsuitable Sample
N/E	not evaluated
<	"less than"
>	"greater than"
SOP	Standard operating procedure
LOD	Limit of detection

Comments or interpretations are beyond the scope of UKAS accreditation

The results relate only to the items tested

Uncertainty of measurement for the determinands tested are available upon request

None of the results in this report have been recovery corrected

All results are expressed on a dry weight basis

The following tests were analysed on samples as received and the results subsequently corrected to a dry weight basis TPH, BTEX, VOCs, SVOCs, PCBs, Phenols

For all other tests the samples were dried at < 37°C prior to analysis

All Asbestos testing is performed at the indicated laboratory

Issue numbers are sequential starting with 1 all subsequent reports are incremented by 1

Sample Deviation Codes

A - Date of sampling not supplied

B - Sample age exceeds stability time (sampling to extraction)

C - Sample not received in appropriate containers

D - Broken Container

E - Insufficient Sample (Applies to LOI in Trommel Fines Only)

Sample Retention and Disposal

All soil samples will be retained for a period of 30 days from the date of receipt

All water samples will be retained for 14 days from the date of receipt

Charges may apply to extended sample storage

If you require extended retention of samples, please email your requirements to:

customerservices@chemtest.com

APPENDIX E:
Notes on Limitations & Contamination Guidance

UK BACKGROUND

Environmental Protection Act 1990: Part 2A Revised Statutory Guidance (April 2012)

This revised document explains how the Local Authority should decide if land, based on a legal interpretation, is contaminated. The document replaces the previous guidance given in Annex 3 of DEFRA Circular 01/2006, issued in accordance with section 78YA of the 1990 Environmental Protection Act.

The main objectives of the Part 2A regime are to *“identify and remove unacceptable risks to human health and the environment”* and to *“seek to ensure that contaminated land is made suitable for its current use”*.

Part 2A uses a risk based approach to defining contaminated land whereby the “risk” is interpreted as *“the likelihood that harm, or pollution of water, will occur as a result of contaminants in, on or under the land”* and by *“the scale and seriousness of such harm or pollution if it did occur”*.

For a relevant risk to exist a contaminant, pathway and receptor linkage must be present before the land can be considered to be contaminated. The document explains that *“for a risk to exist there must be contaminants present in, on or under the land in a form and quantity that poses a hazard, and one or more pathways by which they might significantly harm people, the environment, or property; or significantly pollute controlled waters.”*

A conceptual model is used to develop and communicate the risks associated with a particular site.

To determine if land is contaminated the local authority use various categories from 1 to 4. Categories 1 and 2 include *“land which is capable of being determined as contaminated land on grounds of significant possibility of significant harm to human health.”*

Categories 3 and 4 *“encompass land which is not capable of being determined on such grounds”*.

PRELIMINARY CONCEPTUAL MODEL

Preliminary Conceptual Models are undertaken in accordance with CIRIA C552. The Preliminary Conceptual Model assesses the consequence and the likelihood of a risk being realised to provide a risk classification, using the tables detailed below.

CONSEQUENCE OF RISK BEING REALISED (Based on C552 CIRIA, 2001)

Classification	Definition	Example
Severe	Short-term (acute) risk to human health, the environment, an element of the development or other aspect with is likely to result in <i>significant harm</i> , damage or both.	High concentrations of cyanide on the surface of an informal recreational area. Major spills of contaminants from site into controlled water. High concentrations of explosive gas in the subsurface environment that have a clear unobstructed pathway into buildings.
Moderate	Chronic damage to human health, a plausible chance that an event will occur, although the timeline is not immediate to be in the short-term.	Appreciable concentration of contamination that over the longer-term will cause significant harm i.e. high lead concentration in topsoil. Shallow mine workings that are potentially unstable but may remain in a satisfactory or stable conditions for a number of years.
Mild	Low level pollution of non-sensitive water, a feasible hazardous scenario although the timeline of such occurring can probably be considered in 10's of years.	The effect of high sulphate concentrations on structural concrete. Pollution of non-classified groundwater.
Minor	Harm, although not necessarily significant to human health, or with respect to other aspects of the development, which are considered implausible in terms of occurrence, or will have little consequential impact.	The presence of contaminants at such low concentrations that protective equipment is required during site works. Any damage to structures is minimal and will not be structural in characteristics.

PROBABILITY OF RISK BEING REALISED (C552 CIRIA, 2001)

Classification	Definition
High Likelihood	There is a viable pollutant linkage and an event that either appears very likely in the short term and almost inevitable over the long term, or there is evidence that the receptor has been harmed or polluted.
Likely	There is a viable pollutant linkage and all elements are present and in the right place, which means that it is probable that an event will occur. Circumstances are such that an event is not inevitable, but possible in the short term and likely over the long term.
Low Likelihood	There is a viable pollutant linkage and circumstances are possible under which an event could occur. However, it is by no means certain that even over a longer period such event would take place, and is less likely in the shorter term.
Unlikely	There is a viable pollutant linkage but circumstances are such that it is improbable that an event would occur even in the very long term.

RISK CLASSIFICATION MATRIX (C552 CIRIA, 2001)

Risk = Probability x Consequence		Consequence			
		Severe	Moderate	Mild	Minor
Probability	High likelihood	Very high risk	High risk	Moderate risk	Moderate/low risk
	Likely	High risk	Moderate risk	Moderate/low risk	Low risk
	Low likelihood	Moderate risk	Moderate/low risk	Low risk	Very low risk
	Unlikely	Moderate/low risk	Low risk	Very low risk	Very low risk

HUMAN RECEPTORS

Human exposure to contaminants present in soils can occur via several pathways. Direct exposure pathways include dermal absorption after contact with contaminated ground, inhalation of soil or dust, inhalation of volatilised compounds, and inadvertent soil ingestion (or deliberate soil ingestion in the case of some children). Other indirect pathways include human ingestion of plants grown in contaminated soil or contaminated ground or surface water. Contaminants associated with wind blown dust can affect humans on surrounding sites.

VEGETATION

Plants can be affected by soil contamination in a number of ways resulting in growth inhibition, nutrient deficiencies and yellowing of leaves. Contaminants are taken up by plants through the roots and through foliage. Contaminants identified as being highly phytotoxic include boron, cadmium, copper, lead, nickel, and zinc.

To establish if the levels of contaminants present on a site may pose a risk to vegetation the results of the contamination testing are compared to a series of threshold values published in 'Code of Good Agricultural Practice for the Protection of Soil'.

GROUNDWATER AND SURFACE WATER RECEPTORS

The principal pathway by which soil contamination may reach the water environment is through a slow seepage or leaching to groundwater or surface water. The potential for contaminants to migrate along such pathways is dependent on the chemical and physical characteristics of the contaminants and the local hydrogeology. Surface watercourses may also accumulate contamination as contaminated sediments are deposited within the water body.

Where the site investigated overlies major/principal aquifers (and in some cases minor/secondary aquifers depending on certain conditions), groundwater Source Protection Zones and areas in close proximity to groundwater abstractions, contamination test results have been compared with the Water Supply (Water Quality) Regulations 1989 and The Water Supply (Water Quality) Regulations 2000.

Should a surface water receptor, such as a fresh water environment (river, canal, stream, lake etc), or marine environment be considered sensitive in relation to a site, then test results are compared with DEFRA & SEPA Environmental Quality Standards (2004). Many of the Environmental Quality Standards are hardness (CaCO₃) depended. Where no hardness values are available, Solmek assume conservative values (of between 0 and 50mg/l).

In the absence of vulnerable ground and surface water environments, Solmek may compare any test results with the Environment Agency Leachate Quality Threshold Values.

DETAILED QUANTITATIVE RISK ASSESSMENT (DQRA)

In line with Environment Agency's guidance document Environment Agency *Land Contamination Risk Management*, which replaced the now-withdrawn *Contaminated Land Report 11 – Model Procedures for the Management of Land Contamination (2004)*, a DQRA for groundwater/human health may be required following a Phase 2 investigation and before the preparation of a Phase 3 Remediation Strategy. For human health DQRA, a site specific assessment criteria is undertaken using CLEA Software Version 1.06. For groundwater DQRA, the Environment Agency Remedial Targets Worksheet Version 3.1 is used.


WASTE CLASSIFICATION AND WASTE ACCEPTANCE CRITERIA

During the site strip and construction activities, material may be required to be removed from site. Any such material would require classification, in line with Environment Agency Technical Guidance *Waste Classification: Guidance on the classification and assessment of waste (2015)*. This would classify the material as either Non-Hazardous or Hazardous Waste.

Once the material has been classified, determining the suitable landfill for disposal is governed by landfill directive Waste Acceptance Criteria (WAC) testing, with landfills categorized as Inert Waste, Stable Non-Reactive Hazardous Waste and Hazardous Waste. The WAC testing relates to materials that are to be exported from a site/development to landfill, and do not directly relate to human health specifically. The testing results are generally presented as certificates which can be used by site owners/contractors etc, which should be presented to the accepting waste facility or waste contractor.

If waste classification and/or WAC testing are not undertaken, material taken off site may be subject to WAC testing by the appropriate waste disposal company. The decision on whether or not to accept waste, or whether further testing is required, is at the discretion of the waste disposal company.

The below flow chart provides further information on the waste classification process.



CONSTRUCTION MATERIALS

Materials at risk from possible soil contaminants include inorganic matrices such as cement and concrete and also organic material such as plastics and rubbers. Acid ground conditions and high levels of sulphates can accelerate the corrosion of building materials. Where pH and soluble sulphate analysis has been undertaken, Solmek compare the test results with the guidelines presented within BRE Special Digest 1, 2005 (3rd Edition) 'Concrete in Aggressive Ground'. Plastics and rubbers are generally used for piping and service ducts and are potentially attacked by a range of chemicals, most of which are organic, particularly petroleum based substances. Drinking water supplies can be tainted by substances that can penetrate piping and water companies enforce stringent threshold values.

The levels of potential contaminants should be compared to thresholds supplied in the UK Water Industry Research (UKWIR) publication "Guidance for the selection of Water Supply Pipes to be used in Brownfield Sites" (January 2011). A Brownfield Site is defined in the document as "Land or premises that have not previously been used or developed that may be vacant or derelict". It should be noted that Brownfield sites may not be contaminated. The guidance does not apply to Greenfield Sites however water companies may have their own assessment criteria which should be checked by the developer. The table below outlines the pipe material selection threshold concentrations.

Parameter group	Pipe Material (Threshold concentrations in mg/kg)					
	PE	PVC	Barrier pipe (PE-AL-PE)	Wrapped Steel	Wrapped Ductile Iron	Copper
Extended VOC suite by purge and trap or head space and GC-MS with TIC	0.5	0.125	Pass	Pass	Pass	Pass
+ BTEX + MTBE	0.1	0.03	Pass	Pass	Pass	Pass
SVOCs TIC by purge and trap or head space and GC-MS with TIC (aliphatic and aromatic C5-C10)	2	1.4	Pass	Pass	Pass	Pass
+ Phenols	2	0.4	Pass	Pass	Pass	Pass
+ Cresols and chlorinated phenols	2	0.04	Pass	Pass	Pass	Pass
Mineral oil C11-C20	10	Pass	Pass	Pass	Pass	Pass
Mineral oil C21-C40	500	Pass	Pass	Pass	Pass	Pass
Corrosive (Conductivity, Redox and pH)	Pass	Pass	Pass	Corrosive if pH <7 and conductivity >400µS/cm	Corrosive if pH <5, Eh not neutral and conductivity >400µS/cm	Corrosive if pH <5 or >8 and Eh positive
Specific suite identified as relevant following site investigation						
Ethers	0.5	1	Pass	Pass	Pass	Pass
Nitrobenzene	0.5	0.4	Pass	Pass	Pass	Pass
Ketones	0.5	0.02	Pass	Pass	Pass	Pass
Aldehydes	0.5	0.02	Pass	Pass	Pass	Pass
Amines	Fail	Pass	Pass	Pass	Pass	Pass

REQUIREMENTS OF PARTIES WITHIN THE DEVELOPMENT PROCESS

Interested parties involved in the development process may use the data in different ways and there may be varying views and interpretation of the factual data. Local Authority staff may have a view on contamination and human health and the wider environment. The Environment Agency are concerned principally with the protection of Controlled waters. Building insurers, funders and purchasers may be primarily concerned with issues of potential commercial blight. Purchasers are also not always fully informed, and perceptions on issues associated with risk can affect the decision to purchase. Developers and construction organisations will focus on financial aspects of dealing with the contamination in the context of the development and construction programme.

RISKS & LIABILITIES FROM CONTAMINATION

In simple terms, risks associated with contamination may be considered in terms of 1) statutory risks and 2) development related risks. If contamination is severe or forms a potential hazard based on its potential to affect groundwater, surface water or human health, a statutory risk may be present, and as such, if the risk is not reduced, criminal proceedings may be instigated by a government body or local authority.

If the contamination is less severe or not considered to be mobile, it may be considered a commercial liability which could, in theory remain untreated, but which may at a later date affect the value of the property, or, with changing legislation, become a statutory risk. Commercial liabilities could give rise to civil proceedings by third parties if there are grounds for action.

♣Solmek conditions of offer, notes on limitations & basis for contract (ref: version1/2022)

These conditions accompany our tender and supercede any previous conditions issued. Solmek will prepare a report solely for the use of the Client (the party invoiced) and its agent(s). No reliance should be placed on the contents of this report, in whole or in part by 3rd parties. The report, its content and format and associated data are copyright, and the property of Solmek. Photocopying of part or all of the contents, transfer or reproduction of any kind is forbidden without written permission from Solmek. A charge may be levied against such approval, the same to be made at the discretion of Solmek.

Solmek cannot be held liable and do not warrant, or otherwise guarantee the validity of information provided by third parties and subsequently used in our reports. Solmek are not responsible for the action negligent of otherwise of subcontractors or third parties.

Site investigation is a process of sampling. The scope and size of an investigation may be considered proportional to levels of confidence regarding the ground and groundwater conditions. The exploratory holes undertaken investigate only a small volume of the ground in relation to the overall size of the site, and can only provide a general indication of site conditions. The opinions provided and recommendations given in this report are based on the ground conditions as encountered within each of the exploratory holes. There may be different ground conditions elsewhere on the site which have not been identified by this investigation and which therefore have not been taken into account in this report. Reports are generally subject to the comments of the local authority and Environment Agency. The comments made on groundwater conditions are based on observations made at the time that site work was carried out. It should be noted that mobile contamination, ground gas levels and groundwater levels may vary owing to seasonal, tidal and/or weather related effects. Solmek cannot be held liable for any unrecorded or unforeseen obstructions between exploratory boreholes and trial pits. This includes instances where previous structures on the site (buried man made structures) or the presence of boulder clay (cobbles and/or boulder obstructions) have been anticipated. All types of piling operations should make allowance for obstructions within the construction budget to accommodate this. Unrecorded ancient mining may occur anywhere where seams that have been worked and influence the rock and soil above. Dissolution cavities can occur where gypsum or chalk is present. Rotary drilling is the recommended technique to prove the integrity of the rock.

Where the scope of the investigation is limited via access to information, time constraints, equipment limitations, testing, interpretation or by the client or his agents budgetary constraints, elements not set out in the proposal and excluded from the report are deemed to be omitted from the scope of the investigation.

Desk studies are generally prepared in accordance with RICS guidelines. Environmental site investigations are generally undertaken as 'exploratory investigations' in accordance with the definitions provided in paragraph 5.4 of BS 10175:2011 in order to confirm the conceptual assumptions. You are advised to familiarize yourself with the typical scope of such an investigation. No pumping of water will be undertaken unless a licence or facilities/equipment have been arranged by others.

Where the type, number or/and depth of exploratory hole is specified by others, Solmek cannot and will not be responsible for any subsequent shortfall or inadequacy in data, and any consequent shortfall in interpretation of environmental and geotechnical aspects which may be required at a later date in order to facilitate the design of permanent or temporary works.

All information acquired by Solmek in the course of investigation is the property of Solmek, and, only also becomes the joint property of the Client only on the complete settlement of all invoices relating to the project. Solmek reserve the right to use the information in commercial tendering and marketing, unless the Client expressly wishes otherwise in writing. The quoted rates do not include VAT, and payment terms are 30 days from dispatch of invoice from our offices. Quotes are subject to a site visit.

We have allowed for 1 mobilisation and normal working hours unless otherwise stated. The scope of the investigation may be reviewed following the desk study and/or fieldwork. The presence or otherwise of Japanese Knotweed or other invasive plants can be difficult to identify especially during winter months. If Japanese Knotweed or other invasive species are suspect, it should be confirmed by an ecologist. We have not allowed for acquiring services information, and cannot be responsible for damage to underground services or pipes not shown to us or not clearly shown on plans. Costs incurred will be passed on to you, and in commissioning Solmek you understand and accept that you/your agent have a contractual relationship with Solmek & you accept this. Our rates assume unobstructed, reasonably level and firm access to the exploratory positions and adequate clear working areas and headroom. We have priced on the basis that you or your client have the necessary permissions, wayleaves and approvals to access land. All boreholes and pits are backfilled with arisings except where gas monitoring pipes are installed with stopcock covers. Solmek are not responsible for any uneven surfaces as a result of siteworks and rutting and backfilled excavations may require re-levelling and/or making good by others after fieldwork is complete, and Solmek has not allowed for this. No price has been provided or requested for a return visit to remove pipework and covers. Hourly rates apply to consultancy only and do not include expenses unless otherwise shown. If warranties are required, legal costs incurred will be passed on to you assuming Solmek agree to complete such warranties, modified or otherwise and you understand and agree to pay all costs.

We reserve the right to pursue full payment of the invoice prior to release of any information including reports. We advise you/your client that we may elect to pursue our statutory rights under late payment legislation, and will apply 8% to the base rate for unreasonably late payments. Solmek are exempt from the CIS Scheme. Solmek offer to undertake work only in strict accordance with conditions covered by our current insurances, which are available for inspection. Solmek are not responsible for acts, negligent or otherwise of subcontractors and as a matter of policy cannot indemnify any other parties. Professional indemnity Insurance is limited to ten times the invoice net total except where stated otherwise by Solmek. Solmek give notice that consequential loss as a direct or indirect result of Solmek's activities or omission of the same are excluded.