



KEY
[Not all features shown on key may be present on every plan]

Proposed elements

- Proposed feathered tree planting
- Proposed pre-established coir roll
- Proposed planting strip for marginal Root Trainer plugs
- Proposed Neutral Wet Grassland (NWG) seed mix.
- Proposed permanent post and wire stock fencing
- Proposed pedestrian maintenance access gate
- Proposed new wetland area

- NOTES**
- For planting and seeding mixes, see Dwg ENVRESW001353-CH2-XX-400-DR-EN-5438.
- WFD ENHANCEMENT MEASURES**
- Stated horizontal dimensions and slope gradients of WFD channels and marginal shelves are average dimensions for guidance - the intention is that these should vary to provide a more complex, varied platform than the plan views and cross-sections imply. It is intended that excavation works on site are directed by an experienced ecologist to assist achieve the level of variation required. It is important, however, that vertical dimensions and levels do not vary significantly from those shown on the plans and cross-sections to ensure water levels are suitable for the intended habitat.
- All works to be undertaken in accordance with the Works Information and Environmental Action Plan (EAP), including:
- CULTURAL HERITAGE**
- Archaeological monitoring investigation and recording to mitigate risks to previously unknown assets and deposits of paleoenvironmental and geoarchaeological interest.
- WATER**
- Refer to EAP for contractual requirements for control of construction impacts on water quality due to sediment disturbance and risk of reduced oxygen levels.
- TREES**
- Existing trees and scrub to be retained to be protected during construction in accordance with BS 5837:2012 and Tree Protection Plan.
- SOILS**
- Soils to be managed in accordance with the 'Construction Code of Practice for the Sustainable Use of Soils on Construction Sites' (DEFRA 2009) and Soil Management Plan (to be produced by the Contractor). Existing topsoil within all working areas to be stripped, stockpiled and protected during construction for re-spreading on completion of bank raising works.

Rev	Rev. Date	Purpose of revision	Drawn	Checked	Rev'd	Apprv'd
P03	20/05/2021	VALUE ENGINEERED FINAL ISSUE	SM	DTM	DTM	TW
P02	05/08/2020	FOLLOWING CLIENT REVIEW	DTM	ADL	ADL	TW
P01	11/05/2020	DRAFT	SM	ADL	ADL	TW

JACOBS
Aperture, Pynes Hill Court, Pynes Hill, Exeter EX2 5SP
Tel: +44 (0) 1392 269800
www.jacobs.com

Client: **Environment Agency**

Project: **RIVER SOWY AND KING'S SEDGEMOOR DRAIN ENHANCEMENTS SCHEME: PHASE 1**

Drawing title: **LANDSCAPE MASTERPLAN (LMP) TYPICAL DETAIL SOWY TWO-STAGE CHANNEL**

Drawing status: **A4**

Scale: 1:2000 **DO NOT SCALE**

Jacobs No. B2368000 Rev **P03**

Client no. ENVRES001353

Drawing number: **ENVRESW001353-CH2-XX-400-DR-EN-5437**

© Copyright 2021 Jacobs U.K. Limited. The concepts and information contained in this document are the property of Jacobs. Use or copying of this document in whole or in part without the written permission of Jacobs constitutes an infringement of copyright. Limitation: This drawing has been prepared on behalf of, and for the exclusive use of, Jacobs' Client, and is subject to, and issued in accordance with, the provisions of the contract between Jacobs and the Client. Jacobs accepts no liability or responsibility whatsoever for, or in respect of, any use of, or reliance upon, this drawing by any third party.